Bill of Quantities for: Proposed Supply & Installation of Split typ A. C. unit work for Modasa Branch & ATM, for UCO Bank, Ahmedabad Zone.

Sr. No.	Description	Qty.	Rate	Unit	Amount
1	1.50 ton SPLIT TYPE A.C. UNIT				
	Supplying & providing 1.50 TR split A. C. with high wall mounted unit 3 STAR				
	RATING with copper condenser & current year model for Manager cabin &				
	Banking Hall etc. completed as per direction.				
	(HITACHI/CARRIER/DAIKEN/BLUE STAR)	4		NO	
2	1.00 ton SPLIT TYPE A.C. UNIT				
	Supplying & providing 1.00 TR split A. C. with high wall mounted unit 3 STAR				
	RATING with copper condenser & current year model for Manager cabin &				
	Banking Hall etc. completed as per direction.				
	(HITACHI/CARRIER/DAIKEN/BLUE STAR)	2		NO	
	DEMOVING A DE EIVING EVICTING A C. LINIT				
3	REMOVING & RE-FIXING EXISTING A.C. UNIT				
	Removing & re-fixing of existing split A. C. indoor & outdoor unit with water				
	washing servicing, repairing, gas filling etc. completed as per new lay out plan as	0		NO	
	per direction.	U		INO	
	Installation charges for above 1.50 & 1.00 TR split A.C. including 3.0 RMT				
3	copper tubing per unit with proper insulation tape etc. complete as directed.	6		NO	
3		6		NO	
	Supplying & fixing Copper tubing with proper insulation & electrical cable for				
	outdoor unit for additional length after 3.0 RMT of standard length. (For				
	additional length above 3.00 RMT). This item also includes making zari in				
	wall/floor and filling the same with cement mortar and POP as per direction of				
4	Architect/ Bank.	50		RMT	
	Supplying & fixing 15/20mm dia. U-PVC drain pipe concealed in wall, floor with				
	necessary insulation etc This item also includes making zari in wall/floor and				
5	filling the same with cement mortar and POP as per direction of Architect/Bank.	60		RMT	
_	Providing & fixing powder coated L-shape stand for keeping out door unit of Split				
6	A. C. etc. complete.	6		NO	
	Fabricating & fixing M. S. platform/stand made from Angle, Patti etc. as per			1	
	design for keeping outdoor unit of split A. C. unit including cage for locking				
-	arrangement etc. complete as directed			NO	
7		6		NO	
	Filling the Gap/hole of wall for A. C. copper & drain piping by cement, brick etc.			+++	
8	with line & level etc. complete as per direction.	5		NO	
-	The state of the s	ა		INO	
	TOTAL OF AIR CONDITIONING WORK			Rs.	
				- 101	
	ADD FOR GST @ % ON RS. A.C. MACHINE		(+)	Rs.	
			. ,		
	ADD FOR GST @ % ON RS. LOW SIDE WORK		(+)	Rs.	
	· 		. ,	1 1	
	FINAL TOTAL OF AIR CONDITIONING WORK			Rs.	

Rupees

Name of Contractor with Seal & Signature

Date: Place:

Note: 1. Above rates includes all transportation charges etc..

2. Make: Hitachi, Daiken, Blue Star, Carrier

3. THE VENDOR SHOULD MENTION THE MAKE OF A. C. UNIT CLEARLY. THE A. C. UNIT WILL HAVE 3 STAR RATING INVERTER TYPE

The vendor will give warranty for one year (1) for the entire A. C. unit and further four (4) years warranty for the compressors of the A. C. units

Ar. Bimal Talati 1