

<u>Publishing of Corrigendum & Addendum to the Tender Document for Supply, Installation, Commissioning & Maintenance of Fire Hydrant, Sprinkler System & Fire Alarm System for Chennai Zonal Office Building.</u>

The Tender for <u>Supply, Installation, Commissioning & Maintenance of Fire Hydrant, Sprinkler System & Fire Alarm System for Chennai Zonal Office Building</u> was published on <u>05/02/2025</u>. The date of Pre-bid meeting was on 13/02/2025. Based on the queries/ suggestions received during the Pre-bid meeting, certain corrigendums and addendums is being published in Bank's Website as mentioned below:-

## Corrigendums to the Original Tender Document:-

<u>SI.</u>	<u>Page</u> <u>No.</u>	<u>Point /</u> <u>Section</u>	<u>Main</u> <u>Section</u> Name	Existing clause	Modification to the Clause.
01	18	4.2.4 Piping Installation	Part IV - Scope of Work	A) Tender drawings indicate schematically the size and location of pipes. The Contractor on the award of work, shall prepare detailed working drawings, showing the cross section, longitudinal sections, details of fittings, locations of isolating and control valves, drain and air valves, and all pipe supports. He must view the specific openings in buildings and other structures through which pipes are designed to pass.	section, longitudinal sections, details of fittings, locations of isolating and control valves, drain and air valves, and all pipe supports. He must view the specific openings in buildings and other structures through which
02	19	4.2.4 Piping Installation	Part IV - Scope of Work	F) Cut-outs in the floor slab for installing various pipers are indicated in the drawings. Modification of these cutouts/additional cutouts if required shall be included in the offer	installation of new hydrant lines (Wet riser) should be carried out as per

## Addendums to the Original Tender Document:-

<u>SI.</u>	<u>Page</u>	Point /	Main Section	Additional Point.
	<u>No</u>	<u>Section</u>	<u>Name</u>	
01	20	4.2.4	Part IV - Scope of	M) Underground Sump to be kept tidy and vacant
		Piping	Work	prior to the start of the work.
		Installation		
02	20	4.3 Pump	Part IV - Scope of	4.3.7. An area of 5X5 Sq.m. in front of the building
		Sets	Work	(on top of the underground sump) to be earmarked
				for the installation of pumpsets 'using specially
				made cushy foot mountings' to avoid any sort of
				damage to the existing sump.