

Subject: 'Corrigendum' in change of quantities in B.O.Q under head 'INTERNAL ELECTRICAL WORK_BOQ_2 BHK FLAT' against tender of RFP no. HO/GAD/1968/2024-25 dated 13-12-2024, pre-bid meeting dated 20-12-2024 for repairing & renovation work at Regent Tower, 121/1, N.S.C. Bose Road, Kolkata-700040. The repairing & renovation works includes Civil, Electrical and Furnishing interior works

A). Modifications of quantities in – B.O.Q under head 'INTERNAL ELECTRICAL WORK_BOQ_2 BHK FLAT' (Page:53 & 54 of RFP)

Sl. no	As specified in RFP	Existing quantities mentioned	Amendment quantities will be
1	Providing and Fixing Wiring for sub main wiring with the following size of PVC insulated, copper conductor, with insulated copper wire for loop earthing as required in surface/recessed PVC conduit as required: 3x2.5 sq.mm. in 20mm PVC conduit	152	60
2	Providing and Fixing Wiring for sub-main wiring with the following size of PVC insulated, copper conductor, with insulated copper wire for loop earthing as required in surface/recessed PVC conduit as required: 2x4 sq.mm. + 1x2.5 sq.mm. in 25mm PVC conduit	200	30
3	Providing and fixing 3 x 1.5 sq.mm. FRLS/ PVC insulated copper wire conductor along with PVC insulated/ bare copper wire for loop earthing as required in 20 mm dia. surface/ recessed PVC conduit with clamps saddles at every 1m distance and 5/6 A modular switch for a distance of 5 mtrs.	945	20
4	Providing and fixing 3 x 1.5 sq.mm. FRLS/ PVC insulated, copper conductor in surface/recessed PVC Conduit along with bare copper wire/PVC copper cable for loop earthing as required and 5/6 amp modular type switch and 5/6 amp socket upto 5 metre - with Metal Box	1300	20
5	Additional wiring of 3 x 1.5 sq.mm. FRLS/ PVC insulated copper wires along with PVC insulated/ bare copper wire for loop earthing as required to provide light point/ fan point/ exhaust fan/ call bell point through 20mm dia surface/ recessed PVC conduit (i.e. more than 5 mtrs.) with clamp saddles at every 1m distance as per above specification and without any fittings.	121	15
6	Providing and fixing 2 x 4.0 sq.mm. FRLS/ PVC insulated, copper conductor cable in 20 mm dia surface/ recessed PVC casing and capping along with 1 x 2.50 sq. mm PVC insulated/bare copper wire for loop earthing as required including providing and fixing 3 pin 16 A socket outlet and 16 A modular type switch upto 5 m, earthing the 3rd pin as required.	1705	8
7	Supplying & fixing Regulator switch type; single module	430	4
8	Supplying and fixing of Single phase motor starter 25 A Modular	577	2

यूको बैंक



UCO BANK

सम्मान आपके विश्वास का HONOURS YOUR TRUST

9	S/Fixing of Modular type MCB Distribution Boards with all mechanical fittings complete- 12 Way SPN	2670	1
10	Supplying and fixing 5 amps. to 16 amps. Rating, 240 volts, miniature circuit breaker of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required: Single pole	270	8
11	Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts, residual current circuit breaker (RCCB), having a sensitivity current upto 100 milli amperes in the existing MCB DB complete with connections, testing and commissioning etc. as required: 40 amps.	2930	1

Please note that other terms & conditions will remain same.

(Vikash Sharma)
Asstt. General Manager(GA)

