

## BOQ OF FURNISHING FOR UCO BANK, SABOUR BRANCH

A					
FURNISHING WORK					
S. No.	Description	Quantity	Unit	Rate (In Rs.)	Amount (In Rs.)
1	<p>a. Providing and fixing <b>GYPNUM BOARD FALSE CEILING</b> in levels as per the detailed drawing - made up of G.I frames as specified by Gypsum India limited and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200 mm c/c, and ceiling section at 457 mm c/c the work includes taping and jointing, applying primer, two or more coats of plastic emulsion paint of approved shade <u>ICI/ ASIAN PAINTS</u> make, making cut-out for light fixtures, etc. The Final coat shall be done with FOAM ROLLER, and no brush marks should be visible. Providing of perimeter channels/ beading etc. as per drawing complete in all respects.(All measurement in sq.ft. only) (<u>Suggested Make- SAINT GOBAIN / ARMSTRONG / GYPROCK</u>)</p>	345	SQFT		
1	<p>b. <b>GRID FALSE CEILING (BANKING HALL+ATM)</b></p>				
	<p>Providing and fixing of false ceilings at all heights of 600 mm x 600 mm x 16 mm <u>ARMSTRONG Mineral Fibre ceiling tiles</u> of type Prima Dune Premier-Beveled Tegular Edge RH-99 laid on Armstrong 15mm exposed grid system. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tee.</p>	875	SQFT		
2	<p><b>PARTITIONS</b></p>				
2	<p>a. <b>Low height Partition</b> Providing &amp; fixing of LOW HEIGHT PARTITION (HT. 4'-6") made of 2" x 2" or similar available size aluminium sectionn 1.5 mm at 2'0" c/c both ways 6mm BWP ply of <u>CENTURY /GREEN</u> Make on both faces finished with 1mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make of approved shade. Till the height of 3'-3" and 1'-3"(10mm thk.)glass on top complete with teak beading, The spirit polishing teak sections of approved shade as per drawing Complete in all respects to the complete satisfaction of the Architect.</p>	220	SQFT.		




b	<p><b>CASH CABIN PARTITION</b></p> <p>Providing &amp; fixing of CASH CABIN PARTITION (HT. 7'-6") (partly glazed (6mm glass) as per design), 2" x 2" or similar available size aluminium section 2'-0" c/c both ways 6mm MR grade Ply of <u>CENTURY/ GREEN</u> Make on both faces finished with 1mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make, shade as approved. The work includes providing a 6" x 9" voucher cut out with tray, spirit polishing of shade on woodwork and steam beach beading etc. Including doors but excluding cost of door closers mortise locks. Complete in all respects to the complete satisfaction of the Architect./Engineer.</p>	175	SQFT		
c	<p>Cash Cabin front Partition With 12 mm Glass including fixing. Complete in all respect. <u>Glass Make: Tata- Asahi/ Modifloat/ St. Gobain</u></p>	34	SQFT		
d	<p><b>Full height Non Glazed Partition</b></p> <p>Providing &amp; fixing of FULL HEIGHT PARTITION (HT. 10'-0") made 2" x 2" or similar available size aluminium section [1.5mm]2'0" c/c both ways 6mm BWP ply of CENTURY / GREEN Make on both faces finished with 1mm thick laminate of CENTURY/ AMULYA/ GREENLAM Make of approved shade and shade as approved minimum 10 mm thick glass (4'x3') with itching as required on glazed portion. The spirit polishing teak sections of approved shade as per drawing Complete in all respects to the complete satisfaction of the Architect. Including doors and accesories but excluding cost of door closure.</p>	245	SQFT		
e	<p><b><u>PARTLY GLAZED FULL HEIGHT WOODEN PARTITION WITH DOOR FOR MANAGER CHAMBER</u></b></p> <p>Supplying &amp; erecting full height door partly glazed wooden door for Manager Chamber as per drawing and conforming to the following specifications</p> <p><b>Basic Frame Work</b> - Well seasoned Malaysian hard wood section treated with two coats of wood preservatives 2 1/2" x 1 3/4" (minimum) at maximum 2'-0" horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored at floor &amp; ceiling level to ensure rigidity. Exposed frame members in the glazed portions shall be wider spacing (approx 6'-0") or as per instructions</p> <p>Exposed members shall be finished with 1 mm thick laminate sheet of same or combination shade over 12 mm BWR plywood facing including 4 x 6 mm grooves at location as per instructions</p> <p><b>Skin Membrane</b> - Opaque portion up to 3'-0" from floor level and from false ceiling from floor level with 2 x 6 mm thick BWR grade plywood on each face. With Groove formed at the top layer as per drawing/ instructions</p> <p><b>Finishing</b> - 6 mm thick clear float glass fixed with continuous steam beech wood glazing beads of approved shape (finished 0'-1 1/4" x 0'-1") all round polished and coated with NC lacquer finish. The rate should also include cost for decorative itching on one side of the glass</p> <p><b>Hardware</b> - Providing &amp; Fixing door closer &amp; mortise lock with 4" kabja &amp; other misc. hardware.</p>	275	SQFT		
(f)	<p>Knight latch for cash cabin door (<b>Make Godrej</b>)</p>	2	NO.		




(ii)	Hydraulic Door closer.( <b>Make Godrej/Universal</b> )	3	NO.		
(iii)	Mortise locks (with handles).(Make Godrej)	1	NO.		
(iv)	Floor springs for main Entrance Door+ATM.( <b>Make Godrej / Amar/Hardwn</b> )	1	NO.		
3	<b>ENTRANCE DOOR AND WINDOWS</b>				
a	<b>Main Entrance Door</b> 8'-0" x 6'-0"(All aluminium sections powder-coated).glass for doors: 12mm thick plain glass with etching of logo & Aluminium sections for door shutter :3 1/4"x 1 3/4" x 2mm thick & 18" SS handle, lock & Tower bolts etc. complete in all respects including powder coating. ( <b>Make: Hindalco / Jindal</b> )	48	SQFT		
b	<b>ATM Main Entrance Door</b> 8'-0" x 6'-6"(All aluminium sections powder-coated). Glass for doors: 6 mm thick glass with etching of logo & Aluminium sections for door shutter: Vertical member 83.5mm x 45mm x 2mm thick, Top and bottom member 85-100mm x 45mm x 2mm thick, Middle member Approx. 83.5mm to 100mm x 45mm x 2mm. 18" SS handle, Lock & Tower bolts etc. complete in all respects including powder coating. Rate should be inclusive of making arrangements for fixing entrance access lock with suitable aluminium box section adjoining the main door and Floor springs.for main entrance door.( <b>Make: Godrej, Universal, Sandhu</b> )	54	SQFT		
4	<b>COUNTERS AND TABLES</b>				
a	Providing and fixing <b>MANAGER'S TABLE</b> 6'0" x 3'-0" x 2'-6" and the total height of 2'-6" as per detailed drawing; made up of 19mm BWP board of <u>CENTURY/ GREEN</u> approved Make and finished with 1 mm thick laminate of make, and shade as approved, as per detailed drawing. (with 10mm thick glass on table top) Table shall be provided with drawers sliding on telescopic channels ( <u>Ebco/ Godrej make</u> ) and one cabinet with proper locking arrangements and keyboard with telescopic channels ( <u>Ebco/ Godrej make</u> ) . Tabletop shall be finished with 1.0mm thick laminate of approved shade & quality. The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, spirit polishing of steam beach/ white cedar beading etc. and all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above. complete in all respects to the entire satisfaction of the Architect/Bank.				
(i)	Table size: 6'-0" x3'0"x 2'-6" ( <b>Must be kept loose without fixing to the wall</b> )	1	NO.		
(ii)	Table size: 4'-6" x2'6"x 2'-6" (Must be kept loose without fixing to the wall)	5	NO.		




b	<b>SIDE CREDENZAS (Must be kept loose without fixing to the wall)</b> Providing and fixing SIDE CREDENZAS of size 2'-6" to 4'-6" x 1'-3" x 2'-6" made of 19mm BWP board <u>CENTURY/GREEN</u> finished with 1 mm thick laminate of approved Make and shade on top, sides and front having two drawers and cabinet below complete with all accessories like locks, handles etc. Teak wood beading on all exposed edges with spirit polish. all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above.	5	NO.		
	PRINTER TABLE				



c	<p><b>CASH COUNTER</b>          Providing and fixing of CASH COUNTER 3'-9" high made up of 19mm BWP board of <u>CENTURY/ GREEN</u> Make and finished with 1 mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make, shade as approved and as per detailed drawing. 2'-6' wide working table top, key board tray, drawer with telescopic channels (<u>Ebco/ Godrej make</u>)(TOP DRAWER SHOULD BE DIVIDED INTO SECTIONS SO AS TO PILE DIFFERENT CURRENCY NOTES SEPERATELY) and cupboard. All exposed surfaces (such as counter front, sides, drawers and cupboard etc) to be finished with 1mm thick laminate of approved make. Tabletop shall be finished with 1mm thick laminate. all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above. The work includes fixing of furniture locks, wire managers, spirit polish of steam beach wood beading/ lipping etc. complete in all respects to the entire satisfaction of Architect</p>	10	RFT	
d	<p><b>RUNNING STAFF TABLE</b>          Providing and fixing of COMPUTER work Stations as per layout plan, 2'-6" high working top ( As per drawing) made up of 19mm BWP board of <u>CENTURY/ GREEN</u> Make, finished with 1 mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make, shade as approved as per the detailed drawing . The tables shall have 2'-6" X 11'-0" table top as per approved shade and color as below mention dimension. <b>All exposed surfaces (such as counter front, sides, drawers and cupboard etc.) must be finished with 1mm thick laminate of approved make (with 10mm thick glass on table top with edge grinding and round corner). Tabletop shall be finished with 1mm thick laminate. all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above.</b> Each unit of table shall be provided with keyboard tray with telescopic channels(<u>EBCO/ GODREJ</u>). Tabletop shall be finished with 1.0mm laminate of approved shade &amp; quality. The work includes fixing of wire managers, locks, footrests, spirit polishing the steam beach beading, lipping, exposed frame, etc. as per drawings, and all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above . complete in all respects to the complete satisfaction of the Architect/Bank.</p>		RFT	
(i)	<p><b>PANTRY TABLE</b></p>			
5	<p><b>FULL HEIGHT STORAGE AT 10' HT.</b></p>			



a	<p><b>10'-0" HEIGHT STORAGE CABINETS[ BACK OFFICE AREA]</b>  Providing &amp; fixing STORAGE CABINETS of 10'-0" ht and 1'-4" deep as per layout plan made up of 19mm BWP board of <u>CENTURY/ GREEN</u> Make and finished with 1mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make, shade as approved and per detailed drawing. With 2-3 shelves made up of 19mm thick commercial board, all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above. The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc complete in all respects to the complete satisfaction of the Architect.</p>	325	SQFT		
	<b>LOW HEIGHT STORAGE AT 2'6" HT.</b>				
b	<p><b>2'-6" HEIGHT STORAGE CABINETS[ BACK OFFICE AREA]</b>  Providing &amp; fixing STORAGE CABINETS of 2'-6" ht and 1'-4" deep as per layout plan made up of 19mm BWP board of <u>CENTURY/ GREEN</u> Make and finished with 1mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make, shade as approved and per detailed drawing. With 2-3 shelves made up of 19mm thick commercial board, all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above. The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc complete in all respects to the complete satisfaction of the Architect.</p>	85	SQFT		
c	<p><b>VOUCHER STAND</b>  Providing and fixing VOUCHER STAND, excluding Clearing &amp; Suggestion Box, cheque drop box, writing top at 3'9" height . provide space for vouchers and 3'x2' soft board-as per specifications laid down in the detailed drawing and as per Bank specifications. all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above.</p>	1	NO.		
d	<p><b>COLUMN/WALL PANNELING (ONLY IN COLUMNS OF BANKING HALL)</b>  Providing and fixing of <del>COLUMN</del> <sup>WALL</sup> PANNELING (8'-6" Ht.) as per design, consisting of 6mm thick BWP ply <u>CENTURY/ GREEN</u> Make fixed on wall with 1.5 mm aluminum section . The above shall be laminated with 1mm thick mica <u>CENTURY/ MERINO/ GREENLAM</u> Make, work complete in all respects as per detailed drawings to the complete satisfaction of the Architect.</p>	1100	SQFT		
e	<p>Providing &amp; fixing <b>ELECTRICAL PANEL BOXING</b> of 8'-6" ht and depth as per size of the electrical panel, layout plan made up of 19mm BWP board of <u>CENTURY/ GREEN</u> Make and finished with 1mm thick laminate of <u>CENTURY/ AMULYA/ GREENLAM</u> Make, shade as approved all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above.r. A fix glass window should also be given to show the indicator LEDS of the panel inside. The work also includes supplying, fixing of hinges, magnetic catchers, handles, Steam Beach lipping, Ventilator Grill etc complete in all respects to the complete satisfaction of the Architect.</p>	0	NO.		



6		Providing & fixing rubber mat [2.5 mm thick ] in ups room	30	SQFT		
7		<b>vertical blinds</b> : Providing & fixing levelor 10mm vertical blinds having top rail 39mmX34mm hgh with wall thicknessof 1.2mm having 25mm decorative insert. Control unit shall be of Derlin. Plastic runner shall be moulded from Derlin plastic with artification head rail & the top end of the louver fabric shall be polyster viscose/polyster yarn dyed in fast colour with or without protective coating on louvers with chemical for stain resistance and soil repetancy and shall have GI weight and steel/polymer ball chain for spacing. The top rail should be fixed on bracket of 14 SWG galvanized spring steel fixed firmly on walls by nylon plug and screw as per approved design and direction of the Architect. (Makes - Vista, Universal ).	60	SQFT		
8	a	<b>(CHECK DROP BOX)</b> Providing and fixing one suggestion box, made with 12 mm ply as per standard design and specifications of the Bank, fully complete, lock, lettering on top, etc.	1	EACH		
	b	<b>(SUGGESTION BOX)</b> Providing and fixing one suggestion box, made with 12 mm ply as per standard design and specifications of the Bank, fully complete, lock, lettering on top, etc.	1	EACH		
	c	<b>(NOTICE BOARD)</b> Providing and fixing a notice board near the Waiting area, frame to be made of 1st quality hardwood, and infill of 12 mm thick 'Celotex, board, duly covered with "Matte" quality cloth of approved colour and make.The frame is to be securely fixed to the wall, all complete as per directions for the Architect / Employer. Size: 4'-6" x 3'-0".	1	EACH		
9		<b>(ALUMINIUM MESH ON TOP OF CASH CAGE)</b> Providing and fixing aluminium mesh cage on top of cash cage area, all complete with polished gambhar wood frame, duly supported at regular intervals to prevent sagging, all complete.	85	SQFT		
10		<b>RUNNING FRONT 12 MM THIK.GLASS</b> Providing and fixing 12MM THK. GLASS 2'0" HT. WITH ALL FITTING ON RUNNING OFFICE TABLE.	36	SQFT		
11		<b>ATM WALL PANELLING WITH ACP</b> (ALUMINIUM COMPOSITE PANEL):-Providing and fixing in position ACP panelling with Aluminium framing of aluminium tube sections of min. 1.5"x1" and 20 gauge @2'-0" c/c both ways.Acp to be in 2'-0" wide panels or distributed equally. The panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with silicon based sealent.ACP thickness of 3mm min. Aluminium foil thickness to be 0.20mm.ACP only on the ATM side with thickness of 3mm min, of approved shade and make, in plumb, line and level complete as directed) including front rolling shutter cover 1. ENTRANCE SHUTTER WITH ATM , TOTAL FRONT AREA COVER BOX WITH ACP	410	SQFT		
		Bank color approved logo (acrlic borad) back area in branch manager cabin with installation size- 3'x4'( as per drawing)	12	SQFT		



	Entrance (8'-0" x 8'-0")(All aluminium sections powder-coated).Fixed glass 12mm thick plain glass with logo & Aluminium sections for shutter :3 1/4"x 1 3/4" x 2mm thick Tower bolts etc. complete in all respects including powder coating. (Make: Jindal)	64	SQFT		
	<b>TOTAL</b>				
	<b>TOTAL [IN WORD]: + GST</b>				<b>GST</b>
	NOTE: Rates in the estimate are as per Prevailing Market Rates. Any removing and dismnanthling and disposal of scraps are included in the scope of the work. It may include minor civil dismantelling work too. Contractors are requested to visit site before quoting rates.				

