

ZO/AGT/GAD/2024-25/4336

Date: 06-02-2025



UCO Bank
Zonal Office
Agartala, Kamanchowmuhan
Central Road, Tripura- 799001
Phone-9862450644,8544736332
Email - zoagartala.gad@ucobank.co.in

RFP for Furnishing & Electrical works at Imphal Branch situated at 1st Floor, Imphal West District, Imphal, Manipur.

Part – I (Technical Bid)

The information provided by the bidders in response to this RFP Document will become the property of the Bank and will not be returned. The Bank reserves the right to amend, rescind or reissue this RFP Document and all amendments will be advised to the bidders and such amendments will be binding on them. The Bank also reserves its right to accept or reject any or all the responses to this RFP Document without assigning any reason whatsoever.

This document is prepared by UCO Bank for Interior Furnishing and electrical works at Imphal Branch situated at 1st Floor, Imphal West District, Manipur. It should not be reused or copied or used either partially or fully in any form.

INDEX

Sl.No.	Particulars	Page No.
1	Notice Inviting Tender	1-5
2	Eligibility Criteria & Evaluation Criteria	6
3	REJECTION OF BID	6
5	ANNEXURE-I(DECLARATION)	7
6	ANNEXURE-II (TECHNICAL SPECIFICATION)	8
7	FINANCIAL BID-BOQ	9-21

Disclaimer

While the document has been prepared in good faith, no representation or warranty, express or implied, is or will be made, and no responsibility or liability will be accepted by UCO BANK or any of its employees, in relation to the accuracy or completeness of this document and any liability thereof expressly disclaimed. The RFP is not an offer by UCO BANK, but an invitation for bidder's responses. No contractual obligation on behalf of UCO BANK, whatsoever, shall arise from the offer process unless and until a formal contract is signed and executed by duly authorized officials of UCO BANK and the selected Bidder.

Notice Inviting Tender

UCO Bank invites open tender for Renovation of Interior Furnishing and Electrical (Wiring, Fitting Accessories, Switch Gear, Land Cable Section) works at Imphal Branch situated at 1st Floor, Imphal West District, Imphal, Manipur.

- A)** The bidder (also called the vendor or bidder through this document) selected through this bidding process shall own the single point responsibility for fulfilling all obligations and providing all deliverables and services required for successful implementation of the project.

B) Salient Features

Tender Reference	ZO/AGT/GAD/2024-25/4336 dated 06.02.2025
Name of the work	Renovation of Interior Furnishing & Electrical works at Bank's Zonal Office situated at Imphal Branch situated at 1 st Floor, Imphal West District, Imphal, Manipur.
EMD	EMD: a) EMD of 1) Rs. 7,500/- for furnishing work 2) Rs.3,500/- for electrical works. DD must be submitted with Technical Bid (Part-I) in the form of pay order /demand draft in favour of UCO Bank, payable at Agartala. Not Applicable for MSME (Document related MSME to be furnished Under Part-I). b) EMD of unsuccessful bidders will be released (without any interest). c) EMD of L-1 bidders will be released (without any interest) after submission of Performance Bank Guarantee. d) However, if Successful tenderer withdraws their acceptance before completion of Work, UCO Bank will have the right to forfeit the Earnest Money Deposit without making reference.

Last date and time for submission of tender	Off line original hard copy of Part-I and Part-II of tender document to be submitted by 17-02-2025 upto 14:00 hrs at UCO Bank, GAD(General Administration Department), Agartala Zonal Office, Kaman Chowmuhani, Central Road , Tripura -799001
Date of opening of tender	Technical and financial bids to be opened on 18-02-2025 at 16:00 hrs.
Time for completion	30 Days from issue of work order
Address of communication	UCO Bank, Agartala Zonal Office General Administration Department Kaman chowmuhani, Central Road, Agartala, Tripura- 799001
Email	zoagartala.gad@ucobank.co.in
Phone No.	9862450644,8544736332
Architect for technical clarifications and drawings	M/s Rajeshor and Associates Contact - 9612154194
Mode of submission	Offline hard copy
Contents of technical bid (Part-1)	<ul style="list-style-type: none"> a. Original Demand Draft of EMD (Not Applicable for MSME (Document related MSME to be furnished). b. Bidder's Covering letter (Annexure 1) c. Empanelment Letter suitable, If any for the said category Issued by any of our Zonal office.
Validity of tender	90 (Ninety) days from date of opening

C) Submission of tender

The envelope containing Part-I of tender should be super scribed clearly " Part-I (Technical Bid)" with the name of work and will be addressed to 'The Zonal Manager, UCO Bank Agartala Zonal Office' and must be submitted on or before the stipulated date & time of submission of tender. The financial bid should be submitted in one big non window-envelope in the same envelope containing envelope of Technical Bid. The sealed envelope should be super-scribed as "Furnishing & Electrical works at Imphal Branch at **Imphal Branch at 1st Floor , Imphal West District, Imphal, Manipur.**

1. The documents should be submitted to UCO Bank, Agartala Zonal Office General Administration Department, Kaman chowmuhan, Central Road, Agartala, Tripura-799001 within stipulated time frame.

D) Miscellaneous items

1. Vendor's representatives will be allowed to be present during opening of bids at their cost.
2. In case date of pre-bid meeting, last date of receipt or opening of tender are declared as holiday, the respective date shall be treated as deferred and will be re-scheduled to next working day correspondingly.
3. It may be noted that the requirement given in this RFP is indicative only.
4. Tenders/offers through email will not be accepted.
5. Bank reserves the authority to accept or cancel any or all tenders without assigning any reason.
6. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect or there is any correction in Price Bid is not duly signed and dated by the bidder are liable to be rejected.

**Zonal Head
Agartala Zonal Office**

Eligibility Criteria

- i) The bidder must be a Firm/Company/Govt Dept having valid license issued by the Local Body, authorized to issue such certificate (Submit proof).
- ii) The bidder must be registered under GST (Submit proof).
- iii) The bidder should have PAN (Submit proof)
- iv) The bidder must have experience in executing the similar work as under at Public Sector Banks/RBI/Govt Organizations/PSU/Reputed Private Organization:
 - a. Three similar completed works each costing not less than the amount equal to 40% of the estimated cost within seven years ending last day of the month previous to the one in which applications are invited in execution of similar works.
 - or
 - b. Two similar completed works each costing not less than the amount equal to 50% of the estimated cost within seven years ending last day of the month previous to the one in which applications are invited in execution of similar works.
 - or
 - c. One similar completed work costing not less than the amount equal to 80% of the estimated cost within seven years ending last day of the month previous to the one in which applications are invited in execution of similar works .
- v) The contractor must apply only in that trade (furnishing & electrical Works) in which he has sufficient experience as per point no(IV) of eligibility criteria.

Note: Bidder must provide documental proof for point No. I to IV

Evaluation Criteria

Lowest Bid Value will be evaluated on lowest price offered by the bidder against Financial Bid.

Rejection of Bids

The bid is liable to be rejected summarily if:

- i) Tenders are not received in two parts in separate envelopes.
- ii) It is not in conformity with the instruction mentioned in this tender document.
- iii) If it is not accompanied by requisite tender cost and EMD as stated above.
- iv) It is received after expiry of the due date and /or time.
- v) It is evasive and contains incorrect information.
- vi) If there is canvassing of any kind.
- vii) It is submitted anywhere other than the tender box or to the addressee.
- viii) If any indication of price/rate/charges is being found in Part-I of the tender

ANNEXURE – I

To
Zonal Head
UCO Bank Zonal Office
Agartala

Sir

1. We have carefully examined all the contents incorporated in the various parts of this Tender Document no dated and taken note of all the terms & conditions stated in the Tender Document in its various parts.
2. We hereby agree to abide by and fulfil all other Terms and Conditions of the Tender.
3. We also agree to keep the retention money clause as mentioned in the tender document.
4. The integrity and letter of undertaking and indemnity submitted by us during empanelment in Bank's list of empaneled contractors shall be binding on me during the course of this work.

For and on behalf of

(With seal)
Signature _____
Name _____
Designation _____
DULY AUTHORIZED SIGNATORY

_____ day of _____ 2025

ANNEXURE-II
TECHNICAL SPECIFICATIONS
Approved Make

APPROVED MAKE OF MATERIALS		
1.	False Ceiling/Channels	India Gypsum/Armstrong/AMF/Saint Gobain
2.	Aluminium Framework/Aluminium Section	Jindal/Tata
3.	Wood Skirting/Moulding/Lipping/Beading	C P Teak
4.	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI / Bison by British Paint
5.	Fire Retardant Paint	Industrial grades of Nobel/Viper
6.	Marine Ply with ISI:710 Mark	IS:710 BWR Green/Century/Archid (Sub-brand is not accepted)
7.	BWP Block Board (IS:1659)	IS:710 BWR Green/Century/Archid (Sub-brand is not accepted)
8.	Laminate (1 mm thick)	Merino Lam / Green lam /Century mica / Sun mica
9.	Door Closure (Heavy Duty)	Ebco / Ozone / Dorma / Godrej
10.	Door Lock	Godrej/Ebco
11.	Door Handles	Godrej / Hafele /Hettich / Ebco
12.	Drawer/Storage Handle	Godrej / Hafele /Hettich / Ebco
13.	Drawer/Storage lock (Multipurpose)	Godrej / Hafele /Hettich / Ebco
14.	Night latch	Godrej
15.	Screws	GKF/Nettle Fold
16.	Hinges	CIEF
17.	Sliding telescopic drawer channel	Ebco / Kombo / Earl Behari / Efficient Gadgets
18.	Cable Organiser	Ebco/Innofitt Systems (CM 63C)
19.	Adhesive	Fevicol SH / Araldite
20.	Soft Board	Jolly Board
21.	Vertical/Roller Blinds	Mac / Vista / Wincab
22.	Glass	Modiguard /AIS / Saint Gobain
23.	Paints (Synthetic Enamel / Acrylic Emulsion)	Asian Paints / Berger / Dulux
24.	PVC Flooring	Krishna Vinyl / Armstrong / Birla
25.	Texture Paint	Asian Paints / Berger / Dulux
26.	G I Pipe	TATA(Medium)/Jindal Steel
27.	Cement	Ultratech/Ambuja/ACC
28.	Vitrified tiles	Johnson/Kajaria/Nitco/ASL
29.	Ceramic Tiles	Johnson/Kajaria/Nitco/ASL
30.	ACP	Alucobond/Alstone/Eurobond
31.	Veneer (4mm)	Century/Ply
32.	All materials not covered above	As per sample approved by Bank

BRANCH/ OFFICE- ZONAL OFFICE, EMAIL: ZO.AGARTALA@UCOBANK.CO.IN CONTACT:

FOLLOW UCO BANK ON TWITTER: [UCOBANKOFFICIAL](https://twitter.com/UCOBANKOFFICIAL); FACEBOOK: [OFFICIALUCOBANK](https://www.facebook.com/OFFICIALUCOBANK); INSTAGRAM: [OFFICIALUCOBANK](https://www.instagram.com/OFFICIALUCOBANK);

LinkedIn: [UCO BANK](https://www.linkedin.com/company/UCO BANK); You Tube: [UCO Bank Official](https://www.youtube.com/channel/UCO Bank Official)



UCO Bank
Zonal Office
Agartala Kaman Chowmuhani
Central Road Tripura-799001
Phone- 9862450644,8544736332
Email - zoagartala.gad@ucobank.co.in

RFP for Renovation of Interior Furnishing and Electrical works at Imphal Branch situated at 1st Floor, Imphal West District, Imphal Manipur .

Part – II (Financial Bid)

The information provided by the bidders in response to this RFP Document will become the property of the Bank and will not be returned. The Bank reserves the right to amend, rescind or reissue this RFP Document and all amendments will be advised to the bidders and such amendments will be binding on them. The Bank also reserves its right to accept or reject any or all the responses to this RFP Document without assigning any reason whatsoever. This document is prepared by UCO Bank for Renovation of Interior Furnishing and electrical works at 1st Floor, Imphal West District, Imphal Manipur. It should not be reused or copied or used either partially or fully in any form.

BOQ for Renovation of Interior furnishing works

S.NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	AMOUNT
A.	FURNISHING WORKS				
1	Full Height Partition	220.80	SQFT		
	Providing and fixing in position full ht. partition made out of G.I frame with C Channel stud with top, bottom & end channel being 50mm thick and intermediate channels 48mm thick with intermediate spacing of 600 mm centre to centre horizontally as well as vertically. Frame to be covered with 12mm MDF Board of approved make and finished with 1.00mm laminate of approved make & shade and complete with hardware , glue etc. of approved make complete as per drawing and as directed by Bank or its Architect. Framing of the partition to be erected upto Beam/slab bottom , however plywood & laminate to be pasted upto false ceiling height. Measurement will be upto false ceiling height only. If the GI frame is not available wooden frame of merandi/salwood to be used.				
2	Full Ht. Partly Glazed Partition	87.60	Sq.Ft		
	Providing and fixing in position full ht. partition made out of G.I frame with C Channel stud with top, bottom & end channel being 50mm thick and intermediate channels 48mm thick with intermediate spacing of 600 mm centre to centre horizontally as well as vertically. Partition to be provided with 12 mm Toughned Glass as per drawings. Frame to be covered with 6mm IS 303 MR Grade Plywood of approved make and finished with 1.00mm laminate on both sides of approved make & shade and complete with hardware , glue etc. of approved make complete as per drawing and as directed by Bank or its Architect. Framing of the partition to be erected upto Beam/slab bottom , however plywood & laminate to be pasted upto false ceiling height. Measurement will be upto false ceiling height only. If the GI frame is not available wooden frame of merandi/salwood to be used.				

3	Fully glazed Toughened Glass Single & Double Door: Providing and fixing in position fully glazed single leaf toughened glass door made out of 12mm thk. clear toughened glass. The door shall be provided with heavy guage patch fittings, floor spring, s.s. handle, special lock etc. of approved make as per the requirement. The SS Handle to be of 22mm dia and 300mm high. Work to be completed as per drawing and as directed by the Bank or its Architect.	38.50	Sq.Ft		
4	Flush Door	51.10	Sq.Ft		
	Providing and fixing in position single leaf flush door made out of 35mm thick IS 1659:1990 BWR grade Block Board of approved make with 1.0mm thick laminate of approved make & shade on both sides T.W lipping on edges polished, approved heavy brass hinges, handles, tubular lock, latches, door closer etc. approved make complete as directed. Work to be completed as per drawing and as directed by the Bank or its Architect.				
	Storage Unit	71.75	Sq.Ft		
5	Providing in position Full Height storage with top & sides made out of 19mm IS 303 MR grade plywood, Shelves & shutters made out of 16mm IS 303 Mr grade plywood, and rear/back made of 6mm Is 303 Mr Plywood all plywood to be used of approved make. Storages to be finished in 1.0mm thick laminate externally of approved make & shade and internal surfaces to be finished with approved shade of 3 coats of enamel paint. Edges to be foinished with Edges banding tape complete with all hardware including handles, hinges, lock , etc. of approved make complete as per drawing and as directed by Bank or is Architect.				
	Low Height Partition	189.30	Sq.Ft		
6	Providing and fixing in position low ht. partition made out of G.I frame with C Channel stud with top, bottom & end channel being 50mm thick and intermediate channels 48mm thick with intermediate spacing of 600 mm centre to centre horizontally as well as vertically. Frame to be covered with 12mm MDF Board of approved				

	make and finished with 1.00mm laminate of approved make & shade and complete with hardware , glue etc. of approved make complete as per drawing and as directed by Bank or its Architect. Framing of the partition to be erected upto Beam/slab bottom , however plywood & laminate to be pasted upto false ceiling height. Measurement will be upto false ceiling height only. If the GI frame is not available wooden frame of merandi/salwood to be used.				
7	Counter for Cashier	6.20	Sq.Ft		
	Providing and fixing cashier counter as per drawing with solid partition on three sides 2440 mm high. Partition made with GI frame with C Channel stud with top, bottom & end channel being 50mm thick and intermediate channels 48mm thick with intermediate spacing of 600 mm centre to centre horizontally as well as vertically. Frame to be covered with 6mm IS 303 MR Grade Plywood of approved make and finished with 1.00mm laminate of approved make & shade. Front side side of the counter have solid partition upto 1370mm high and solid 8mm thick toughened glass above it till total height of 2440 mm with a cut out made for cash exchange. A customer counter top of 200 mm wide at height of 1370 mm made out of 12mm thick IS 303 MR grade plywood of approved make and finished with 1.00 mm thick laminate of approved shade of enamel paint on inner surfaces. Edges to be finished with Edge banding tape. Table to be provided with keyboard tray, CPU trolley, wire manager. Counter to be covered with aluminium jali on top. Counter to be completed with necessary hardware, glue etc. of approved make complete as per drawing and as directed by Bank or its Architect. Door and cash deposit to be paid extra.				
8	Branch Manager Table	1.00	Sq.Ft		
	Branch Manager (1830 x 910 x 750 mm Ht): Providing in position manager table as per the drawings made out of 19mm thick IS 303 MR grade plywood of approved make for top sides &				

	Fron Apron. Table Top & sides exposed surfaces to be finished with 1 metal Keyboard tray. The edges to be finished with PVC Edge Banding tape. Table to be provided with one three unit Drawer made out of 12mm thick IS 303 MR grade plywood of approved make with necessary lock, drawer channel & other hardware of approved make, drawer to be externally finished with 1.0mm thk. Laminate of approved make & shade and internal surfaces finished with 3 coats of enamel paint of approved shade and complete as per drawing and as directed by Bank or its Architect.				
	Officer Table	4.00	Sq.Ft		
9	Office Table (1520 x 750 x 750 mm Ht): Providing in position manager table as per the drawings made out of 19mm thick IS 303 MR grade plywood of approved make for top sides & Front Apron. Table Top & sides exposed surfaces to be finished with 1 mm laminate of approved make & shade and internal surfaces finished with 3 coats of enamel paint. Table to be provided with a metal keyboard tray. The edges to be finished with PVC Edge Banding tape. Table to be provided with one three unit Drawer made out of 12mm thick IS 303 MR grade plywood of approved make with necessary lock, drawer channel & other hardware of approved make, drawer to be externally finished with 1.0mm thk. Laminate of approved make & shade and internal surfaces finished with 3 coats of enamel paint of approved shade and complete as per drawing and as directed by Bank or its Architect.				
10	Office Table (1220x750x750 mm Ht): Providing in position manager table as per the drawings made out of 19mm thick IS 303 MR grade plywood of approved make for top sides & Front Apron. Table Top & sides exposed surfaces to be finished with 1 mm laminate of approved make & shade and internal surfaces finished with 3 coats of enamel paint. Table to be provided with a metal keyboard tray. The edges to be finished with PVC Edge Banding tape. Table to be	5.00	Sq.Ft		

	provided with one three unit Drawer made out of 12mm thick IS 303 MR grade plywood of approved make with necessary lock, drawer channel & other hardware of approved make, drawer to be externally finished with 1.0mm thk. Laminate of approved make & shade and internal surfaces finished with 3 coats of enamel paint of approved shade and complete as per drawing and as directed by Bank or its Architect.				
	Side Table Cum Storage	3.00	Sq.Ft		
11	Side table cum storage (1060x450x750mm):- Providing in position side table cum storage as per the drawings with Top, Bottom and sides made out of 19mm IS 3030 MR grade plywood of approved make. Mid level shelf & shutters made out of 12mm IS 303 MR plywood of approved make and Back of table cum storage made of 8mm IS 303 MR grade plywood of approved make including all necessary hardware, glue etc as per approved make. External surfaces to be finished with 1mm laminate of approved make & shade and internal surfaces to be finished with 3 coats of enamel paint of approved shade. Edges of the table cum storage to be finished with Edge banding tape. Work to be completed as per drawing and as directed by Bank or its Architect.				
	Writing Desk	1.00	Sq.Ft		
12	Writing desk: Providing fixing in position writing desk, made out of 19mm thk. IS 303 MR grade plywood of approved make finished with 1.0 mm thk laminate of approve make & shade tw lipping on edge French polish etc. as per shape and 6mm thk. vertical glass support with machine polished edges etc. complete as directed by the Bank or its Architect.				
	Suggestion Box & Cheque Drop Box	1.00	Sq.Ft		
13	Providing & fixing Suggestion box of size (450mm x 150mm x 300mm) made out of 12mm block board finished with 1mm laminate and openable shutter with locking arrangement.				
	False Ceiling Work				

	Gypsum False Ceiling	499.20	Sq.Ft		
14	<p>Gypsum False Ceiling:- Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets from M.S. sheets and galvanized with zinc coating of 120 gsm/sqm (both side inclusive) as per IS:277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 27mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9mm running at the spacing of 1200 mm centre to centre to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26 mm each having lips of 10.5mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre with 25mm long dry wall screws @ 230mm, interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dray wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut-outs made with frame of perimeter channels suitable fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum plain board</p>				

	conforming to IS: 2095-(Part I): 2011 (Board with BIS certification marks)				
	Modular False Ceiling	1167.99	Sq.Ft		
15	<p>Modular False Ceiling :- Providing and fixing 15mm thick densified regular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dopped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main T runner suitably spaced at joints to get required length and of size 24x28mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main T at 600mm centre to centre to form a grid of 1200x600mm and secondary croos T of length 600mm and size 24x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x600 mm panel to from grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle precoated steel of size (24x24x300 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calcium silicate ceiling tiles of approved texture in the grid, including cutting / making opneing for services like diffusers, grills, light fiitings, fixtures, smoke detectors etc. wherever required.</p> <p>Main T runners to be suspended from ceiling using G.I slotted cleats od size 25x35x1.6 mm fixed 85x30x0.8 mm spaced at 1200 mm centre to centre along main T, bottom exposed with 24 mm of all T sections shall be pre-painted with polyster baked paint, for all heights , as per specifications, drawings and as directed by Engineer-in-Charge.</p>				
	Total				
	Discount if any				
	Total After Discount				
	GST amount will be Extra				

	Total Amount In word:	
Sl. No.	Materials	Approved manufacturers / suppliers
1	Paint	I.C.I. (Dulex - Duco) / Asian paints / Goodlac Nerolac
2	Plywood	BWR- Century/Green/Archid only Premium quality
3	Wood preservative	BWR- Century/Green/Archid only Premium quality
4	False ceiling	Armstrong , Indian gypsum board
5	Laminates	Sunmica/ Archid/Century/Green 1mm thick as per bank approved color
6	Screws	G.K.W./Nettle fold
7	Adhesive	Fevicol SH
8	Night latch	Godrej
9	Locks	Godrej
10	Aluminium door frame	Jindal
11	Glass	Modi/Asahi/Saint Gobain
12	Aluminium cladding	Eurobond/Altobond/Alukbond
13	Key board drawer	EBCO
14	Telescopic CPU stand	EBCO
15	Cable organiser (wire manager)	EBCO
16	Vitrified tiles	Jhonsions Perlto
17	Venetion blind	Vista, Luxaflex

Note : Plywood mentioned in the drawings as well as in bill of quantities should be IS: 710
BWR- Century/Green only Premium quality.

(Signature of bidder with seal) _____

Name _____

Designation _____

Note: The Bank reserves the right, neither to execute all items of work nor to execute the full quantity of items, as mentioned in schedule of quantities.

BOQ of electrical work

S. NO.	PARTICULARS/ Items of work	Qty.	Unit	Rate	Amount
A	Wiring				
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5mm ² FR PVC insulated copper conductor single core cable in PVC casing & capping with modular type switch ,modular plate,suitable size G.I. box and earthing the point with 1.5mm ² FR PVC insulated copper conductor single core cable etc. as reqd. Group A Group B Group C	10 nos. 8 nos. 8 nos.	Pt. Pt. Pt.		
2	Wiring for light point / power plug with 2x4mm ² PVC insulated copper conductor single core cable in PVC casing & capping along with 1 no. 4mm ² FR PVC insulated copper conductor single core cable for loop earthing etc. as reqd. a) Light Plug point b) Power Plug Point	15 nos. 11 nos.			
3	S/F suitable size GI box with modular plate on surface or in recess with suitable size of cover in front on surface /recess i/c P/F 3 pin 5/6 amp socket outlet and 5/6 amp modular switch, connection painting etc. as reqd. (for light plugs to use in non-residential building).	15 Nos.	Each		
4	S/F suitable size GI box with modular plate on surface or in recess with suitable size of cover in front on surface /recess i/c P/F 3 pin 15/16 amp socket outlet and 15/16 amp modular switch, connection painting etc. as reqd. (for light plugs to use in non-residential building).	11 Nos.	Each		

5	Wiring for circuit / sub-main wiring along with earth wire with (the following sizes of) FR PVC insulated copper conductor single core cable in cassing & capping etc. as reqd. a) 2x2 5mm ² + 1x25mm ² earth wire b) 2x6mm ² + 1x6mm ² earth wire c) 2x10mm ² + 1x10mm ² earth wire	40 mtr 30 mtr 30 mtr	mtr		
B	Fitting Accessories				
6	S/F 2X2 RR LED 36WAT SQ 6500K Lighting i/c connection as reqd.	13 nos.	each		
7	S/F 12W surface mounting LED down light with white powder coated aluminium housing with integrated electronic driver i/c connection as reqd.	12 nos.	each		
8	S/F bell buzzer / ding dong bell (Ding Dong Electronic) and bell push including connection etc as reqd.	1 no.	each		
C.	Switch Gear				
9	P/F 100 amp TP & N dis-connector fuse switch unit inside the existing cubicle panel board with ISI marks HRC fuses including drilling holes in the cubicle panel board, making connection as reqd.	1 no	each		
10	P/F 125 amp TPN stand ground on load change over switch (compact design) 415/500V including connection etc. as reqd.	1 no.	each		
11	S/F bus bar chamber with 4 strips copper bus bar of length 300mm suitable for 100 amp capacity complete with all accessories i/c connection earthing the body etc. as reqd.	1 no	each		
12	S/F 6 way, (4+18 way) double door, TPN prewired, sheet steel MCB distributon board, 240 volts, on surface/recess, complete with loose wire box, terminal blocks, tinned copper busbar, neutral link, earth bar, din bar, detachable gland plate, interconnections, phosphatized powder painted including earthing etc. as required. (but without MCB/RCCB/Isolator).	2 nos.	each		

13	S/F 100 amp, four pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.	2 nos	each		
14	S/F 5 amp. To 32 amp. Rating 230V 'B' series MCB for lighting and other load of (following poles) in the existing MCB DB complete with connection testing and commissioning etc. as reqd.	32 nos.	each		
D	Land Cable section				
15	TP-Link LT-SG3428 Jet Stream 24 port Gigabit L2 managed switch	1 nos	each		
16	Anchor Roma RJ 45 Computer socket Cat 6 white	24 nos.	each		
17	D-Link 305 mtr Cat 6 LAN Cable Grey	1 Roll	Roll		
18	Rapink patch panel 24 port cat 6 with inline keystone 10G support, rapink pass through coupler patch panel Uts 19 inch with removable back bar, 1U network patch panel for cat 6, cat 5E/cat 5 cabling, RJ45, Gold.	1 no	each		
19	CP PLUS wall mount Rack 9U CP-PA-RK5563-9U.	1 no	each		
20	BCH BIL-S-062409 Server rack 24Ux600x900.	1 no	each		
	Total For Electrical works				
	Discount If Any				
	Total After Discount				
	GST Amount will be Extra				
	Total Amount In word				
	List of approved materials				
	Materials	Approved manufacturers/suppliers			
1	MCCB	MDS legrands, ABB, GE, SIEMENS			
2	Changeover	Indo Asian/ HPL Socomec / GE/ Standard stangaurd			

3	Distribution board	MDS / Standard / Indo Asian / HPL
4	MCB	MDS / Standard / Indo Asian / HPL
5	Cable	Gloster / Rallison / Incab / CCI
6	Copper wire	Finolex/anchor
7	Switch / Socket / Call bell and accessories	Anchor / Havells / CPL / MDS / Philips
8	Electrical Light Fittings / Fixtures Complete	Philips
9	Wall Fan / Ceiling Fan / Exhaust Fan	Khaitan/Havells
GST Will Be Extra		

(Signature of bidder with seal) _____

Name _____

Designation _____

Note: The Bank reserves the right, neither to execute all items of work nor to execute the full quantity of items, as mentioned in schedule of quantities.