

अंकवाZOV/यों एवं विP&D/2016-17/ 118

दिनांक/Date : 19.12.2016

निविदा सूचना/TENDER NOTICE

निविदिष्ट के अनुसार वस्तुओं के दर हेतु मुहरबंद निविदाये आमंत्रित हैं/ Sealed items rate tenders are invited for the works noted hereunder :

क्र. स. /S.N	कार्य का विवरण/Name of work	कार्य-स्थल/Location of work	अनुमानित लागत/Estimated Cost
1	शाखा बालापुर, जनपद इलाहाबाद में आंतरिक साज-सज्जा का कार्य/ interior & furniture work at Balapur branch Distt Allahabad	शाखा बालापुर, जनपद इलाहाबाद Balapur branch Distt Allahabad	Rs 2,52,000/-
2	शाखा बालापुर, जनपद इलाहाबाद में विदुअत कार्य/ Electrical work at Balapur branch Distt Allahabad	शाखा बालापुर, जनपद इलाहाबाद /Balapur branch Distt Allahabad	Rs 1,18,000/-

निबंधन एवं शर्तें/ Terms and Conditions :

- कार्य की पूर्ति हेतु समय : 30 दिन / Time of completion of work : 30 days.
- अर्नेस्ट मनी डिपॉजिट : निविदा जमा करने के समय पे आईर/ डी डी / बैंकर्स चेक के रूप में अनुमानित लागत का 1% / Earnest Money Deposit : 1% of estimated value at the time of submission of tender in the form of pay order/DD/Banker's cheque.
- आरंभिक अभिरक्षा जमाराशि : सफल बोली लगाने वाले की अर्नेस्ट डिपॉजिट मनी को शामिल करते हुए अनुबंधित राशी का 2% / initial security deposit : 2% of the contract value including the EMD by successful bidder.
- सफल बोली लगाने वाले के द्वारा अर्नेस्ट मनी डिपॉजिट एवं आरंभिक अभिरक्षा जमा राशी, अनुबंध की अभिरक्षा राशी व रिटेंशन मनी के एवज में समायोजित कर ली जाएगी / The EMD and ISD so deposited by the successful bidder, will be adjusted with the security deposit/ retention money for the contract.
- क्षतिपूर्ति वहन अवधि : कार्य के वास्तविक समापन से छः माह की अवधि तक / Defects liability period : 6 months from date of virtual completion of work.
- निविदा के जमा करने का अंतिम समय एवं तिथि : 28.12.2016 को अपराह्न 2.00 बजे/ Time and last date of submission of tenders : 2:00PM on 28.12.2016.
- निविदा खोलने का अंतिम समय एवं तिथि : 28.12.2016 अपराह्न 4:00 बजे/ Time and last date of opening the tenders : 4:00PM on 28.12.2016.
- जमा करने का स्थान / Place of submission :
यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010
UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi - 221010
- बिना कोई कारण बताये किसी व सभी निविदाओं को स्थगित करने व निरस्त करने का अपना अधिकार बैंक के पास सुरक्षित है। सभी निविदाये, जिसमें निर्दिष्ट कोई शर्त पूरी नहीं है या किसी भी रूप में अपूर्ण है, निरास्त की जा सकती है। Bank reserves its right to postpone/ reject any or all the tenders without assigning any reason what so ever. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- सेवा कर नियमानुसार लगे होगा / Service tax applicable as per norms.
- केवल सूचीबद्ध कॉन्ट्रैक्टर्स ही निविदा प्रस्तुत करें / Only empaneled contractors can submit tenders.

अंचल प्रबंधक / Zonal Manager

यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010
UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi - 221010

Phone: 0542-2221723, 2223323, Fax - 0542- 2223123

e-mail: zo.varanasi@ucobank.co.in

Detailed Estimate/Schedule Of Quantity of Electrical work of UCO BANK BALAPUR BRANCH.

Sl. No.	Item's of Work	Qty.	Unit.	Rate.	Amount (Rs.)
1.	Providing & fixing tube light fitting with tube, frame, choke, starter etc. A) Surface fitting G.E or Philips (Catalogue No. TCS 605- 2xTL-36watt-2PL-D36watt Lamp) Including hanging M.S Rod Wall Socket Testing Etc.)	8.0	No.		
2.	Making point wiring for light & fan by 2x1.5Sqmm + 1x 1Sqmm FR PVC Multi standard wire in suitable PVC conduit.				
a	Single point controlled by single switch.	22.0	No.		
b	plug point on switch board	4.0	No.		
3.	Supply and fixing 15Amp switch and socket along with MS board, cover plate, etc.	3.0	No.		
4.	Supply and fixing 5 Amp switch and socket along with MS board, cover plate, etc	7.0	No.		
5.	Wiring point for computer 5 Amp switch 3 Nos and 5 Amp socket 3 Nos along with 3x1.5 Sqmm multi standard wire in suitable size PVC conduit complete all in all respect. Each point MCB controlled.	7.0	No.		
6.	Supply and fixing Ceiling fan including Fan Regulator testing as per drawing. Make-Crompton & Anchor	5.0	No.		
7.	Supply and fixing cabin fan/ Wall Fan for cash counter.	4.0	No.		
8.	a) Supply and fixing 12 way double door MCB DB with 63 Amp DP MCB and 10 Nos SP MCB for light / fan	2.0	No.		
	b) Same as above but 8 way for UPS	2.0	No.		

9.	Wiring point for Telephone/Fax /Intercom with 1 st swin single core copper wire placed According to drawing with complete fitting with top & socket placed according to Drawing.	1.0	No.		
10.	Supply and lying PVC sheathed & pvc insulated armoured Al cable 50 Sqmm x 3.5 core along with 1 No 8 SWG GI wire on wall / ceiling by saddle at suitable interval termination of cable at both end by proper socket main pole to BO electrical panel.	N/A	Rmt.		
11.	Same as above but 10 Sqmm x 4 core for DG Set.	N/A	Rmt.		
12.	a) Supply and lying 2x 6 Sqmm + 1x1.5mm multi standard wire in suitable size PVC conduit for AC & UPS.	10.0	Rmt.		
	b) Same as above but 2 x 2.5 Sqmm + 1 x 1Sqmm for light / fan.	18.0	Rmt.		
	c) Same as above but 3 x 1.5 Sqmm for fire alarm system.	15.0	Rmt.		
	d) Same as above but 2 x4Sqmm for copper earthing (earth station to UPS room).	12.0	Rmt.		
13.	Earthing 600x600x3mm copper plate earthing stations with earthing resistanc less than 2 Ohm including watering, PVC/G.I. Pipe with funnel, excavation till 8'-0" deep or as instructed by the Architect , back filling with compaction, 2Nos. copper flats 25mm x 3mm conn. Earthing copper wire in PVC conduit pipe from Earthing pit to UPS.	N/A			
14.	Same as above but 600 x 600 x 6mm GI plate with 8 SWG GI wire earth station to main panal.	N/A			
15.	A – Supplying and drawing lan cable cat - 6 d-link or eqv make by 19mm pvc pipe fully concealed.	80.0	Rmt		
16.	B- termination of lan cable in one end with RJ 45 computer jack of MK,Roma or Crab- tree make in suitable enclosures.	7.0	No.		
17.	C- termination of land cable in other end with RJ 45 socket.	7.0	No.		
18.	. Supply & fixing 100Amp TPN main switch havells/ L & T make.	1.0	No.		
19.	Supply and fixing Electronic patty type fitting along with 36Watt tube.	6.0	No.		

20.	Supply & fixing Change over 63Amp 4 pole SFU side handle type along with angle iron nut bolt with suitable size connection wire, LUGS extra Havells/ L & T make.	1.0	No.		
21.	Supply & fixing 63Amp copper Bus Bar TPN (factory made)	1.0	No.		
22.	S/F 100 Amp cutout for main panel.	3.0	No.		
23.	Supply and fixing of Exhaust Fan 300mm heavy duty make Crompton.	1.0	No.		
24.	Supply and fixing 32Amp Changeover 2pole	1.0	No.		
25.	Supply and fixing CFL 23Watt	2.0	No.		
26.	Call bell point with call bell in Manager Cabin	1.0	No.		
			Total Rs.		

SPECIFICATIONS OF ELECTRICAL MATERIALS

<i>S.No.</i>	<i>Item</i>	<i>Make/ Specifications</i>
1.	FITTING	Philips & GE
2.	WIRE	Anchor, Havells, Finolex
3.	SWITCHES	Roma, M.K., Crabe Tee-Havells
4.	MCCB	Havells , L&T
5.	MCB DB	Havells, L&T
6.	Main Switch	HPL, L&T,
7.	Changeover	Havells , L&T,
8.	PVC Pipe	AKG, Plaza. 2mm thick
9.	Wall Fan	Crompton, Havells
10.	Ceiling Fan	Crompton, Havells
11.	Exhaust fan	Usha; Khaitan, Crompton.
12.	Cable	Gloster, Havells, National, Railisons.
13.	Telephone Wire	Delton, Anchor.
14.	Cat- 6 Cable	D - Link
15.	IO - Box	D - Link
16.	MCB	Havells, L&T
17.	CFL	Philips (Only)
18.	MS Pipe	AKG, MK,

Ref No.: BA/43/4242/2016-17

Dated :10-12-2016

Estimate of Furnishing of Uco Bank Of Balapur Branch.

Sl.no	Description of items	Unit	Qty.	Rate	Amount
1.0	P & F Bank Low ht. Counter 2'-6" wide made out of 19mm thick board with drawer unit and open able shutter in two part and front side 12mm thick Etching Glass Supported with Teak wood or Aluminium member with 1.5 mm thick laminate on the top & Front others internal surface to be painted /Polished with with key board sliding drawer On Roller and all edges teak wood beeding, Lipping / moulded. Complete work as per Bank Modular Design of Low Ht. Counter or Architect Satisfaction.	RFT	N.A.		
2.0	P/F of Bank Cash counter in two level cash counter 5'-0" long (with 3'-10" and 2'-6" height) counter for customer to be 1'-6" wide and counter to be 3'-0" wide with drawer unit made out of 19mm thick board with 1.5 mm thick laminate on top and front and other internal surface to be painted/polished Complete work as per Bank Modular Design of Cash Counter All specification as per item no.1	RFT	N.A.		
3.0	P/F of Cash cabin partition front-over the counter supported on 2"x1-1/2" sal wood frame work cover with 8.0 mm thk. Ply with 10mm Etching glass supported of 1"x 1/2" beading with book window in size 5"x6" center of the counter with 2"x2" spacing Aluminium grill will be fixed in front of partition Side partition supported 2"x1-1/2" sal wood well seasoned structure with a cost of antitermite treatment upto 3'-0" height				

	<p>framing of inside area with 2"x1-1/2" sal wood section 2'-0"c/c horizontal and vertical with bothside 6mm thick ply&1.5mm thick laminates both side.The upper portion upto 4'-0" height shall be of 2-1/2"x2"x2-1/2" Aluminum grill will be fixed complete with all accessories and labour.</p> <p>complete work as per Bank Modular Design of Cash Cabin Partition.</p>	SFT	N.A.		
4.0	<p>P/F Low height wooden Manager Cabin partly glazed/laminated wooden partition made out of Sal wood well seasonedstructure with a cost of antitermite treatment upto3'-0" ht.framing of inside area with 2"x 2"sal wood section 2'-0"c/c horizontal and vertical both side 6mm thk ply & 1.0mm thick laminates both side.& middle portion 8mm thk.Etching glass with teak wood beeding,liping/ moulded complete in all respect.</p>	SFT	170.00		
5.0	<p>P/F Low height partition/Wicket gate all specification as item No.4 .</p>	SFT	160.00		
6.0	<p>Providing and fixing in position double leaf powder coated Aluminum entrance door made of 14 gauge thick sheet. All member shall be of 4"x1-3/4"section and bottom rail shall be of 5"x1-3/4"section with 6mm thick clear sheet glass including 4"dia 2 Nos handles 10"long 2 Nos,Tower bolts, floor spring 2 Nos lock etc. complete.</p>	SFT	100.00		
7.0	<p>Providing and fixing Writing desk in position box type Wooden writing in public space of approximate size 4'-0" x 2'-0" made out of 19mm thick good approved quality ply with 6" to 9" wide wide pigeon hole type compartments in the front facade boxing for keeping pay-in-ship, book literature etc. These Writing table's must have laminates 1.0 mm thick on top writing desk and two sides of the Boxes. With beeding, lipping, moulding and painting /polishing complete.</p>	No.	1.00		

8.0	Providing and fixing in position Notice boards of approximate size 3'-0"x2'-0" and 6" deep made out of 19mm thick ply with fully glazed shutter in front and soft board with felt cloth lining at the back inclusive of good approved quality lock to this shutter, hinges, fixtures, handle etc. and front laminate /painted complete as directed by bank architect.	No.	1.00		
9.0	Providing and fixing of Check Drop box size 1'-3" x 1'-6" with all specification as per item no.17.	No.	1.00		
10.0	P/F of Godrej mortice lock	No.	2.00		
11.0	P/F of Godrej Night latch	No.	2.00		
12.0	P/F of Door closer I.S.I mark	No.	2.00		
13.0	Providing and fixing Column/Wall paneling paneling all specification as per item no.4.	SFT	110.00		
14.0	Providing & fixing wooden Filling Cabinet 1'-6" deep to be fixed on the wall frame made out of 19mm thick commercial ply with siding hinge shutters made out of 19mm thick ply with 1.0mm laminate on the front & side other internal surface to be painted as complete with handle, lock, Magnet etc.	SFT	60.00		
15.0	Providing and placing in position Side Units made out of 19mm board with 1.0mm laminate with sliding hinged shutters (made out of 19mm thick ply with 1.0mm thick laminate on it) complete with handle, lock, Magnet etc. size 4'-0"x1'-6"x2'-6"	No.	1.00		
16.0	Providing and placing in position Branch Manager Table made out of 19mm th. Board with 1.0mm Thick laminate on top sides and front (other surface Shall be polished or painted with teak wood beading on edges. Drawer unit T.W. lipping etc. also including multi purpose Godrej locks, wooden handles, foot rest, ball catchers etc. complete all as/ design(size 5'-6"x3'-3"x2'-6")	No.	N/A		

[illegible]

Specifications of Materials

S.No.		Make/ Specifications
1	Item	Green, Century, Archid 100% boiling water proof, 100% Termite proof
2	Ply board	Greenlam, Century Mica, Archid Lam, Marino
3	Laminate (Plane colour)	Fevicol- SH
4	Adhesive	Jindal, indal, Hindalco
5	Aluminium section	Everite, Henco, Hyper
6	Door closer/Floor spring	Earl-Bihari Pvt.ltd.
7	Hinges/drawer slides	Bhor (Marblex), Armstrong.
	Vinyl flooring/Tiles	
8	1'-0"x1'-0"	Godrej
9	Mortice latch and lock	Vista, Luxaflex.
10	Venetian blinds (vertical/horizontal)	Bhor Bilbio.
11	Upholstrey	Usha
12	Exhaust fan	Modi float- 6 mm thick.+++++
13	Glass.	J.K. , Birla
14	White Cement	Hindware (15 Ltr. Capacity)- Public toilet Design No. 189229.
15	P.V.C. Sleafk Cistern	Nerolac ,Asian
16	Paint, Primer	toilet- Hindware –60007 Senso Urinals.
	Urinals	toilet - Hindware –60007 Senso Urinals.
17		For Public toilet - Hindware –20042 Orissa Pan 6 Ltr.
18	Squatting Pans	MAOR – (Marc make)-4060
19	Towel Rods	Modi Guard- 6 m.m. thick.
20	Mirror	TATA.
21	M. S. Tor.	CECO NO. 1
22	Water proofing chemical	Dursban – T.C. (for wood and earth).
23	Antitermite liquid	B -Class.
24	G.I Pipes	Supreme/Prince
25	PVC Pipes.	India Gypsum, Armstrong
26	False Ceiling	Salwood
26	Timber	Jhonsons , (Perlato)
	vetrified Tiles 2'x2'	