

ISSUED TO M/S _____

TENDER DOCUMENT

FOR

FURNISHING OF
UCO BANK
AT
RUMI (JAGRAON)

**OFFICE OF THE
DEPUTY GENERAL MANAGER
UCO BANK, Z.O. S.C.O. NO. 55-57, 1st FLOOR,
SECTOR 17-B, CHANDIGARH - 160017**

ARCHITECTS:

GURDEV GROUP OF ARCHITECTS

SCO 1094-95, SECTOR 22-B,
CHANDIGARH – 160 022
PHONE: 0172-2712201
MOBILE: 094170-08450

Last Date & time for receiving: -----2019 at 2:00 p.m.
of sealed tender.
Place and date of opening -----2019 at 3:00 p.m.
in the of tender in the Office of Chief Officer, Uco Bank,
S.C.O. 55-57, 3rd Floor, Zonal Office, Sector 17-B, Bank Square,
Chandigarh.

DETAILS OF TENDER**TENDER FOR THE FURNISHING OF UCO BANK AT RUMI**

- | | | | |
|----|---|---|---|
| 1. | Details of work to be done | : | Interior / Furnishing & Allied electrical works for Uco Bank, at RUMI. |
| 2. | Form of Contract | : | Item wise rate |
| 3. | Earnest Money | : | Rs. 15,000/- (Fifteen thousand only) in form of Demand draft in favour of Uco Bank payable at Chandigarh. |
| 4. | Period of contract / time of Completion | : | 3 Weeks |
| 4. | Liquidated damages for non-completion of work in time | : | 1.0% of the contract value per week subject to a max of 10% of the contract value. |
| 5. | Defect Liability Period | : | 12 months (Twelve months) from the date of virtual completion as certified by Architect / employer. |
| 6. | Retention amount for 12 months: | : | 8% of the total bill. |
| 7. | Period of submitting of Final bill. | : | 15 days form the date of completion. |
| 8. | Mobilization Advance / Secured Advance | : | No. Mobilization Advance / secured Advance will be given to the Contractor. |

**Chief Officer, Uco Bank,
S.C.O. 55-57, 3rd Floor, Zonal Office,
Sector 17-B, Bank Square, Chandigarh.**

TENDER FOR THE FURNISHING OF UCO BANK AT RUMI
GENERAL CONDITIONS

1. The Contractor shall sign each page of this tender.
2. Payment to the Contractor Agency shall be made as per actual work done at site.
3. Quantity of work may increase or decrease at site as per requirement, which shall not affect the rates quoted by the contractor.
4. Furnishing works including electrical works etc. shall be done to the complete satisfaction of Bank and Architect-in-charge.
5. All teak / Cedar wood / rubber wood to be used should be knotless which is to be polished with all background surface preparation courses maintaining the visibility of wood grains.
6. The contractor agency shall keep particular vigil on his workers / carpenters / painters etc. to maintain very good workmanship of all items, failing which no payment shall be made and no claim of material / labor used shall be made to him in any case, and the same work shall be executed by him again without charging any extra cost.
7. All rates shall be quoted in words & figures & any cutting over writing shall be signed.
8. All items to be executed as per drawings, if any change is required, the same shall be brought to the notice of Architect-in-Charge.
9. Any tender / quotation containing clerical or arithmetical mistakes shall be rejected.
10. Any addition, alteration or correction shall be signed and stamped properly.
11. Contractor agencies are advised (before quoting the rates) to inspect the site of the proposed work. He must go through all drawings and specifications and documents.
12. The Bank reserves the right to accept / reject any tender / quotation without assigning any reason.
13. The Contractor agency should have already executed works of furnishing interiors & exterior, civil works of very good workmanship.
14. Quality of material and workmanship rejected by the Architect / Concerned Authorities shall be removed immediately by the contractor and rectified / replaced.
15. No advance payment shall be made to the Contractor on supply of any material supplied at site for execution. Payment shall only be made on execution of any concerned / particular item.
16. The rates shall include the cost of coat of anti termite treatment on all wooden frame work and all commercial ply / board used for partitions and paneling, furniture etc. The contractor/s shall have to dismantle & dispose the existing counters, tables & partitions within the quoted cost of the total furnishing works.

17. Rates for partitions, paneling, wall cladding and false ceiling shall include cutting and making good of necessary cut-outs/chiseling to be made for electrical conduits, switch boards etc.
18. Bank shall not be responsible for any loss or damage to the contractor/labour due to any natural calamity during the course of construction. Contractor is liable to make good all the damages if any, till the work is completed and handed over to the Bank authorities.
19. Any payment to the contractor on account of execution of work, whether it is running payment or final, shall be verified by the Architect-in-Charge.
20. Unless, otherwise mentioned all materials to be used shall be I.S.I. marked. Failure to do so, the work may be rejected and in that case contractor shall have to remove the defective materials and replace / re-do the work for which no claim shall be entertained.
21. The total work shall be supervised by the Architect-in-Charge and he/she shall be kept fully informed by the contractor regarding the progress of work.
22. Bank may award the work in part or whole to a single party or any other party.
23. It may please be noted that the Bank is not bound to allot the work to the lowest party. And as such, the allotment of work shall be based on workability of rates quoted by the contractor on account of quality work.
24. The bank reserves the right to reject any or all the tenders without assigning any reason whatsoever.
25. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful tenderers.
26. Earnest money paid by the contractor shall be forfeited by the Bank if contractor fails to undertake the job if he is communicated about acceptance his rates/tender.
27. The contractor shall take all the necessary precautions while working and to safe guard adjacent property, Bank's property, Bank's Employees, and traffic persons.
28. All the rates quoted are inclusive of removal of existing counters, partitions, wiring, rubbish/ debris collected during the progress of work, rejected materials etc.
29. The contractor shall not directly or indirectly sublet the work to other party without written permission of the Bank.
30. The quantities mentioned in schedule are provisional and likely to increase/decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit / business shall be entertained on this account.
31. The Bank reserves the right to distribute the work for which quotations have been called, among more than one parties, if found necessary. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the Bank.
32. All the workers of the contractor must be properly covered by an insurance policy under "Workman's Compensation act" and "Fatal Accidents Act". The contractor at his own expenses arrange to effect and maintain until the virtual completion of

the contract, insurance policy in the joint name of Bank and the contractor against this risk to be retained by the Bank until the virtual completion of the work, and indemnify the Bank from all the liabilities arising out of such events. In case of delay, contractor shall arrange to extend insurance policy till work is completed.

33. All the work should be completed within the specified period in the tender. If the work is delayed due to the reasons beyond the control of the contractor, he should keep intimating the Bank explaining, therein the reasons for such delays, immediately and if in the opinion Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.
34. The contractor shall furnish well in time before work commence at his own cost, colour samples, samples of materials or workmanship that may be called by Bank's Architect / Engineer for approval. Rates quoted shall cover for such preliminary work.
35. All the glass panes, door handles/ hinges, electric fittings, fans, furniture, records, floors etc. are to be thoroughly cleaned after the work is completed.
36. The rates quoted by the contractor shall be firm throughout the duration of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in cost of material and labour.
37. Conditional tenders are liable to be rejected.
38. The successful tenderer is bound to carry out any item of work necessary for the completion of the job even those such items are not included in schedule of quantities.
39. If in any case of work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period, if deemed fit.
40. Decision of the Bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on the terms and conditions of this contract. However, if the matter can not be resolved then the same shall be referred to the respected qualified person in agreed to both the parties and his opinion shall be binding on both the parties. However, this is precourse to any legal action in this regard.
41. If at any stage during the progress of work, it is observed that the contractor is not progressing the work with due diligence, care of lagging much behind the schedule or fails to gear up the work despite instructions from Bank's Architect, the Employer (Bank) reserves the right to terminate the contract with 7 days notice. In such case the contractor shall be liable to pay the Employer any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposit held by the Bank will be forfeited.
42. Contractor shall follow all rules / regulations in force and should possess the license for employing labour and also follow all safety measures, labour bye laws and shall be responsible for any lapse.
43. At any stage i.e. during the execution of work, any kind of change reqd. whether it is in design or specification, the same has to be in-corporated by the contractor.

CONTRACTOR

UCO BANK

TENDER FOR THE FURNISHING OF UCO BANK AT RUMI

FOR FURNISHING WORK TO BE USED.

<u>DESCRIPTION</u>	<u>BRAND</u>
a) Board / Ply	: Conforming to ISI norms.
b) Laminate	: Century, Greenlam, Formica, Sunmica, AICA Amulya Mica: 1mm th.
c) Door Closer / Floor spring	: Everite, Doorking, Sandhu ISI, Nitco. Marked.
d) Drawer & Keyboard, Slide Rails	: Earl Bihari, Ebco (Telescopic)
e) Glue for fixing commercial Board / Laminate	: Fevicol (Pidilite)
f) Glass	: Triveni, Modi Float, Saint Gobain, Asahi.
g) Mortice Latch & Lock	: Godrej.
h) Vertical Blinds	: Vista Levelor / Mac.
i) Tapestry/leather foam	: Harmony, Vimal, Bhor or as approved
j) Aluminium Sections	: Jindal/Mahavir/Hindalco
k) False Ceiling	: Gypsum marked "Gypsteel"
l) Synthetic Enamel	: Asian, Nerolac, ICI, Berger
m) Emulsion Paint/Plastic Paint	: Asian, Nerolac, ICI, Berger

SPECIFICATIONS / BRANDS / MAKE OF ITEMS
FOR ELECTRICAL WORK TO BE USED.

- SFU/MCCB/ Change over switch/DB	: L&T/Siemen's/MDS Legrand.
- Voltmeter/Ampere meter	: AE/L&T.
- Armored Cable	: Gloster/ CCI/Polycab.
- PVC Insulated Wires	: R.R. Kabels/Finolex/Havells/KEI.
- Telephone cable	: Finolex/Evershine KDK/Delton.
- Data cables & I.O's	: Lucent (Avaya)/D-link.
- Modular switch / socket / call Bell	: Havells/Crabtree/Anchor Roma.
- Light fittings & Lamps	: Philips/Crompton/Wipro.
- Ceiling fan/Wall bracket fan/Exhaust fan	: Usha/Crompton/Orient.

CONTRACTOR

UCO BANK

TENDER FOR THE FURNISHING OF UCO BANK AT RUMI

S. No.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT (RS)
A.	FURNISHING WORKS:				
1.	Providing & Fixing false ceiling at 9'-0" ht. (as per drg.) of India Gypsum Ltd. (GMFSC-4.1) using 12.5mm thick Gypboard, paper tape, jointing compound, G.I. Sections marked "Gypsteel" to be placed at 4'-0" C/C in one direction and at 1'-6" C/C in other direction. The false ceiling shall be finished properly after cutting / making holes for fixing light fixtures including three coats of oil bound distemper paint etc. complete as per drgs.	700	Sqft.		
2.	Providing & fixing Aluminum partitions / fixed glass window on sides of entrance (powder coated of size 3 1/4" x 1 1/2" x 2mm bottom section 4 1/2" x 1 3/4" x 2mm th. with 5mm th. glass. And aluminum door: 3'-9"X7'-0" powder coated having; External frame called chowkhat: 3 1/4" x 1 1/2" x 2mm thick, Internal door frame and lock rail: 3 1/4" x 1 3/4" & Bottom rail: 4 1/2" x 1 3/4" with 5mm thick etched glass as per design. including all fittings such as al. handles, locks, stopper, tower bolts, etc.	90	Sqft		
3.	Providing and fixing wooden partition strictly as per drgs. made of internal frame of 1 1/2" x 2" partal wood placed at 2'-0" c/c vertically and horizontally with 6mm thick commercial ply on both sides. The partition shall have 9mm thick commercial ply with 1.00 mm thick laminate on both sides with horizontal grooves 3/8" x 3/8". These partitions shall have 5.00 mm thick glass (etching as per design) above 2'-6" ht. or 4'-0" ht with beading 1/2"x1 1/2" . The rate of partition shall include providing & fixing door in partitions made as per the specifications of partition, but with complete hardware required such as latches, stopper. The low ht. partition shall have rubber-wood gola of size 3" x 3/4" which shall be polished as per shade reqd.				
i)	Low ht. partitions with 12mm thick glass.	40	Sqft.		
ii)	Full ht ptn. with 5mm th glass.	-	Sqft.		
iii)	a) Cash-Cabin's pts (7'-3" high)	60	Sqft.		
iv)	b) Cash cabins' as well as single windows' front ptn. with 12mm th. Glass.	30	Sqft.		
v)	Rear partition and doors for banking hall.	100	Sqft.		
vi)	Cost Mortice locks (with handles)	5	Nos.		
vii)	Cost of Multipurpose locks for storages, drawers etc.	40	Nos.		
viii)	Cost door closers.	7	Nos.		
ix)	Cost floor springs.	1	Nos.		
x)	Cost of Knight Latches	1	No.		
xi)	Aluminum grill.	0	Sqft.		
4.i)	P/F wall paneling on soft wood frame 1 1/2" x 2"	350	Sqft.		

	placed @ 2'-0" c/c horizontally & vertically @ 1'-0" C/C, finished with 9mm thick commercial ply by making horizontal grooves of size 3/8"x3/8", 1.00 mm thick lamine as per design, the paneling shall be closed with 2" x 1" rubber wood beading				
ii).	Providing and laying texture paint of "Heritage" Co. " <u>Rustic type</u> " as per colour scheme.	400	Sqft.		
iii)	Pin-up board finished with cotton cloth & rubber wood beading.	40	Sqft.		
5.(i)	Providing & fixing Banking Counters (SW) as per design, 2'-6" ht. & 3'-3" ht. (2 heights). The banking counters shall have the provision to adjust the key board, drawer, storage complete <u>shelf for CPU at bottom and foot rest</u> . The banking counters shall be made of 19mm thick commercial board, with rubber - wood Gola of size 1 1/2 "x 3/4 ", which is to be polished as per color scheme. The counter shall be finished with 1mm thick laminate of approved shade / colour, handles, magnet catchers, hinges. Inside of counters shall be painted with synthetic enamel paint as per color scheme.	4.5	R.Ft.		
6. (i)	Providing & fixing office tables <u>with/without drawer and storage below</u> of size 2'-4 1/2" (wide), 2'-6" (high) with the provision of key board, with sliding channels of Ebco, <u>complete shelf for CPU at bottom and foot rest</u> . The table shall be made of 19mm thick commercial board; 1mm thick laminate with rubber - wood gola of size 1 1/2 " x 3/4 " polish, painting inside only, side golas etc., with hardware such as hinges, catchers and handles.	14	R.ft.		
ii)	Providing & fixing office tables <u>with one no. drawer and storage below</u> as per drgs of size 2'-4 1/2" (wide), 2'-6" (high) with the provn. of key board on sliding channels of Ebco, <u>complete shelf for CPU at bottom and foot rest</u> . The table shall be made of 19mm thick commercial board; 1mm thick laminate with rubber - wood gola of size 1 1/2 " x 3/4 " polish, painting inside only, side golas etc. complete in all respects as per design.	-	R.ft.		
7.	Providing and fixing side rack, 2'-3" ht. as per design. These racks shall have two drawers with storage below and be made of 19mm thick commercial board; 1mm thick laminate with rubber -wood gola of size 1 1/2 " x 3/4 " polish, painting inside only, side golas, handles, catchers, hinges etc.	12	R.ft.		
8.	Providing & fixing storage along wall 1'-6" deep made of 19 mm th. Comm. Board & 1 mm th. laminate, polish, inside painting, complete finished with golas/margins, handles, hinges and catchers, front openable shutters, as per requirements / design / drg.	100 (Face Area)	Sqft.		
9.	Providing & Fixing Cash – counters 2'-6" wide, with two levels i.e. 2'-6" & 4'-0" ht. The lower portions top & all other exposed surface shall have 1mm thick laminate and golas/margins. The lower portion on cashier side there will be provision of 3 nos. drawers with sliding channels of Ebco. for cash, stationery, key	5	R.ft.		

	board, etc. Inside of cash counters shall be painted with synthetic enamel paint as per color scheme, rubber-wood beadings / gola etc.				
10.	Providing & fixing Branch Manager table 2'-6" ht. with rubber-wood Gola of size 1 1/2" x 3/4". as per drgs. having drawer/s, storage cabinet, key, board, with sliding channels of Ebco, foot rest, space for CPU & Monitor, all as per drg. / design, the table shall be made with 19mm thick com. Board finished with 1 mm thick laminate Inside of table shall be painted with synthetic paint, the other hardware, such as handles, catchers, hinges etc. shall be provided as per requirement.	6	R.ft.		
11.	Providing & fixing writing stand of size 4'-0" x 1'-0" x 1'-7 1/2" high (face area) as per design drg. Made of 19mm th. Com. Board, 1 mm th. Laminate with rubber wood lipping etc.	3	Rft.		
12.	Supplying Stainless Steel Chrome plated perforated 3 seater chair for customer area.	2	Nos.		
13. i)	Providing & fixing notice board of size 2'-6"x 4'-0" finished with ivory colour 1mm th. laminate, 1"x1" th. rubber wood beading on all sides.	1	Nos.		
ii)	Providing & fixing soft boards of size 3'-6"x 2'-0" (covered with openable glass shutters) on 10mm th. comm. ply 12mm th. soft board finished with cotton fabric, 1"x2" rubber wood beading.	1	Nos.		
14.	Providing & Fixing cheque drop box and complaint box of size 18" x 27" as per detail.	2	Nos.		
15.	Painting work on walls & cemented ceiling with oil bound distemper paint and enamel paint on shutters and grills.	2500	Sqft.		
	TOTAL				

B.	<u>ELECTRICAL</u>	QTY.	UNIT	RATE	AMOUNT (RS)
1.	Providing & Fixing 2' x 2' recessed mounted LED Luminaire LCTLR-36-CDL of Crompton.	8	Nos.		
2. i)	Providing & Fixing 15 W LED ROUND DOWNLIGHTER LCND-15-CDL of Crompton.	10	Nos.		
ii)	Providing & fixing LED tube lights 1x40W of Philips.	10	Nos.		
3. (i)	Providing & Fixing wall fans: Khaitan / Crompton Greaves / Orient.	9	Nos.		
(ii)	Exhaust Fans 12" Dia : 1400 rpm (Double ball bearing) Heavy duty Crompton Greaves / Phillips.	4	Nos.		
iii)	Providing & Fixing ceiling fans: Khaitan / Crompton Greaves / Orient 4' dia.	2	Nos.		

iv)	Cost of modular regulators of Havells / Anchor ROMA makes.	2	Nos.		
4.	<u>ELECTRICAL POINTS:</u> Providing laying, fixing & testing of electrical points including wiring from MCB's to switches, plate type switches, socket & M.S. Modular boxes with rust proof treatment size to accommodate the required nos. of switches & sockets plus circuit wiring from switches to lights/fans/fixtures etc. wherever required complete with earthing 1.00 mm ² multi strand wire in 25mm dia. Unbreakable PVC conduit ISI marked with specials under floor / wall & above false ceiling or making truff under / along work - stations including chase cutting, disposal of melba away from the site and repair of the same with cement mortar, copper conductor wires only will be used of approved make.				
a)	<u>Electrical wiring for Air-Conditioning:</u> P / F 32 Amp wiring with MCB from D/B to site of outdoor and indoor A/C Unit, i.e. circuit wiring with 4mm sq. multi-strand PVC copper wire, earth wire with DP switches.	4	Nos.		
b)	<u>Electrical wiring for UPS (charging point for UPS):</u> P / F 2 runs of 4mm sq. and one run of 1.5 sq. mm as earth wire multi-strand PVC copper wires from D/B to the location of UPS room for input to UPS in PVC pipe with DP's or 15 Amp. Power plugs and sockets (2 sets: one for input and the other for output) .	2	Nos		
c)	15 Amp wiring with 2.5mm sq. multi strand PVC copper wire & metal clad enclosure sockets & plus.	6	Nos.		
d)	5 Amp plug point wiring with 1.5mm sq. multi stand PVC copper wire inc. Plate switches, sockets, plugs. Etc.	7	Nos.		
e)	Call-bell point wiring including Ding-dong bell with 1.5mm sq. multi strand PVC copper wire including plate switches, sockets, etc.	1	Nos.		
f)	Wall Fan pts (with 2-pin socket), lights from raw power & UPS supply & exhaust fan point wiring with 1.5mm sq. from D/B to switches & fittings multi strand PVC copper wire including plate switches, sockets, etc. (For payment no. of switches shall be counted).	40	Nos.		
g)	Signage wiring (material & labour) - P&F of 3x4mm & copper flexible wire & PVC conduiting of ISI make complete with all accessories like Saddles, bends modular switches etc.	1	No.		
5.	<u>UPS POINTS:</u> P/L & testing electrical three point wiring /circuit wiring having individual circuits for computers with 2.5mm ² Multi-strand copper PVC wire in unbreakable PVC conduits 25mm dia wall thickness 2mm thick with specials under floor / wall & above false ceiling including chase cutting, disposal of malba away from the site and repair of the same with cement mortar, incl. Switches & socket M.S. switch boxes with rust proof treatment size to accommodate the required nos. of Modular switches, sockets etc. & plate type				

	sockets with indicator three in one plate including earthing with 1.00 mm ² multi strand wire complete in all respect.				
i)	Set of 6 amp. 4 sockets & 4 switches	10 Sets	Each set		
6.	GEL TYPE CHEMICAL EARTHING (Distance between each pit shall be min 1.5meter) Supplying and installation of copper Gel Earthing station having length 3000 mm including bore-well, chamber with cover and all required civil allied works each earth pit to filled with 2 bags in 30 Kg pack of "Black-Fill Compound" (BFC) EARTHING CONDUCTORS: Wiring with 1x10 sqmm PVC insulated copper conductor wire of 650/1100 volts grade (Finolex make flame guard quality) as earth wire with concealed/exposed PVC pipe including making all the connections.	2	No.		
7.	Providing and fixing of PVC conduit in wall floor including Telephone wire , M.S. box and two pin telephone sockets or R.J. – 11 plates out let incl. Testing and commissioning etc. as required.	8	Nos.		
8.i)	Providing, laying, testing and commissioning CAT-VI/ Lucent / D-link computer networking cable in PVC conduit in floor or wall from server room to each table with I.O.'s (Socket)	10	Nos.		
ii)	Supplying of patch chords for computers 1m & 2m length.	10	Nos.		
9.	Providing and fixing main electrical dist. Board with items mentioned below including all internal electrical and generator connections with 10 sq.mm multi strand copper wire, which shall include the following items.				
i)	Amp Meter and voltmeter set	1	Set.		
ii)	Kit-kats 100 Amp. & Neutral Link	3	Nos.		
iii)	Aluminum bus bar 100 Amp proper tinned.	1	Nos.		
iv)	100 Amp. Main switch MCCB type.	1	No.		
v)	Change –over 63 Amp. 3-Phase of Havells make.	1	No.		
vi)	Providing and fixing different rated MCB,s for lights, fans, power supply and AC's. of Havells make.	16	Nos.		
vii)	Providing and fixing TPN (tripping type) of 100 Amp of Havells make. (one for lights and one for AC's and power supply)	2	Nos.		
viii)	Making double-door powder coated M.S. Distribution board 3'x4' to accommodate the above noted electrical items.	12	Sqft.		
	UPS Supply:				
viii)	Providing and fixing (MCB type) DP of 63 Amp of Havells make for UPS supply.	4	No.		

ix)	Providing and fixing different rated MCB,s for UPS supply of Havells make.	8	Nos.		
x)	P/F single phase 10-way D/B (Quote the cost of Box only) for UPS supply for MCB's.	1	No.		
10. i)	Providing & fixing main electrical cable 4- core al. cable armored from elect. pole to meter 25mm dia.	30	Mtr.		
ii)	P/F generator wire/cable 16mm 4-core Alum. Cable armoured.	30	Mtr.		
iii)	P/F 16mm 4-core Alum. Cable from bus-bar to ATM.	0	Mtr.		
11.	Making double-door wooden laminated Distribution board 3'x8' to accommodate the above noted electrical items.	24	Sqft		
12.	Connectivity for the VSAT / leaselines (material & labour) – P&F of 40mm PVC conduit of ISI make including data cable of D-link & RJ-45, complete for connectivity.	1	No.		
13.	Providing, fixing, testing and commissioning computers 16- Ports networking switch with racks.	1	sets		
14. i)	P/L copper pipe with complete insulation required for 1.5 ton split type A.C.s from the place of external units upto the location of inside units.	30	Rft.		
ii)	Providing and laying 25mm dia. PVC pipe heavy duty Diplast make for drainage of water of inside units.	300	Rft.		
	TOTAL				
	TOTAL BRANCH (FURNISHING + ELECTRICAL)				

ESTIMATE FOR THE SITE PREPARATION OF ATM FOR UCO BANK AT RUMI

S.No.	Description	Unit	Rate	Amount (Rs)
1.	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges, if any including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note: - Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings, steps or any type of design etc.)	50 sft.		
2.	Providing & fixing Aluminum partitions / window (powder coated of size 3 1/4" x 1 1/2" x 2mm bottom section 4"	50 Sft.		

	x 1 3/4" x 2mm th. with 5mm th. glass. And aluminum door: 3'-0"x7'-0" powder coated having; External frame called chowkhat: 3 1/4" x 1 1/2" x 2mm thick, Internal door frame and lock rail: 3 1/4" x 1 3/4" & Bottom rail: 4" x 1 3/4" with 5mm thick etched glass as per design. including all fittings such as al. handles, locks, stopper, tower bolts, etc.			
3.	Black granite slab – P&F black granite slab 18-20 mm thick fixed to entrance door steps with grinding, moulding and polishing.	Nil Sqft		
4.	Providing & fixing in position Aluminium Composite Paneling, partition with ACP sheet on both sides, rolling shutter box (ACP) with framing of Aluminium Tube sections of min 1.5" * 1" and 18 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with Silicon based sealant (Black colour). ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.20 mm on both sides. Alstrong, ALEX, Alstone, Alcobond, prime bond or equivalent ISO certified or approved brands to be used. Shades to be as per bank's approval. It has to be used for cladding, boxing over main door and both side Jam of main door and fixed glazing. Complete panelling should be of ACP.	300 Sqft		
5.	Grouting of ATM Machines with Anchor fastener as per Bank's rules, (Including the cost of RCC 12" slab.	1 nos		
6.	Providing & Fixing Flooring with vitrified tiles joint – free of minimum 9 mm thickness, size 24" X 24", 4 " Skirting, all fixed in 1:5 cement mortar, complete with cutting and filling joints with white cement. Make of tiles Johnson/bell/euro/asian /nitco/naveen/somani or equivalent. Ivory / shade or as specified by the bank.	Nil Sqft		
7.	P/F cheque drop box-cum-writing top having 12mm th glass top.	1 No.		
8.	P/F acrylic notice board of size 2'x3' with chrome spacers.	2 No.		
9.	Providing and supplying plastic dust bin and chair.	1 set		
10.	P/F Aircon louvers powder coated of size 12" long.	2 Nos.		
	TOTAL			
	ELECTRICAL WORKS FOR ATM:			
11.	Signage wiring and AC wiring for indoor and out door units: P&F of 3x4mm & copper flexible wire & PVC conduiting of ISI make complete with all accessories like Saddles, bends, DP switches, MCB's etc.	1 Nos.		
12.	Connectivity from server/dish Antenna: P&F of 40mm PVC conduit of ISI make including data cable of D-link (Cat-VI) & RJ-45, complete for connectivity. (to be concealed with openable and lockable box)	2 Nos.		
13.	Providing & Fixing 2' x 2' recessed mounted LED Luminaire LCTLR-36-CDL of Crompton.	1 Nos.		
14.	Providing & Fixing 5 W LED ROUND DOWNLIGHTER LCND-5-CDL of Crompton.	7 Nos.		
15.	Providing & fixing ordinary tube lights 1x40W of Philips.	1 No.		
16.	GEL TYPE CHEMICAL EARTHING (Distance between each	1 Nos.		

	<p>pit shall be min 1.5meter)</p> <p>Supplying and installation of copper Gel Earthing station having length 3000 mm including bore-well, chamber with cover and all required civil allied works each earth pit to filled with 2 bags in 30 Kg pack of "Black-Fill Compound" (BFC)</p> <p>EARTHING CONDUCTORS:</p> <p>Wiring with 1x10 sqmm PVC insulated copper conductor wire of 650/1100 volts grade (Finolex make flame guard quality) as earth wire with concealed/exposed PVC pipe including making all the connections.</p>			
17.	Lights point wiring from UPS (2 lights points and one access lock wiring) and rest shall be connected with raw power supply with 1.5mm sq. from D/B to switches & fittings multi strand PVC copper wire including plate switches, sockets, etc. (For payment no. of switches shall be counted).	9 Nos.		
18.	<p><u>Electrical wiring for UPS input-output:</u></p> <p>P / F 32 Amp wiring with 2 DP's of 32 Amp. from D/B to the location of UPS/UPS room for input and output power supply with 2 runs of 4mm sq. and one run of 1.5 sq. mm as earth wire multi-strand PVC copper wires, with DP switches / power pt. i.e. switch-socket.</p>	1 No.		
19.	<p>P/L & testing electrical three point wiring having individual circuits for computers with 2.5mm² Multi-strand copper PVC wire in unbreakable PVC conduits 25mm dia wall thickness 2mm thick with specials under floor / wall & above false ceiling including chase cutting, disposal of melba away from the site and repair of the same with cement mortar, incl. Switches & socket M.S. switch boxes with rust proof treatment size to accommodate the required nos. of Modular switches, sockets etc. & plate type sockets with indicator three in one plate including earthing with 1.00 mm² multi strand wire complete in all respect.</p> <p>Set of 6 amp./16 1 socket & 1 switch (to be concealed with openable and lockable box)</p>	4 Sets		
20.	15 Amp wiring with 2.5mm sq. multi strand PVC copper wire & metal clad enclosure sockets & plus.	1 Nos.		
21.	5 Amp plug point wiring with 1.5mm sq. multi stand PVC copper wire inc. Plate switches, sockets, plugs. Etc.	1 Nos.		
22.	P/L copper pipe with complete insulation required for 1.5 ton split type A.C.s from the place of external units upto the location of inside units.	Nil		
23.	Providing and laying 25mm dia. PVC pipe heavy duty Diplast make for drainage of water of inside units.	Nil		
24.	Supplying, erection and commissioning of timer switch 240-volt single phase with 32 Amp single phase MCB 40 Amp. DP contactor: for AC	Nil		
25.	P/F M.S. D/B 2'x2' with MCB's and TPN of Havells make with MCB.s 10 Amp. to 16 Amp./20 Amp./32 Amp for supply lights, AC's glow sign Board .	1 No.		
26.	4-way single phase D/B of Havells make with MCB's and DP switch for UPS supply to computers.	1 No.		
27.	Supplying, erection and commissioning of 1.0 ton capacity split type AC's "3-star" Model of Voltas / Blue Star / Hitachi / Carrier make, M. S. stands including stabilizers, insulated copper pipe and drainage PVC pipe with each AC.	nil		
28.	Providing and fixing 16mm cable 4-core aluminum from main panel to the DB of ATM.	5 Mtrs.		
30.	Supplying, erection and commissioning of timer switch 240 volt single phase with 32 Amp single phase MCB 40 Amp. DP	1 No.		

	contactor: for Glow-sign board.			
	TOTAL			
	TOTAL ATM (furnishing + electrical):			

TOTAL (BRANCH + ATM)

RS. -----

Quote further discount, if any

=

(-)

RS -----

NET TOTAL

=

RS-----

QUOTE GST (EXTRA) Tick YES / NO =

Rs.-----

(Rupees_____)

CONTRACTOR

UCO BANK