

TENDER FOR
Proposed Civil & Furnishing work for
TRAINEE HOSTEL, UCO BHAVAN,
SECOND FLOOR, AHMEDABAD
FOR
UCO BANK

Issued to :

(CIVIL & FURNITURE WORK)

Owners
UCO BANK
Circle Head,
Circle Office, 7th Floor, UCO Bhavan,
Ashram Road, Ahmedabad – 380 009.

BIMAL TALATI
Architects & Interior Designers,
304, President House,
Opp. C. N. Vidyalaya,
Ambawadi, Ahmedabad - 380 006.
Phone : (079) 2642 1682, E-mail : bimaltalati@gmail.com

Circle Head,
UCO Bank,
Circle Office,
7th Floor, UCO Bhavan,
Ashram Road,
Ahmedabad – 380 009.

Sub : **Proposed Civil & Furnishing work TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road Ahmedabad, for UCO Bank. (CIVIL & FURNITURE WORK)**

Sir,

I/We the undersigned have carefully gone through and clearly understood the plans, specifications, schedule of quantities, with General conditions for the above mentioned work and having visited and examined the site of the proposed work, do hereby tender to execute and complete the entire work in accordance with the priced bill of quantified and/or as given in the special specification of each works attached hereto.

It is understood that the lowest or any Tender will not necessarily be accepted and that you are not bound to assign any reason of the same.

I/we agree to keep our offer open for three months from the date of opening.

Having examined the drawings, schedule of quantities relating to the proposed Tender for civil & furniture work and having visited and examined the site of the proposed works and having acquired the Tender invited by you, we the undersigned hereby offer to execute, complete and maintain the proposed work in strict accordance with the specifications described in the Tender at the item rates quoted by us in the Tender for the sum of Rs._____

We undertake to complete and deliver the total work within 60 days from the date of issue of work order from you, that the work shall remain incomplete after the expiry of the aforesaid date as liquidated and ascertained damages and not by way of penalty. Suitable extension of time shall be granted for delays beyond our control.

Name and address of the contractor

Signature & Stamp of contractor

Place :

Date :

NOTICE OF INVITATION TO TENDER

Sealed tenders on item rate basis are invited from the enlisted competent civil & furnishing contractors having Technically sound and financial capacity for **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road Ahmedabad, for UCO Bank. (CIVIL & FURNITURE WORK)**. Tender Documents will be available from **UCO Bank, Circle Office, Seventh Floor, UCO Bhavan, Ashram Road, Ahmedabad OR** may be downloaded from the Bank's Web Site : **www.ucobank.com**

Parties who have not executed one or two works of similar nature, each costing not less than 40 %/50 % of the estimated cost satisfactorily during the last two to three years and does not have any office/site or presence in and around the town or district/state in which the project is located need not respond.

Earnest Money Deposit : Rs. 18,500/- by crossed demand Draft/Bank Guarantee on a bank other than the clientele, dischargeable/payable at Ahmedabad and drawn in favor of **UCO Bank, Ahmedabad.**

Time of completion : 60 days, calendar (2) months from the date of commencement.

Time & date of submission
Of Tender : On or Before **02/05/2015 at 1.00 p.m.**

Time & date of opening
Of Tender : **02/05/2015 at 2.00 p.m.** at UCO Bank, Circle Office, Seventh Floor, UCO Bhavan, Ashram Road, Ahmedabad – 380 009.

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders with out assigning any reason whatsoever.

Circle Head,
UCO Bank,
Circle Office,
Ahmedabad.

Name of Work : **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road Ahmedabad, for UCO Bank. (CIVIL & FURNITURE WORK)**

TENDER NOTICE

Sealed Item Rates Tenders are invited on behalf of **UCO BANK, CIRCLE OFFICE, Ahmedabad** from competent contractors, who have executed two or more works of similar nature satisfactorily during last three years. The contractors should be technically sound and financially capable.

The details are as under :

1. Name of Work : **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road Ahmedabad, for UCO Bank. (CIVIL&FURNITURE WORK)**
2. Earnest Money Deposit by Pay Order or Demand Draft from Nationalized Bank(No Interest payable on this deposit) : Rs. 18,500/- in favour of UCO Bank, A'bad.
3. Tender Cost : -
4. Time of Completion : 60 days from the date of commencement
5. Issue of Tender : Tender Documents will be available from **UCO Bank, Circle Office, Seventh Floor, UCO Bhavan, Ashram Road, Ahmedabad OR may be downloaded from the Bank's Web Site : www.ucobank.com**
From date **20/04/2015 to 01/05/2015** between 10.00 a.m. to 6.00 p.m.
6. Submission of Tender : Sealed Tenders with the name of work subscribed on top of the cover will be received at Circle Head, UCO Bank, Circle Office, Seven Floor, UCO Bhavan, Ashram Road, Ahmedabad on or before **02/05/2015 at 1.00 p.m.**
7. Time & Date of Opening of Tender : **02/05/2015 at 2.00 p.m.**
8. Tender Rights : Conditional Tenders will not be accepted. The Bank reserves the right to accept or reject any or all the tenders without assigning any reason thereof or to accept any tender in part thereof.
9. Date of Commencement : Immediately on issue of work order.

Circle Head,
UCO Bank,
Circle Office,
UCO Bhavan,
Ashram Road,
Ahmedabad.

GENERAL CONDITIONS

- (1) Sealed tenders should be addressed to Circle Head, UCO Bank, Circle Office, Seven Floor, UCO Bhavan, Ashram Road, Ahmedabad and super scribed

Name of work : **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road Ahmedabad, for UCO Bank.
(CIVIL & FURNITURE WORK)**

- (2) The tenders will remain valid for a period of 3 months from the date of openings of tenders. Bank reserves the right to accept or reject any or all the tenders without assigning any reason to do so. Bank does not bind itself for accepting the lowest tender.
- (3) The tenderer should quote the rates in figures as well as in words.
- (4) All erasures, corrections and alterations made while filling the tender must be attested by initials of tenderer. Overwriting of the figures is not permitted.
- (5) The Bank reserves the right to reject any or all the tenders, accept part of any tender or entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason or giving any explanation. The rates quoted by the contractor will hold good for this bifurcation and no compensation will be paid on this account.
- (6) Joint tenders shall not be considered.
- (7) Within 7 days of receipt of Intimation regarding acceptance of his tender by the Bank, the tenderer should send his acceptance of the work order in writing. If the tenderer does not do that, or does not start the work within 10 days of such intimation to him or fails to give justified reasons not to do so, acceptance of his tender would be withdrawn and Earnest Money Deposit would be liable to be forfeited.
- (8) The rate quoted in the tender shall include all charges of scaffolding, lift, any tools and plants railway freight labour conditions and fluctuation in the rates, excise duty, sales tax, octroi and any other taxes or expenditure for carrying out the work.
- (9) Water and Electricity will be available free at site.
- (10) No Escalation in rates will be allowed under any circumstances.
- (11) The successful tenderer is bound to carry out entire work within stipulated time limit. The tenderer will have to pay liquidated damages for non-completion of job within stipulated period at the rate of Rs. 500/- per day after expiry of period of completion subject to maximum of 10 % of site contract value.

- (12) The liquidated damages as mentioned above may not be reforced if the contractor applies sufficiently in advance for extension of time mentioning the unavoidable reasons for extension. The Bank shall, if in its opinion (which shall be final and biding upon the contractor) finds genuine reasons shown by the contractor for such request, grant suitable extension in time limit. Any claim for damage or compensation in relation there to by contractor is not permissible. Also other terms and conditions of the contract will remain unaltered in the extended period.
- (13) The successful tenderer is bound to carry out items of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra items will be derived from the tender. In case the rates do not exist in the tender and extra item is not similar to tender item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15 % towards contractor's profit & overheads. For this contractor must submit the rate analysis supported by original vouchers for purchase and labour.
- (14) The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly with least possible delay and to the satisfaction of the Bank.
- (15) The contractor shall remove all rubbish etc. out of site/premises wash and clean the floors and hand over the site in proper and tidy condition.
- (16) The tenderer shall acquaint himself with the site conditions making his own arrangement for storing of material at site, lift, etc.
- (17) Contractor shall shift furniture, cupboard, records, for the purpose of electrification & wiring and rearrange the same as directed. No extra charge shall be paid for the same.
- (18) Contractor shall be prepared to work at times convenient to the Bank. No charges shall be paid for the same.
- (19) The contractor will attend to all defects noticed during defect liability period. If the contractor fails to attend the defects within a reasonable time these defects will be rectified by the Bank and the expenditure incurred on this account will be recovered from security deposit, or any other money due on to time.
- (20) The contractor shall make adequate arrangement for watch and ward of his material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or other sub contractor.
- (21) The work executed should be got approved by the Architect/Bank and contractor shall rectify any bad workmanship pointed out at any stages and remove from site all the rejected material immediately.

- (22) The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by him or by his sub contractor.
- (23) The contractor will take necessary precautions for carrying out the work avoiding any damage to fixed or loose furniture, structures/decorative parts of the property. The contractor will rectify any damages done at his cost.
- (24) The contractor shall ensure that workmen employed by him for execution of work are suitably covered against workmen's Compensation Act, ESIS and other legislative enactments applicable to such works and workmen shall be to the contractor's account.
- (25) The contractor shall inform the Architect/Bank to check quality/measurements of any work which is likely to be hidden before covering.
- (26) In case of non-completion or delay in completion of work or removal of defects in time, the Bank shall be free to appoint another agency to get the job done at contractor's risk and cost.
- (27) Income Tax at applicable rate of the Bill Amount will be deducted at sources from the contractor's bill and will be deposited with the I.T.O. as per rules.
- (28) The Bank may delay the progress of work without, in any way, vitiating the contract and grant such extension of time for the commencement/completion of the contract as it may think proper and sufficient in consequence of such delay and the contractor shall not make claim for compensation or damage in relation thereof.
- (29) The contractor will not execute any extra item without Bank's permission in writing.
- (30) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on actual work done by the contractor. However, the contractor should not deviate the quantity without Bank's permission.
- (31) Conditional tenders quoted by the tenderer is liable to be rejected.
- (32) The Bank has a right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alternations or variations shall be carried out without prejudice to this contract.
- (33) The Bank has right to terminate the contract, if the contractor abandons the work, or fails to commence and complete the work in time, or fails to abide by the contract conditions. No compensation will be paid in such cases.
- (34) Measurements for all items shall be taken as per actual work done and no claim for any wastage in all material shall be considered.

- (35) Contractor has to get the samples of all the materials like switch, wire, or any other accessories for the approval of the Architect/Bank.
- (36) Contractor must quote balanced rates as quantities mentioned in the tender are approximate and may vary to any extent. No extra rate shall be given on this account.
- (37) The contractor while executing the work during the working hours of the Bank shall take special care that disturbance is not created to Bank's staff and customer during the office hours. The contractor should also keep the banking hall in a reasonably good condition during the banking hours.
- (38) Contractor will submit Photographs of the existing site condition along with completed civil & furnishing work in duplicate along with soft copy in form of C. D.
- (39) **THE CONTRACTOR IS REQUIRED TO OBTAIN NECESSARY LABOUR LICENCE FROM LABOUR ENFORCING AUTHORITY BEFORE COMMENCEMENT OF THE WORK. HE IS ALSO REQUESTED TO ABIDE BY THE LABOUR LAWS APPLICABLE INCLUDING SUBMISSION OF FORM VI-B TO THE LABOUR ENFORCEMENT OFFICER.**
- (40) **THE CONTRACTOR WILL ADHER TO THE IBA/CVC GUIDELINES DURING EXECUTION OF WORK.**
- (41) **THE RATES SHOULD BE FIRM INCLUDING ALL TAXES. DISCOUNT IN TOTAL AMOUNT WILL NOT BE CONSIDERED AND THE SAME TENDER WILL BE LIABLE FOR DISQUALIFICATION.**
- (42) **THE CONTRACTOR MUST GIVE CELL/MOBILE NO., WHICH SHOULD BE ON 24 HOURS FOR THE PURPOSE OF COMMUNICATION DURING EXECUTION OF WORK.**

Name of Contractor with seal & signature

Date :

Place :

SPECIAL CONDITIONS OF CONTRACT

1. Earnest Money Deposit : Rs. 18,500/-
2. Initial Security Deposit (ISD) : 2 % of tender amount inclusive of Earnest Money Deposit
3. Defects Liability Period : 12 months from the date of issue of virtual completion and handing over the site to owners.
4. Period of commencement : Immediately .
5. Stipulated period for completion : 60 days
6. Minimum value of work : Minimum value of work not less than Rs. 10,00,000/-
7. Retention Money : 8 % retention money from each running Bill.
8. Terms of Rate : The rates shall be at site of work and should be inclusive of all taxes including works contract tax if any.
9. Period of validity of Tender : Three months from the date of opening tender.
10. Period for honouring interim certificate : 7 working days from the date of Architect's certificate.
11. Period of honouring final certificate : 10 working days from date of Architect's certificate.
12. Validity of rates after award of Tender : "NO ESCALATION IN PRICE WILL BE ALLOWED".
13. Income Tax clearance certificate : The tenders to submit the latest Income Tax clearance certificate along with the tender.
14. Release of Retention Money : 8 % Retention Money shall be released after satisfactorily completion of Defects Liability period of 12 months.

Circle Head,
UCO Bank,
Circle Office,
UCO Bhavan,
Ahmedabad.

SPECIFICATION OF MATERIALS

All the material to be used shall be from the list of ISI approved Brand. Any deviation from this shall be got approved from Architect/Owner, the contractor shall submit samples of materials used for verifications and produce Bill in original.

1. SAMPLES : After receipt of the bids but prior to award of the contract, bidder shall, upon notification from owner submit samples of materials he intends to use. The owner shall reserve the right to evaluate the sample with regard to the specification before award of work. Samples as directed by the Architect/Owner for various items shall be prepared/brought for approval without any cost.
2. PLYWOOD : Plywood should be Termite and Powder proof.
3. GLASS : Glass shall be float glass of Modiguard company.
4. TIMBER : Wherever specified shall be teak wood from Central Province (C.P.)/Ghana best quality. It shall be well seasoned, uniform in colour, free from sap wood, wares, free from large and loose knote, cracks, shakes and other defects. All wood shall be treated for anti termite treatment with two coats of solingnum paint and two coats of fire retardant paint.
5. HARDWARE : Hinges, Handles, Stoppers, Stays etc. wherever required shall be brass/stainless steel of approved shape and size only.
6. UPHOLESTRY : Fabric or upholstery material wherever called for shall be of the colour, texture and manufacture approved by the Architect/Owner.
7. WORKMANSHIP : The work involved calls for high standard of workmanship and shall be carried out and completed in the best possible manner keeping modern trend of artistic finishes and designs in view so as to make the entire work/furnishing aesthetic looking, keeping in harmony with other furnishing in the area.
8. DIMENSIONS & JOINTS : The dimensions mentioned in the schedule of quantities and drawings are approximate. The contractor may suggest small deviations in the dimensions so as to make the individual items as also the entire job

functionally sturdy, comfortable as well as aesthetic in look. The final decisions regarding sizes of various members and working dimensions etc. will however to be taken at the time of approval of sample. The contractor should take actual dimensions available at site before fabrication. The joints shall be perfect and sturdy and shall preferably be machine made and assembled with approved quality synthetic glue. The structural design of different members and also the items as a whole shall be sturdy and capable of with standing the various loads likely to be subjected to in day to day use.

9. ADDITIONAL
MEMBERS AND
FIXTURES

: The contractor shall provide additional members wherever necessary for providing door, openings, cut-outs, etc. to facilitate fixing of light fixtures, plug points, air-conditioning supply and return grilles etc. The work includes cost of fittings and fixtures & fixing the various items in position in floors, walls, ceilings etc. in the building in accordance with two drawings of as directed by the Architect/Owner. It will be also necessary to make holes, chases, etc. in floors, walls, ceilings, R.C.C. etc. as may be required for fixing the partition. The contractor shall allow for such provisions in his quoted rate. It will be deemed that while quoting rates the contractor has taken into account all foreseeable contingencies which will include making good disturbed floors, walls, ceilings, etc. to their original condition.

10. POLISHING : All visible T.W. members shall have lequare polish, other surface may have french polish as directed complete.

SCHEDULE OF APPROVED MAKES FOR MATERIALS IN

CIVIL WORKS

- | | |
|--|---|
| 1. Vitrified Tiles | 1 st Quality of Vermora/Nitco/Asian or as approved by Bank/Architect. |
| 2. Wash Basin | 1 st Quality of Hindware (Hindustan Sanitarware), CERA, or as approved by Architect. |
| 3. European W.C. pan | 1 st Quality of Hindware (Hindustan Sanitarware), CERA, or as approved by Architect. |
| 4. Orissa W.C. pan | 1 st Quality of Hindware (Hindustan Sanitarware), CERA, or as approved by Architect. |
| 5. Urinal pan | 1 st Quality of Hindware (Hindustan Sanitarware), CERA, or as approved by Architect. |
| 6. PVC pipe & fittings | Astral/Prince/Supreme or as approved by Architect. |
| 7. Bib cock, Stop cock, Pilalr cock, Angle cock, Flush cock, Jet Spray | Essco/ESS ESS/Jacquare (Continental series or approved by Architect. |
| 8. Cement | 43/53 grade Ambuja, Ultra Tech, L & T, or as approved by Architect. |
| White Cement | JK White, Birla White or as approved by Architect. |
| 9. Glazed Tiles | 1 st Quality of Asian/Kajaria/Johnson/Bell or as approved by Architect. |
| 10. Antiskid Tiles | 1 st Quality of Asian//Kajaria/Johnson/Bell or as approved by Architect. |
| 11. External Paving tiles | 1 st Quality of Super Tiles, Ultra Designer Tiles, Eurocon Tiles, or as approved by Architect. |
| 12. Bricks | Obtained from Chimney Kiln or as approved by Architect |
| 13. Sand | Coarse clean river sand free from salt & other impurities. |
| 14. Kotah stone | 18 to 20mm thick 1 st Quality, uniform in colour & thickness |
| 15. Granite stone | 20 to 25mm thick 1 st Quality, uniform in colour & shed thickness without cracks |
| 16. Granite tiles | 8 to 12mm thick 1 st Quality, uniform in colour & shed |

| | |
|-----------------------------|---|
| 17. Anticorrosive paint | Fin coat, Tikitar or as approved by Architect |
| 18. Red oxide | Nerolac, Asian, Shalimar |
| 19. Wheel Valve | Zoloto, Leader (ISI marked) |
| 20. Stainless steel sink | Nirali, Diamond or as approved by Architect. |
| 21. Water Proofing Compound | Pidilite, Choksey or as approved by Architect. |
| 22. Hardners | Ironite, Ferrox, Hardonite or as approved by Architect. |
| 23. Tile Fixing Adhesive | Pidilite, Choksey or as approved by Architect. |
| 24. Sealant | Pidilite, Choksey, Rhone Poulenc or as approved by Architect. |
| 25. PVC Water Tank | Sintex or as approved by Architect. |
| 26. Exterior Paint | Sandtex Matt of Snowcem or as approved by Architect. |
| 27. Aluminum section | Jindal or as approved by Architect. |
| 28. TMT bars FE – 415 | Tata or as approved by Architect. |
| 29. Anti termite Treatment | Any ISI Brand or as approved by Architect. |

- Note :
1. ARCHITECT reserves the right to select the approved make from the above list and to make changes (Add or Delete names of other makes) in this list with consent of Bank.
 2. Vendor should quote the rates of items considering **FIRST MAKE** only.
 3. All materials shall be of the first quality (among the approved brand, selecting brand shall be done as per Bank/Architect choice).

SCHEDULE OF APPROVED MAKES FOR MATERIALS IN

FURNITURE WORKS

- | | |
|------------------------|---|
| 1. Glass | Modiguard float/ Indo Asian/Gujarat Gaurdian Ltd., or as approved by Bank/Architect. |
| 2. Plywood (B.W.P) | Amul/Anchor/Greenply/Euro or as approved by Bank/Architect. |
| 3. Block Board (B.W.R) | Amul/Anchor/Greenply/Euro or as approved by Bank/Architect (IS 1659). |
| 4. Plywood (B.W.R.) | Amul/Anchor/Greenply/Euro or as approved by Bank/Architect. (IS 1659) |
| 5. Polish | N.C. clear liquor polish/Duco/Asian Melamine or as approved by Bank/Architect. |
| 6. Plastic Paint | ICI Dulux (valvet), Nerolac paints/Asain paint (Royal) or as approved by Bank/Architect. |
| 7. Adhesives | Fevicol SH/Blue Coat or as approved by Bank/Architect. |
| 8. Castor Wheels | Efficient gadget or as approved by Bank/Architect. |
| 9. Revolving Stand | Pitroda or as approved by Bank/Architect. |
| 10. Hardware | Efficient gadget/Erl. Bihari or as approved by Bank/Architect. |
| 11. Sal wood | Sal Wood (First class) or only seasoned timber to be used or as approved by Bank/Architect. |
| - For External Use | 1 st Quality imported Sal Wood without knots, joints and bend wood |
| - For Internal Use | 1 st Quality Sal Wood without knots, joints and bend wood. |
| - For Wooden Molding | 1 st Quality of Steam beech without knots, joints and bend wood. |
| - For Leaping/Border | 1 st Quality Steam Beech without knots, joints and bend wood. |
| 12. Laminates | Samrat/Sun Mica/Amulya Mica or as approved by Architect. |
| 13. Carpet | Unitex/Modi/Transansia or as approved by Architect. |

| | |
|--|--|
| 14. Glass Wool | Lloyds/Fibreglass pikington or as approved by Architect. |
| 15. Door Closer | Efficient Gadget/Sterling/Yale |
| 16. False ceiling | Gypsum Board |
| 17. Latex Rubber | Geofoam or as approved by Architect. |
| 18. Particle Board | MDF/NOVAPAN/New wood. |
| 19. Floor Spring | Efficient Gadget. |
| 20. Locks | Efficient Gadget/ Godrej. |
| - Multipurpose Set Locks | EBCO-Efficient Gadgets -EGL or as approved by Bank/Architect. |
| - Mortise Locks | 6 level Yale brand or as approved by Bank/Architect. |
| 21. Veneers | Archid/Anchor/Greenlam or as approved by Bank/Architect. |
| 22. Venetian blinds(Vertical & Horizontal) | Vista leavlor, Aerolux, New Delhi or as approved by Bank/Architect. |
| 23. Alluminium Section | Jindal Alluminium Ltd./Hindustan Alluminium Ltd. or as approved by Bank/Architect. |
| 24. Prelaminated Particle Board (PLPB) | Novapan/Bhutan Board/Archid Ply or as approved by Bank/Architect. |

- Note :
1. ARCHITECT reserves the right to select the approved make from the above list and to make changes (Add or Delete names of other makes) in this list with consent of Bank.
 2. Vendor should quote the rates of items considering **FIRST MAKE** only.
 3. All materials shall be of the first quality (among the approved brand, selecting brand shall be done as per Bank/Architect choice).

FORM OF TENDER

To,
Circle Head,
UCO Bank,
Circle Office,
7th Floor, UCO Bhavan,
Ashram Road,
Ahmedabad – 395 009.

Sub : Proposed Civil & Furnishing work TRAINEE HOSTEL, at Second Floor, UCO Bhavan, Ashram Road, Ahmedabad, for UCO Bank. (CIVIL & FURNITURE WORK)

Dear Sir,

As per the above subject matter our clarification is as under :

1. I/We refer to the Notice Inviting Tender issued by you for the captioned work.
2. I/We do hereby offer to perform, provide, execute, complete and maintain the works in conformity with Bill of Quantities, Drawings, Specification, Design, General and Special conditions of Contract, Instruction to tenders, etc. as contained in the tender documents for the sum as arrived and filled, at the respective rates quoted by me/us in the Schedule of Quantities and/or at any other sum and rate subsequently negotiated and accepted/agreed by the Bank and me/us.
3. I/We have satisfied myself/our self as to the site conditions, examined site and drawing, and all aspect of tender documents/conditions and are acceptable to us. I/We do hereby agree, should this tender be accepted in whole or in part, to
 - (A) Abide by and full-fill the terms, conditions and provisions of tender documents annexed hereto.
 - (B) Complete the work within stipulated completion time at no extra cost to the Bank.
4. I/We are enclosing herewith the Earnest Money Amount of Rs. in the form of Bank Draft/ Pay Order /Banks Cheques no. _____ dated _____ drawn by _____ in favour of **UCO Bank** payable at Ahmedabad.
5. I/We are submitting herewith duly filled up and signed tenders as per the following details.

a) **“Sealed Cover”**

Sealed cover marked as **“Tender for Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabad for UCO Bank”** on the cover and containing.

- (i) EMD
- (ii) Complete set of tender documents
- (iii) My/our specific terms/ clarifications/ conditions/ consideration (if any) on my/ our letter head.
- (iv) **In case of partnership firm** : Attested copy of Partnership Deed and Special Power of Attorney which contain specific powers authorizing under signed/s for tendering.
- (v) **In case of company** : Attested copies of Memorandum and Articles of Associations of the company along with Board Resolutions authorizing undersigned for tendering.

Sealed cover should be addressed as above and having seal & address of our firm/company at bottom left corner of the envelopes.

I/We confirm that I/we are duly authorized to participate in the tendering/bidding and understand that my/our tender is liable to be rejected if,

- (i) At any items it comes to the notice of the Banks that I/We have concealed or/and have given any wrong information.
- (ii) The tender is not duly filed and /or signed and /or is incomplete and/ or covers are not properly sealed.
- (iii) The price bid contains any condition/ alteration/ modification and/ or any tempering with the tender documents is done at our end.
- (iv) Tender received by the Bank after due date and time.

All the pages of the tender documents are affixed with the seal/stamp of my/our company and initialed/ signed by the undersigned.

Signature of Tenderer/s
(Duly authorizing for tendering)

Seal/ Stamp of the Firm/Company

Place :
Name :

Date :
Designation :

FORM OF GUARANTEE FOR WATER PROOFING

Name of work : **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabad for UCO Bank.**

Free Maintenance Guarantee – Water Proofing Work :

By _____

We, _____ hereby guarantee that the surfaces treated by us for water proofing in the above work, shall remain entirely water tight. Should, however, due to any unforeseen defect left out in the work carried out by us at the time of execution of the work, there be any leakage from any treated by us during the period of five years from the date of virtual completion of the work, i.e. from _____ to _____ the same shall be rectified by us without any extra cost to UCO Bank.

However, we shall not be responsible in any way if our work is tampered with or if the body of the structure is damaged due to sinking, cracking and/or by any other act of God beyond our control.

Name of Contractor with seal & signature

Date :

Place :

Note : The above Form of Guarantee for water proofing shall be submitted by the Building Contractor on Stamp Paper of Rs. 100/-.

ARTICLE OF AGREEMENT

Article of Agreement made this at Ahmedabad in this day of 2015, between the **UCO BANK, Circle Office, Seventh Floor, UCO Bhavan, Ashram Road, Ahmedabad – 380 009** (hereinafter called “the Employer” of the one part), and Name : **M/s**_____ (Hereinafter called the contractor of the other part) where as the Employer is desires of having **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabad for UCO Bank. (CIVIL & FURNITURE WORK)** and has caused drawings and specifications describing the work and bills of quantities prepared through its appointed Architect Shri Bimal Talati, Architect, Registered Member, Council of Architecture, Govt. of India, of **BIMAL TALATI, Architects & Interior Designers, 304, President House, Opp. C. N. Vidyalaya, Ambawadi, Ahmedabad – 380 006** and whereas the said drawings have been seen, the specifications and/or the schedule of quantities have been signed by or on behalf of the partners have hereto the contractor and whereas the contractor has agree to execute upon and subject to all conditions of contract (all of which are collectively hereinafter referred to as

“the said conditions”) the work shown upon the said drawing and/or described in the said specifications and included in the said schedule of quantities at the respective rates therein set forth amounting to the sum as therein arrived at of such other sum as shall become payable there under (hereinafter referred to as “the said contract amount”).

NOW IT IS HEREBY AGREED AS FOLLOWS

1. In consideration of the said contract amount to be paid at the time and in the manner set forth in the said conditions execute and complete the work shown upon the said drawings and described in the said specifications and the schedule of quantities, either in whole or in part.
2. The employer shall pay the contractor the said contract amount or such other sum as shall become payable at the time and in the manner hereinafter specified in the said conditions.
3. The term “the Architects” in the said conditions shall mean the said **BIMAL TALATI, Architects & Interior Designers, 304, President House, Opp. C. N. Vidyalaya, Ambawadi, Ahmedabad – 380 006**, or in the event of their death or ceasing to be the architects for the purpose of this contract, such other person or persons as shall being a nominated for the purpose by the employer not being a person to whom the contractor shall object for reasons (maintained in said conditions) considered to be sufficient by the employer. Provided always that no person or persons subsequently appointed to be architects under this contract shall be entitled disregard or over rule any previous decision or approval or direction given or expressed in writing by the architects for the time being.
4. The said conditions an appendix shall be read and construed as forming part of this agreement and the parties hereto shall respectively abide by to submit themselves to the conditions and perform the respective agreements on their part as contained in the said conditions contained.
5. The Architect refers to **BIMAL TALATI, Architects & Interior Designers, Ahmedabad**, while “Civil Engineer” refers to the Technical Officer of **UCO BANK, Circle Office, Ahmedabad**.
6. The plans, agreement and documents mentioned herein shall from the basis of this contract.

7. The contract is neither a fixed lump sum contract nor a piece work contract, but is a item rate contract to carry out work in respect of **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabad for UCO Bank. (CIVIL & FURNITURE WORK)** and also some addition and alteration works to be paid for according to actual measured quantities at the rates contained in the schedule of rates and probable quantities as provided in the said conditions.
8. The contractor shall afford every reasonable facility for the carrying out of the all works relating to **Proposed Civil & Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabad for UCO Bank. (CIVIL & FURNITURE WORK)**. Preparing the civil & furniture work and other ancillary works in the manner laid down in the said conditions, and shall make good and damage done to walls, floors etc. after the completion of his work.
9. The Employer through the architect and technical officer reserves to himself the right of altering the drawing and nature of the work of having portions of the same carried out without prejudices to this contract.
10. The said conditions shall be read and construed as forming part of this agreement and the parties hereto will respectively abide by to submit themselves to the conditions and stipulations and perform the agreements of their parts, respectively in such conditions contained.
11. Time shall be considered as the essence of this agreement and the contractor hereby agrees to commence the work soon after the formal work order issued to him and complete the entire work within 60 days.
12. All payments by the Employer under this contract will be made only at **Ahmedabad**.
13. All disputes arising out or in any way connected with this agreement shall be deemed to have arise in **Ahmedabad** and only the Courts in **Ahmedabad** shall have jurisdiction to determine the same.
14. The several parts of this contract have been read and fully understood by the contractor. In witness whereof the employer if the contractor have set partnership or an their respective hands to these individual. Presents and two duplicates here of the day and year first here in above written.

In witness where of the parties hereof the Employer if the contractor has set its hand to these company.

Presents its duly authorized official and the contractor has caused its common seal to be affixed hereunto and the said two duplicates has caused these presents and the said two duplicates hereof to be excavated on its behalf, the day and year first herein above written.

SIGNATURE CLAUSE

SIGNED AND DELIVERED BY M/S_____.

By the hand of Shri _____, Proprietor.

In the presence of

1.

Witnesses :

If the party is a partnership firm or an individual should be signed by all or on behalf of all the partners.

SIGNED AND DELIVERED BY

In the Presence of

2.

Witness :

THE COMMON SEAL OF

UCO BANK

Name of work : **Proposed Civil & Furnishing work for TRAINEE HOSTEL
at Second Floor, UCO Bhavan, Ashram Road,
Ahmedabad for UCO Bank.**

S U M M A R Y

| | | |
|--------------------------------------|------------------|-------|
| A. CIVIL WORK | Rs. | |
| B. FURNITURE WORK | Rs. | ----- |
| | Rs. | |
| Add for Service Tax @ _____ % on Rs. | (+) Rs. | ----- |
| | TOTAL Rs. | |

(RUPESS

Name of Contractor with seal & signature

Date :

Place :

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|-----------|---|-----------|------|-----|-------------------|
| 1. | DISMANTLING BRICK WALL | | | | |
| | Demolishing the existing 9" thick brick wall/rcc work and unserviceable material and debris to be carted away from the second floor to ground floor as directed. | 10 SMT | | SMT | |
| 2. | DISMANTLING BRICK WALL | | | | |
| | Demolishing the existing 4½" thick brick wall/rcc work and unserviceable material and debris to be carted away from the second floor to ground floor as directed. | 20 SMT | | SMT | |
| 3. | REMOVING OF EXISTING TOILET DOOR | | | | |
| | Removing the existing the wooden doors of toilet at Second floor and to be stacked at site as per direction | 5 NOS | | NO | |
| 4. | DISMANTLING TOILET BLOCK | | | | |
| | Demolishing the existing toilet block including W. C. and Urinal space, plumbing lines, sanitary lines and sanitary fittings and glazed tiles flooring & dado etc. and unserviceable material and debris to be carted away from the second floor to ground floor as directed. | 1 JOB | | JOB | |
| 5. | REMOVING OF EXISTING WOODEN PARTITION SOLID & GLAZED | | | | |
| | Removing the existing the wooden partition (glazed & solid) from the floor at Second floor and to be stacked at site as per direction | 50 SMT | | SMT | |
| 6. | CUTTING THE EXISTING FLOORING | | | | |
| | Cutting the floor for new proposed brick wall required as per thickness and debris to be carted away from the second floor to ground floor as direction | 75 RMT | | RMT | |

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|----------|---------------------|----------|------|-----|-------------------|
|----------|---------------------|----------|------|-----|-------------------|

7. BRICK WALL

Providing & constructing 9 & 14" thick brick masonry in C. M. 1:6 (1 cement : 6 coarse sand) with approved bricks having minimum crushing strength 50 Kg./Sq. Cm. Including all necessary scaffolding, racking out the joints, curing etc. complete as directed in all levels. at Second floor.

- Do - as above but in super structure at all heights above ground floor height.

20
SMT

SMT

8. BRICK WALL

Providing & constructing 4½" thick brick masonry in C. M. 1:6 (1 cement : 6 coarse sand) with approved bricks having minimum crushing strength 50 Kg./Sq. Cm. Including all necessary scaffolding, racking out the joints, curing etc. complete as directed in all levels. at Second floor

- Do - as above but in super structure at all heights above ground floor height.

200
SMT

SMT

9. RCC LINTEL

Providing & laying Ordinary cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and finishing smooth with curing etc. complete including the cost of form work and reinforcement for RCC work in Lintel etc. complete as per direction. at Second floor.

50
RMT

RMT

10. SMOOTH CEMENT PLASTER

Providing & laying 15mm thick smooth cement plaster on wall in cement mortar 1:4 (1 cement : 4 sand) up to floor two levels at Second floor and finished even and smooth for new constructed wall etc. complete as per direction of Bank/Architect.

400
SMT

SMT

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|------------|---|-----------|------|-----|-------------------|
| 11. | ANTISKID TILES FLOORING FOR TOILET | | | | |
| | Providing & laying of Antiskid/Ceramic Tiles of 12" X 12" size & 8mm thick and approved make in flooring laid on a bed of 12mm thick cement mortar 1:3 (1 cement: 3 coarse sand) finished with flush pointing in white cement at Second floor etc. complete as per direction of Architect. This item also includes cleaning the tiles after fixing with acid wash if required. (Basic cost of tiles @ Rs. 45/- per SFT). | 20 SMT | | SMT | |
| 12. | GLAZED TILES FLOORING & DADO FOR TOILET | | | | |
| | Providing & fixing of coloured glazed tiles of approved size in flooring and dado up to 5'-0" height laid on a bed of 12mm thick cement mortar 1:3 (1 cement: 3 coarse sand) finished with flush pointing in white cement at Second floor etc. complete as per direction of Architect. | 75 SMT | | SMT | |
| 13. | WOODEN FRAMED FLUSH DOORS | | | | |
| | Providing & fixing new flush doors including 4" X 3" hard teak wood frame and shutter should be made from t.w. section of required size & will be covered 6mm th. water proof plywood on both the sides with necessary fittings like stainless steel hinges, Stainless steel handles, door stopper, aldop, door closer etc. complete with both the side finished with 1mm thick laminate of approved color & shade at Second floor as per instruction of architect. | 20 SMT | | SMT | |
| 14. | POWDER COATED ALUMINUM FRAMED BACKELITE SHEET DOORS | | | | |
| | Providing & fixing new powder coated aluminum section framed including 4" X 3" size in p section and shutter should be made from required frame 3" X 2" and 3mm thick Bakelite sheet of approved | | | | |

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|------------|--|-----------|------|-----|-------------------|
| | color with necessary fittings like stainless steel hinges, stainless steel handles, door stopper, aldrop, etc. complete with rubber gasket at Second floor etc. as per instruction of architect. | 15 SMT | | SMT | |
| 15. | POWDER COATED ALUMINUM FRAMED VENTILATION WITH GLASS | | | | |
| | Providing & fixing new powder coated aluminum section framed including 4" X 3" size in p section and 5mm thick wired glass of approved make ventilation with required grill with painting of approved color at Second floor etc. complete as per instruction of architect. | 5 SMT | | SMT | |
| 16. | REPAIRING OF EXISTING WINDOWS | | | | |
| | Repairing, Servicing of existing window with required fittings & fixtures, glass etc. for smooth operations at Second floor as per direction | 50 SMT | | SMT | |
| 17. | RE-FIXING OF EXISTING WOODEN PARTITION | | | | |
| | Re-fixing of existing wooden partition as per new lay out plan with required repairing, beading etc. at Second floor as per direction | 50 SMT | | SMT | |
| 18. | ACRYLIC EMULSION PAINT ON WALLS | | | | |
| | Providing & applying Acrylic Emulsion paint of approved shade and manufacturer on walls applied evenly to give approved uniform matt finish etc. complete as per I. S. specifications including scaffolding. (ICI Dulux (Valvet Touch), Asian (Royal Touch), Nerolac) make, minimum 3 to 4 coats and scarping the existing white wash/paint etc. complete as per direction by Architect. This item also includes one coat of primer and two coats of putty/lapi at Second floor etc. complete as per requirements. | 750 | | SMT | |

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|----------|---------------------|----------|------|-----|-------------------|
|----------|---------------------|----------|------|-----|-------------------|

19. SYNTHETIC ENAMEL PAINT

Providing & applying one coat of primer and three coat of synthetic enamel paint of ICI Dulux/Nerolac/Asian make & tint as per manufactures specifications with brush including rubbing cleaning leveling the surfaces with putty with necessary scaffolding at Second floor etc. complete as per requirements.

100
SMT

SMT

20. WATER PROOFING

Providing chemical water proofing of approved make for toilet sunken portion. This also includes polymer mortar 50 Kg. cement : 150 Kg. sand : 5 Liter Bitobond SBR 45. Apply two coat by brush bond (Fosroc acrylic water proofing coating up to 1.5mm thick). Provision with Water proof plaster 25mm to 30 mm thick with 1 vol. Cement : 3 vol. Sand : 150ml complast X 421 ic as integral water proofing compound in 1 Bag of cement at Second floor. The vendor should give guarantee for this work for minimum 5 year on a specific stamp paper of Rs. 100/-. The entire item will be carried out as per direction.

20
SMT

SMT

21. CINDER FILLING

Providing & filling the light weight material/thor for toilet sunken portion with cement mortar mixed in 1:4 after laying of chemical waterproofing treatment at Second floor as directed.

20
SMT

SMT

22. IPS FLOOR

Providing & laying 50mm thick IPS floor with required slope finished with cement mortar 1:4 (1 cement :4 sand) with neat cement slurry, curing etc. including making junction vata at Second floor etc. complete as per direction.

20
SMT

SMT

23. BASE COAT OF PLASTERING WORK

Providing & laying 15mm thick smooth cement plaster for base coat for glazed

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|------------|---|------------|------|-----|-------------------|
| | tiles dado on wall in cement mortar 1:4 (1 cement : 4 sand) up to floor two levels and finished even and smooth at Second floor etc. complete as per direction of Bank/Architect. | 75 SMT | | SMT | |
| 24. | WATER SUPPLY PIPE LINES | | | | |
| | Providing & fixing to u-pvc wall ceiling & floor PVC tubes (medium grade 'B' class) of the following nominal bore, tube fittings and clamps including making good the wall, ceiling and floor at Second floor etc. complete | | | | |
| | a). 15mm dia. | 100 RMT | | RMT | |
| | b). 25mm dia. | 50 RMT | | RMT | |
| | c). 32mm dia. | 100 RMT | | RMT | |
| 25. | PVC DRAINAGE PIPE LINE | | | | |
| | Providing & laying PVC waste water pipe line concealed/open in the structure as per details and requirements with necessary specials such as Y-s, T-2, offsets, plugs, bends and filling the joints with approved adhesive including cutting of wall floor and making good after the work is over at Second floor etc. complete as per direction. | | | | |
| | a). 50mm diameter | 50 RMT | | RMT | |
| | b). 75mm diameter | 50 RMT | | RMT | |
| | c). 100mm diameter | 50 RMT | | RMT | |
| | d). 150mm diameter | 50 RMT | | RMT | |
| 26. | EUROPIAN W. C. | | | | |
| | Providing, supplying & fixing ceramic coloured European type W.C. of Hindware/Cera make conventional with, PVC seat cover, C. P. brass connector of approved make & standard quality etc. complete as directed. This item includes all the related connections, fixtures at Second floor etc. complete as directed. | 7 | | NO | |

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|----------|---------------------|----------|------|-----|-------------------|
|----------|---------------------|----------|------|-----|-------------------|

27. FLUSH TANK

Providing & fixing PVC flush tank of approved quality and make including fixing in pipe line etc. complete with unions of ISI quality at Second floor as per instruction of architect.

7
NOS

NO

28. WASH BASIN

Providing & fixing white/coloured glazed vitreous china Hindware/Cera make in size 550mm X 440mm with central tap hole with C. I. brackets painted white, 32mm dia. C. P. brass bottle trap with brass union and C. P. brass wall discharge pipe with flanges and cap, 32mm dia. G. I. waste water pipe with fitting up to floor trap, 32mm dia. C. P. brass waste couplin with C. P. chain and rubber plug, having quality flexible PVC inlet connections of required length with brass union, washer and C. P. brass cap etc. complete in all respects including cutting and making good the walls, RCC work and floors at Second floor etc. complete as per instruction of architect.

7
NOS

NO

29. BEVELLED EDGE MIRROR

Providing & fixing 600mm X 450mm beveled edge mirror of superior glass 5.5mm thick of approved quality with 12mm plywood backing and T. W. molding with polishing/painting & fixing with C. P. brass screws at Second floor etc. complete as per instruction of architect.

7
NOS

NO

30. TOWEL RING/ROD

Providing & fixing 6" dia. C. P. brass Napkin ring or 18" to 24" long stainless steel towel rod of approved make and type fixed with screws at Second floor etc. complete as per instruction of architect.

7
NOS

NO

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|---------------------------|--|-----------|------|-----|-------------------|
| 31. SOAP DISPONSER | | | | | |
| | Providing & fixing stainless steel soap dish with fixed to wooden cleats with C. P. brass screws at Second floor etc. complete as per instruction of architect. | 7 NOS | | NO | |
| 32. BIB COCK | | | | | |
| | Providing & fixing 15mmdia C. P. brass bib cock of standard make & quality like Jacquare/Essco/ESS make or its equivalent at Second floor with all fittings & fixtures, accessories etc. complete as directed. | 20 NOS | | NO | |
| 33. PILLAR COCK | | | | | |
| | Providing & fixing 15mmdia C. P. brass pillar cock of standard make & quality like Jacquare/Essco/ESS make or its equivalent at Second floor etc. complete as directed. | 7 NOS | | NO | |
| 34. STOP COCK | | | | | |
| | Providing & fixing 15mm dia. stop cock of standard make & quality like Jacquare/Essco/ESS make or its equivalent at Second floor with all fittings & fixtures, accessories etc. complete as directed. | 7 NOS | | NO | |
| 35. JET SPRAY | | | | | |
| | Providing & fixing 25mm dia. Jet spray cock of standard make & quality like Gem/Essco/ESS make or its equivalent at Second floor with all fittings & fixtures, accessories etc. complete as directed. | 7 NOS | | NO | |
| 36. SHOWER COCK | | | | | |
| | Providing & fixing 25mm dia. shower cock of standard make & quality like jacquare/Essco/ESS make or its equivalent at Second floor with all fittings & fixtures, accessories etc. complete as directed. | 7 NOS | | NO | |

Quotation for : **Proposed Civil work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank. CIVIL WORK**

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|-------------------------------------|---|-----------|------|-----|-------------------|
| 37. NAHANI TRAP | Providing & fixing 100mm dia. three piece stainless steel body Nahani trap of approved quality with 15 X 15 cm. C.P. grating with setting in cement and making good the walls and floors at Second floor as directed. | 10 NOS | | NO | |
| 38. WHEEL VALVE | Providing & fixing copper body control valve of standard make & quality like Gem/Essco/ESS make or its equivalent at Second floor etc. complete as directed. a). 25mm dia. | 7 NOS | | NO | |
| 39. DISMANTLING OF A.C. DUCT | Removing & Disconnecting of exiting A. C. duct from the existing A. C. plant Duct and debris to be stacked at site as per direction of Bank. | 2 NOS | | NO | |
| 40. M. S. WINDOW | Providing new M. S. framed glazed window matching with the existing pattern openable/fixed at appropriate location at Second floor as per direction. | 10 SMT | | SMT | |
| 41. DISPOSAL OF DEBRIES | Shifting of debris, unserviceable material from the premises to out side through tractor etc. as per direction of Bank/Architect. The debris will be shifted from second floor to the ground floor through staircase only and lift will not be permitted for the same. This item also include cleaning the whole site after completion of work. | 1 JOB | | JOB | |

Rs. _____

(Rupees

NOTE : 1. The bidders are requested to visit the premises before quoting the rates.

Name of Contractor with Seal & Signature

Date :

Place :

Quotation for : **Proposed Furnishing work for TRAINEE HOSTEL at Second Floor,
UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank.**
FURNITURE WORK

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|----------|---------------------|----------|------|-----|----------------|
|----------|---------------------|----------|------|-----|----------------|

1. WOODEN BEDS

Providing & erecting required size of wooden bed made from four nos. t.w. section legs with support of seven nos. framing of t.w section size 3"x1.25", peripheral 6" wooden bends and center 10mm thick BWR grade plywood of approved make with head rest shall be finished with 1mm thick laminate of approved make & approved colour shed. Bottom portion of the bed surface & legs will be laquore polished. The entire item will be carried out as per direction of Bank/Architect.

Note : If required wood section material is provided by the Bank, cost of the same will be reimbursed to the Bank by the Vendor.

- For Male & Female Room (900mm X 1800 X 450mm) – 3'-0" X 6'-0" X 1'-6"

18
NOS

NOS

2. WOODEN STUDY TABLE WITH LAMINATE FINISH

Providing & fixing table made from 19mm thick BWR grade plywood of approved make provided with one concealed pencil drawer (1'-0" wide x 1.5" inside clear depth). The top shall be made from 19mm thick BWR plywood of approved make finished with 1mm thick laminate of approved make & approved shade and textures with 1½" X ¾" t. w. border patti as per drawing & instructions, vertical sides shall be finished with 1.0mm thick laminate of approved make & approved shade and textures, the drawer unit shall be provided with

Quotation for : **Proposed Furnishing work for TRAINEE HOSTEL at Second Floor, UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank.**
FURNITURE WORK

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|----------|---------------------|----------|------|-----|----------------|
|----------|---------------------|----------|------|-----|----------------|

one drawer and one openable shutter. The front side of drawer shall be made from 19mm thick BWR plywood of approved make and shall be finished with 1.0mm thick laminate of approved make & approved shade and textures. The sides of drawer shall be made from 12mm thick BWR grade plywood of approved make bottom shall be made of 6mm thick BWR grade plywood of approved make. The rate shall be inclusive of providing locking arrangement by fixing 2 nos. Ebco/Godrej make locks. Provision for Key Board Drawer of Erl. Bihari make, CPU Stand & Cable Manager will be done as per Bank's requirement. All the exposed surface of beading, frame shall be duly laquore polished (matching with the laminate) and internal surface will be painted with flat paint of approved make & shade.

- For Male Room (900mm X 600 X 750mm) – 3'-0" X 2'-0" X 2'-6" 8 NOS NO
- For Female Room (750mm X 600 X 750mm) – 2'-6" X 2'-0" X 2'-6" 10 NOS NO

3. CHAIRS

Providing & supplying ISI standard designed ergonomically & aesthetically good looking chairs. The five pronged base fabricated from M.S. Rectangular metal tube/flat with powder coating. The base diameter should be 600mm & diameter of vertical tube should be 55mm. The revolving mechanism of the chair should be from the bottom with the help of bearing & not with bushes. The roller-castor should be provided.

Quotation for : **Proposed Furnishing work for TRAINEE HOSTEL at Second Floor,
UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank.**
FURNITURE WORK

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|----------|---------------------|----------|------|-----|----------------|
|----------|---------------------|----------|------|-----|----------------|

The tilting mechanism should be of spring action which can take necessary force. The chair should have two polyurethane arms with necessary metal inserts. The seat should have 50mm thick high density (43 kg/m³) U-foam & back should have 38mm thick high density (33 kg/m³) U-foam which will be covered with fabric of Rs. 200/- per Meter of approved quality and shade as per instructions of the Architects.

- For Male & Female room Study Table chair – revolving + tilting (Low back)

18
NOS

NO

4. **WOODEN CUP BOARD WITH SHUTTER**

Providing & fixing wooden cup board (storage units) made out of 19mm thick BWR grade plywood of approved make sides, shelves and front doors and 6mm thick BWR grade plywood of approved make back with teakwood beading to exposed edges. The units shall be finished with 1mm thick laminate of approved make approved colour and shed on front shutter and top. The storage cup cabinate will have necessary two drawers with locks, channels, etc. and wooden shelves as per requirement. All the exposed wooden surfaces shall be duly laquore polished (matching with the laminate) and internal surface will be painted with flat paint of approved make & shade. The shutter back will be finished with 0.8mm thick balance laminate of approved make, color & shade. The shutters shall be provided with Ebco/Godrej make multipurpose locks, SS hinges and approved quality

Quotation for : **Proposed Furnishing work for TRAINEE HOSTEL at Second Floor,
UCO Bhavan, Ashram Road, Ahmedabd for UCO Bank.**
FURNITURE WORK

| Item No. | Description of item | Quantity | Rate | Per | Amount Rs. Ps. |
|-----------|--|----------|------|-----|----------------|
| | handles etc. complete as per direction of Architect. | | | | |
| - | For Male Room (900mm X 600 X 1800mm) – 3'-0" X 2'-0" X 6'-0" | 15 | | SMT | |
| | | SMT | | | |
| - | For Female Room (600mm X 600 X 1800mm) – 2'-0" X 2'-0" X 6'-0" | 12 | | SMT | |
| | | SMT | | | |
| TOTAL Rs. | | | | | ----- |

(Rupees

- NOTE :**
- 1. The size of all the wooden members shown in this tender are NET/CLEAR after planeing.**
 - 2. All the wooden sections & plywood for partitions (or where necessary) will have antitermite paint from inner surface before laying the laminate.**
 - 3. The bidders are requested to visit the premises before quoting the rates.**

Name of Contractor with Seal & Signature

Date :

Place :

[illegible]

ALTERNATIVE - 4

A diagram of a compass rose with a red circle. The word "NORTH" is written vertically inside the circle, and a letter "N" is placed to the left of the circle. A blue shaded sector is shown, bounded by a vertical line and a diagonal line extending to the left.

BIMAL TALATI
ARCHITECTS & INTERIOR DESIGNERS,
304, PRESIDENT HOUSE,
OPP. C.N. VIDYALAYA,
AHMEDABAD - 380 006
INDIA.
PHONE:- (079) 26421682
Email : bimaltalati@gmail.com