

Date: 18/02/2023

Corrigendum in the RFP/NIT Ref. No. HO/GAD/2022-23/4087 date: 03/02/2023 towards Renovation works at Kolkata Main Branch at Ground Floor, Head Office-1, Kolkata-700001.

Following are the clauses of the RFP for which corrigendum has been made.

REVISED B.O.Q OF FOLLOWING ITEMS OF CIVIL WORK - UCO BANK, KOLKATA MAIN BRANCH (GROUND FLOOR)				
B. No.	Page No.	BRICK WORK & PLASTERING WORKS	Existing UNIT	MODIFIED UNIT
B.1	44	10" THK BRICK WALL (Toilet and Kitchen)	CUM	Sq.ft.
		Constructing 10" thk. Brick wall in 1:4 cement mortar. Brick used shall be of best quality kiln burnt, having sharp edges & giving clear ringing sound when struck against each other. Including A 5" R.C.C. lintel Beam shall run horizontally @ 6'-6" ht. The rate shall be inclusive of all materials, scaffolding, curing etc, complete.		
B.2	44	5" THK BRICK WALL (Toilet and Kitchen)	CUM	Sq.ft.
		Constructing 5" thk. Brick wall in 1:4 cement mortar. Brick used shall be of best quality kiln burnt, having sharp edges & giving clear ringing sound when struck against each other. Including A 5" R.C.C. lintel Beam shall run horizontally @ 6'-6" ht. The rate shall be inclusive of all materials, scaffolding, curing etc, complete.		



Assistant Gen. Manager(GA)  
Head Office

