



सममान आपके विश्वास का

Honours Your Trust

NOTICE OF INVITATION TO TENDER

Date: 20.11.2015

Sealed tenders on item/rate over estimated cost basis are invited from competent Interior furnishing designing contractors having sound technical and financial capacity for Interior Furnishing work of **Hardoi Branch and E-Lobby**.

Parties who have not executed one or two work of similar nature, each costing not less than 50% of the estimated cost satisfactorily during last two or three year & does not have any office/site or presence in the U.P. state need not respond.

Note-In case of two part tenders, specific instruction on packaging and superscription of envelopes and date of opening of parts should also give here.

Tender collection: - Tender document may be obtained from 21.11.2015 to 5.12.2015 at 10:00 AM to 05:00 PM from following address-

UCO Bank Zonal Office, Lucknow, B-1/122, Vineet Khand, Gomti Nagar, Lucknow 226010

Tender fee : - **Rs 250=00**

Estimated cost of project: - **Rs. 515270.00**

Time of completion: - 15 Days

Earnest money: - **5153.00** By crossed demand draft/Banker's cheque drawn in favour of **ZONAL MANAGER UCO BANK** payable at **Lucknow**.

Time and date of Submission of tender:- Before 05:00 P.M. on 07.12.2015 at:

UCO Bank, Zonal Office, Lucknow, B-1/122, Vineet Khand, Gomti Nagar, Lucknow 226010

Time and date of Opening of tender :- At 03:00 P.M. on 08.12.2015 at:

UCO Bank, Zonal Office, Lucknow, B-1/122, Vineet Khand, Gomti Nagar, Lucknow 226010

The bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without any reason what so ever.

Dy. Zonal Head

UCO BANK

Zonal Office, Lucknow

यूको बैंक, अंचल कार्यालय, बी-1/122, प्रथम तल, विनीत खण्ड, गौमतीनगर, लखनऊ 226010
UCO Bank Zonal Office, Lucknow, B-1/122, 1st Floor, Vineet khand, Gomtinagar, Lucknow 226010
ई-मेल/ E-mail - zo.lucknow@ucobank.co.in



GENERAL RULES AND INSTRUCTION FOR GUIDANCE OF TENDERERS

- (1) Tenders are hereby invited on behalf of **UCO BANK, LUCKNOW ZONE** for Interior Furnishing of **Hardoi Branch including E-Lobby** and estimated cost of **Rs.515270.00**
- (2) Contract documents consisting of the plan, complete specification, the schedule of quantities of the various classes of work to be done, and the set of conditions of contract to be complied with by the persons whose tenders may be accepted, and which will also be found in the form of tenders can be purchased from **UCO BANK ZONAL OFFICE LUCKNOW** Between the 10:30 AM to 05:00 PM every day, except on Sunday and Bank Holiday (Saturday till 02.00 PM).

The site for the work is available/The site for the work shall be made available in parts as specified below.
- (3) Tenders, which should always be placed in sealed cover, with the Name of project written on the envelopes will be received by **UCO BANK ZONAL OFFICE LUCKNOW** up to 5:00 PM on 07.12.2015 and will be opened by him in his office at 03:00 PM on 08.12.2015.
- (4) Tenders are to be on the prescribed form which can be obtained from **UCO BANK ZONAL OFFICE LUCKNOW**. The time allotted for the carrying out of the work will be 10 Days from the next day after the date of written orders to commence work.
- (5) The contractors should quote rate and amount in figures as well as in words tendered by them. The amount of each item should be worked out and requisite totals given.
- (6) Contractors should signs & stamp on each page on tender papers and submit it.
- (7) The last date of Issue of tender form will be on 05.12.2015 up to 05:00 PM.
- (8) Earnest money Rs.5153.00 in the form of Bank draft/Banker's cheque in favour of **ZONAL MANAGER UCO BANK** must accompany with each tender and each tender is to be in a sealed Envelopes super scribed on it "**TENDER FOR (Name of the Project)**" and addressed to :-

**ZONAL MANAGER
UCO BANK ZONAL OFFICE,
B-1/122, Vineet Khand,
Gomtinagar,
Lucknow 226001**

- (9) The contractor whose tender is accepted will be required to furnish by way of security deposit for the due fulfillment of his contract, such sum as will amount as follow-
 - (a) 10.00% on the first Rs 100000/- of the cost of work.
 - (b) 7.50% on the next Rs. 100000/- of the cost of work.
 - (c) 5.0% on the next amount up to Rs. 2.0 crores of the cost of work.
 - (d) 2.0% for the amount in excess of 2.0 crores of the cost of work subjected to a ceiling on the total security at 25.0 Lakh.

यूको बैंक, अंचल कार्यालय, बी-1/122, प्रथम तल, विनीत खण्ड, गोमतीनगर, लखनऊ 226010
UCO Bank Zonal Office, Lucknow, B-1/122, 1st Floor, Vineet khand, Gomtinagar, Lucknow 226010
ई-मेल/ E-mail - zo.lucknow@ucobank.co.in



The EMD of the contractor, whose tender is accepted, shall be forfeited in full in case he does not remit the Initial security deposit within the stipulated period or start the work by the stipulated date mentioned in the award letter.

- (10) The acceptance of a tender will rest with the UCO BANK LUCKNOW ZONE which does not bind itself to accept the lowest tender, and reserves to itself the authority to reject any or all of the tenders received without the assignment of a reason. All tenders in which any of the prescribed condition are not fulfilled or are incomplete in any respect are liable to be rejected.

The Bank reserves the right to accept the tender in full or in part and the tenders shall have no claim for revision of rates or other conditions if his tender is accepted in part.

- (11) Canvassing in connection with tenders is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.
- (12) All rates shall be quoted on the proper form of the tender alone.
- (13) An item rate tender containing percentage below/above will be summarily rejected, However where the tenderer voluntarily offer a rebate for payment within a stipulated period, this may be considered.
- (14) On acceptance of the tender, the name of the accredited representative of the contractor who would be responsible for taking instruction for the Employer/Architect shall be communicated to the employer.
- (15) Special care should be taken to write the rate & amount in figure as well as in words in such away that interpolation is not possible. The total amount should be written both figures and in words. In case of figures the words Rs. should be written before the figures of rupees and words after the decimal figures. Example Rs. 2.15P, and in case of words, the word "Rupees" should precede and the word "paisa" should be written at the end, unless the rate is in whole rupees and followed by the words "only". It should invariably be up to two decimal places. While quoting the rate in schedule of quantities, the word "only" should be written closely following the amount and it should be not be written in the next line.
- (16) The bank does not bind itself to accept the lowest or any tender and reserves to itself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the quoted rate.
- (17) The rate quoted by contractor includes all tax & royalty like sales tax, V.A.T, contract tax, turn over tax etc. The bank will not entertain any claim whatsoever in this respect.
- (18) The contractor shall give a list of his relatives working with the Bank along with their designation and addresses.
- (19) No employee of the Bank is allowed to work as a contractor for a period of two years of his retirement from the Bank service without the previous permission of the Bank. The contract is liable to be cancelled if either the contractor or any of his employees is found at any time to be such a person who has not obtained the permission of the Bank as aforesaid before submission



such a person who has not obtained the permission of the Bank as aforesaid before submission of the tender or engagement in the contractor's service.

- (20) The tender of works shall remain open for acceptance for a period of two days from the date of opening of tenders if any tenderer withdraw his tender before the said period, then the Bank shall be at liberty to forfeit his earnest money paid along with the tender.
- (21) The tender for the work shall not be witnessed by a contractor or contractors who himself/themselves has/have tendered or who may and had/have tendered for the same work failure to observe this condition would render tenders of the contractors tendering as well as witnessing the tender liable to summary rejection.
- (22) It will be obligatory on the part of the tenderer to tender and sign and tender document for all the component part and that after the work is awarded, he will have to enter into an agreement for each component with the competent Authority in the Bank.
- (23) The tenderer, apart from being a competent contractor must associate him self with agencies of the appropriate class who are eligible to tender for (a) Interior (b) sanitary & water supply installation and (c) AC.



Dy. Zonal Head




LIST OF APPROVED MATERIALS/MANUFACTURERES

<u>DESCRIPTION</u>	<u>MAKE</u>
Board / Ply (BWP)	: Green/ Duro/Century
Laminate (1.0mm th)	: GreenLam/ Formica/ Century
Door Closer / Floor spring	: Everite, Godrej, Hemaco
Drawer & Keyboard, Slide	: Ebco (Telescopic)
Glue for fixing	: Fevicol (Pidilite), Jivanjor
Glass	: Modi Float, Saint Gobain
Mortice Latch & Lock	: Godrej, Golden Industries Ltd.
Aluminium Sections	: Jindal / Indal / Hindalco
False Ceiling	: Gypsum marked "Gypsteel", Lafarge
Synthetic Enamel	: Asian, Nerolac, ICI, Berger
Emulsion Paint/Plastic Paint	: Asian, Nerolac, ICI, Berger
Screws	: Nettlefold / G.K.W.
Vitrified Tiles	: Naveen/Somany/Euro
Ceramic Tiles	: Naveen/Asian/Euro
Wood	: IInd Grade teak wood

Note: Material used other than above mentioned items must be approved from the Architects/ Bank.

यूको बैंक, अंचल कार्यालय, बी-1/122, प्रथम तल, विनीत खण्ड, गौमतीनगर, लखनऊ 226010
UCO Bank Zonal Office, Lucknow, B-1/122, 1st Floor, Vineet khand, Gomtinagar, Lucknow 226010
ई-मेल/ E-mail - zo.lucknow@ucobank.co.in




Gunjan and Associates.
Architects, Engineers, Interiors &
Landscape Designers.
141, Sainik Nagar,
Raebareli Road, Lucknow-226002
Phone: 9838818489, 9839018489
E-Mail: arunjan@yahoo.com

**Bill of Quantity for Furnishing works for UCO BANK
at Hardoi Branch and E-Lobby**

- 1.No offsite prefabrication shall be allowed in any case. All fabrication shall be done at the site after getting the materials inspected by the architect
- 2.No payment shall be made for any in completed or unsatisfactory work
- 3.The Contractor should strictly follow the Booklet requirements of the Bank including the detailed drawings in the booklet. Any discrepancy between the booklet and the Specifications below should be brought to the notice of the
- 4.List of material to be strictly as per the booklet.
- 5.Cable Managers to be provided in the tables and Counters wherever required.
- 6.All underframe should be properly treated with antitermite and waterproofing material
- 7.All Locks in the drawers and doorsets. should be of Godrej
- 8.All keyboard Trays and Drawers to be on Channel Sliding Mechanism.
- 9.Etching to be provide as per Banks Design and Specification.

S.No.	Item	Units	Qty.	Rate	Amount
	In case of full height partitions measurement of height shall be taken from the finished floor level upto the level of the false either side of the partition ceiling, in case of varying heights on average height shall be considered.				
	The rate to include provision of extra framework as necessary for skirting & making provision for laying conduit as/drg & directions of site engr./architect. All underframing to be treated with antitermite solution chlorpyrifos based in recommended dilution.				
1	Wooden Partitions (partly glazed and Doors).	Sq. ft.	195.00		
	Providing and fixing of wooden partitions made out of 50mm x 40mm kail / chair wood (with anti- termite -Trishul/Pentaphene(STP)) under framing for horizontal (at 0mm, 75mm, 750mm, 900mm, 1500mm, 2100mm, 2550mm and ceiling levels) & vertical (at 600mm c/c approx.) divisions or as per site conditions. It shall be covered with 6mm thick water proof ply (Archid/Century) with 1mm thick laminate, (from 0mm to 750mm and 2100mm to 2550 mm/ceiling levels) on both sides. The design shall have 6mm x 4mm grooves (horizontal or vertical) at various levels, as suggested by the Architect.				
	It shall have 8mm thick float glass (from 900mm to 2100mm) fixed with teak wood beading (size - 30mm x 20mm, as per profile) with melamine finish. The job shall also include for provision of laying conduits, switch boxes etc. The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete up to the satisfaction of the Architect.				
	All door opening shall have rebated teak wood framework (size - 75mm x 50mm, as per profile) on vertical (2 Nos.) and horizontal (1 No.) sides, with melamine finish and rebate of 40mm x 12mm, all complete up to the satisfaction of the Architect.				
	It shall also include for door shutters, as per required width and 2100mm high. It shall be made out of 75mm x 25mm kail/chir wood (with anti-termite) under framing for styles, top, middle and 100mm x 25mm for bottom rail. It shall be covered with 6mm thick water proof ply with 1mm thick laminate, (from 0mm to 900mm and other under frames) in shade and pattern approved by the Architect, on both sides. The design shall have 6mm x 4mm grooves (horizontal or vertical) at various levels, as suggested by the Architect.				
	the partition and doors shall have hinges floor springs/sliding arrangement/hydraulic door closer, mortise locks (Godrej make all), etc. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to the satisfaction of the Architect.				
P-2	Full Height unglazed Partition				




	Same specification as in 1 but P/F full height unglazed partition upto the false ceiling with the same specs.as above without glass for partition.	Sq. ft.	70.00		
P-3	Low Height Partition				
	Same specification as in 1 but P/F half height partition of height 4'-6" with wooden laminate till 3'-0" and 1'-6" height 12 mm thick glass secured with D brackets including all hardware necessary with the same specs.as above.	Sq. ft.	90.00		
P4	P4-(Full Ht.7'-0" but for Cash Cabin)	Sq.Ft.	150.00		
	(Cash Cabins)				
	Solid till 4'-0" then GLASS height till 6'-6" then again solid				
	Decorative Grill (12mm thk)-hexagonal opening as per instruction of Bank's Engineer/Architect. All exposed edges of Plywood shall be fixed with 1/8" C.P. Teak				
	Other Specification as per partition P1				
	FRONT COUNTER AND CASH COUNTER				
2(C1)	FRONT COUNTER	Rft	15.00		
	Providing & Fixing clerical counter made out of 19.0mm thick ply (as per list of materials) frame work for top, verticals, shelves, apron, sides, drawer unit, shutters, side units, customer top, foot rest, 12.0mm thick ply(as per list of materials for drawer sides, sliding shutters, front apron & 6mm thick ply for side unit back, drawer bottom, drawer unit back along with necessary 2" X 2" or 2" X 1.5" of laminate matching imported wood molding & teak wood supports for fixing of top. The clerical counter shall have 2'-6" in depth & counter shall have two tops i.e. one at 2'-6" for writing and second at 3'-0" for customer in height finish in approved make/color 1.0mm thick laminate etc. complete. The clerical counter shall have 1 No. of key board tray, 2 Nos. of equal drawers or as per the Bank requirements & one open able shutter. All exposed surfaces i.e. apron, counter side etc. finish with approved make/color 1.00mm thick laminate & moulding finish with 3 coats of melamine polish and internal surfaces shall have zinc oxide polish along with necessary approved Stainless Steel				
	Hinges, Ball Catches, Stainless Steel Locks, approved design Stainless Steel Handles, Stainless Steel Powder Coated Grommet (wire manager), Wood Foot Rest (Movable) Earl Bihari make Twin Telescopic Channel, CPU Hanger/Trolley INNOFIT make etc. complete as per detail drawing and Instructions of the Bank's Engineer/Architect				
	this item shall have hinges floor springs/sliding arrangement/hydraulic door closer, mortise locks (Godrej make all), etc. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to the satisfaction of the Architect.				
C2-	Cash Counter				
	Do as above item no. C1 (No side table) cash counter shall have two tops i.e. one at 2'-6" for writing top & other 4'-0" for customer top. upto 7'-0" height (Full front portion and writing top made of 12.0mm ply(as per list of materials) and 3", 12.0mm plain glass slit on customer top) on and above writing top 12 mm plain Glass till 7'-0" should have necessary wooden support and opening edge with proper polish finish for cash and voice transaction.	Rft	5.00		
3	12 MM THICK GLASS FOR CASH CABIN'S AND FRONT COUNTER				
	Providing & fixing 12 m.m. glass in front of cash cabin and front counters with brass clamps including cut out for passing currency as/details.The edges of the glass to be machine polished.	Sq. ft.	35.00		
4	Wicket Gate Solid	No.	1.00		
	(Banking Hall) SS finish Hinges				
	Size-3'-0" X 4'-6"				
	Board-19mm thick (MR Grade IS303)				
	(Incl Door Closer/Stopper/mortice lock)				
5	Entrance door Toughened with glazing toughened FOR E-LOBBY)				

10



	Providing and fixing of door with side panel with 12 mm toughened glass complete with Ozone Patch fittings including Top Patch (OPF-02)Bottom Patch(OPF-3)Angle Lock(OPL-1)Top Pivot (OFS-ACC-GDP)Floor Spring (FS8400)and handle(OGH)32x457	sqft	25.00		
6	Entrance door Toughened with glazing toughened FOR BRANCH)				
	Providing and fixing of door with side panel with 12 mm toughened glass complete with Ozone Patch fittings including Top Patch (OPF-02)Bottom Patch(OPF-3)Angle Lock(OPL-1)Top Pivot (OFS-ACC-GDP)Floor Spring (FS8400)and handle(OGH)32x457	NO.	85.00		
	False Ceiling				
7	False Ceiling(Armstrong)	Sq.Ft.	500.00		
	Providing & Fixing <u>Armstrong (Fine Fissured Micro Look with Tagular Edge using 15.0mm Grid sections)</u> false ceiling of size 24"x24" at levels as shown in the drg. Rate shall be inclusive of providing the total system with installation etc. Contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations.Rate shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills etc.(Note - : Only the plan area will be measured for the purpose of contractor 's payment , no extra payment shall be given for design)				
8	False Ceiling Works (Gypsum)	Sq.Ft.	400.00		
	Providing & fixing with necessary scaffolding frame in 22 gauge GI channel /angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners /screws finished with 12.0mm Gypsum sheets joints covered with POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and two coats of acrylic paint). Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop upto 1'6" etc. (Note - : Only the plan area will be measured for the purpose of contractor 's payment , no extra payment shall be given for design)				
9(S-1)	Storage (Low Height & Full Height) with locks	Sq.Ft.	35.00		
	Size-2'-6" highX 1'-6" deep,8'-6" highX 1'-6" deep				
	Ply Wood-19.0mm thick board for side top and door & back 6.0mm IS 303 with shutters, shelf 19.0mm ply				
	Shelf-19.0mm thick ply				
	Handle-Brush finish stainless steel				
	Lock-Vijayan/Godrej				
	Internal surface zinc oxide polish and other required accessories instructed by Bank's Engineer/Architect.				
S2	Storage (Over Head Storage)with locks	Sq.Ft.	20.00		
	Size-2'-0" highX 1'-6" deep				
	Ply Wood-19.0mm thick board for side top and door & back 6.0mm IS 303 with shutters, shelf 19.0mm ply				
	Shelf-19.0mm thick ply				
	Handle-Brush finish stainless steel				
	Lock-Vijayan/Godrej				
	Internal surface zinc oxide polish and other required accessories instructed by Bank's Engineer/Architect.				
10(T)	Manager Table with Side Table	No.	1.00		
	Same as above complete work including 12 mm thick glass on top.				
	Size-6'-0" X 3'-0" X 2'-6"				
	Side Table-3'-0" X 2'-6" X 1'-6"				
	Ply Wood-19.0mm thick for frame work				
	Supports-2" X 2" & 2" X 1.5" CP Teak Wood and beading Patti				

	Drawer-1'-6" wide two drawers and one shutter below the drawers at left side of the table and two drawers at side table and below two shutters				
	Laminate-1.0mm thick approved colour				
	Key Board Tray-Metal INNOFIT make				
	CPU Metal Stand, Twin Telescopic Drawer Fittings, Brass Powder Coated Wire Manager				
	Foot Rest-12.0mm thick Ply tapered box finish with polish				
	Handle-Brush finish stainless steel, Brass Ball Catches				
	12.0 thick plain glass with edge polish at top of the table (Other Exposed Edge of Ply with half round beading with approved colour polish)				
t-2	Officer Table with Side Table	No.	0.00		
	Same as above complete work including 12 mm thick glass on top.				
	Size-5'-0" X 2'-6" X 2'-6"				
	Side Table-3'-0" X 2'-6" X 1'-6"				
	Ply Wood-19.0mm thick for frame work				
	Supports-2" X 2" & 2" X 1.5" CP Teak Wood and beading Patti				
	Drawer-1'-6" wide two drawers and one shutter below the drawers at left side of the table and two drawers at side table and below two shutters				
	Laminate-1.0mm thick approved colour				
	Key Board Tray-Metal INNOFIT make				
	CPU Metal Stand, Twin Telescopic Drawer Fittings, Brass Powder Coated Wire Manager				
	Foot Rest-12.0mm thick Ply tapered box finish with polish				
	Handle-Brush finish stainless steel, Brass Ball Catches				
	12.0 thick plain glass with edge polish at top of the table (Other Exposed Edge of Ply with half round beading with approved colour polish)				
11	Writing Table & Brochure Holder , Cheque Drop Box ,Suggestion Box with Notice Board .(The work shall be executed as per design and Elevation.)Branch	No.	1.00		
	Providing and fixing in position a writing counter with open storage made of 12mm and 19mm thick ply/ commercial board finished with 1.0mm laminate and teak wood moulding/ lipping with a 6mm glass top with polished edges as per drawing and design. The glass to be of size to fit internally and the 19mm border and 6mm lipping to be flushed with the glass. The storage unit shall consist of vertical space dividers of 12 mm board with 1.0 mm laminate till the glass top for the provision of holding withdraw/ deposit slips stationery etc. The counters to be held in position around the columns by dash fasteners at a height of 3.5/ 4 ft. Notice board with cellotex base & cloth bound in corporate coloured binded with teak wood lipping of 35 by 12 mm.size 1500X1200.All wooden surfaces to be finished in clear melamine polish and all unexposed sides to be finished in enamel paint of approved colour to be approved by the designer all complete				
12	Column Pannelling, meter boxing, wall panelling	Sq.Ft.	550.00		
	Providing & fixing in position 2"x2" kailwood frame and finished with 6 mm thk.ply(as per list of Materials) on both sides with 1.0 mm thk. Laminate on top as per instruction of the Architect				
13	Printer And Server Unit	NO.	1.00		
	Providing and placing in position printer & server unit of size – 1050mm x 375mm x 675mm. The top, vertical sides/dividers, skirting, bottom and intermediate shelves shall be made out of 19mm thick water proof board (Archid/Euro make)with 1mm thick laminate (Sunmica/Archid make) (As/shade approved by the Architect) on all exposed surfaces.				
14	Acrylic Emulsion with POP Base.(FOR AC AREA)	Sq.Ft.	1210.00		
	Painting on undecorated / decorated wall and ceiling surfaces with two or more coats of acrylic emulsion(Asian/ Berger make) (as / shade approved by the Architect) of approved brand. It shall include for preparing the surfaces clean, even and smooth with thoroughly brushing with broom, scratching with patti and sand papering respectively, so that the surfaces are free from oil, grease, dirt, mortar droppings & other foreign and loose matter. It shall also include for preparing the surface and filling of holes with plaster of paris before priming coat of whitening / approved primer.				



	The rate shall include cost of all materials such as plaster of paris, whitening /primer, glue (Fevicol), indigo / stainer, brushes, sand paper, patti, dhoti, broom stick, clean water with storage and other containers, labour, scaffolding / ladder charges, cleaning of floors and other sundries etc., all complete to the satisfaction of the Architect.				
15	Aircon Louvers				
	P and F 6" powder coated aluminum louvers of approved color.	Unit price	1.00		
16	PILLAR LOCK (FOR E-LOBBY)				
	Providing And fixing Access lock pillar comprising of 12 mm IS 303 ply finished with 1mm laminate.	NO.	1.00		
17	Wall Paneling (OUTER WALL) AND Shutter Boxing with Aluminum Composite Panel	95.00	Sq.Ft.		
	ACP Panneling & Rolling Shutter Box.				
	Frame Work-2" X 2" X 1.5 mm thick Aluminium Tubular section (Horizontal/Vertical)				
	Jindal Make				
	Aluminium Composite Panel-3.0mm thick of approved colour with bonding material				
18	Suggestion Box(FOR E-LOBBY)	1.00	job		
	providing & fixing Acrylic Make with shutter, lock and white mat film finish, complete as per instruction of Bank's Engineer/Architect				
19	POSTER FRAMES -WALL MOUNTED(FOR ATM)				
	2 sheets of 36" x 24" clear acrylic (poster to be sandwiched in between). Outer sheet is 5mm thick and bevelled crystal edge polished for 3/4" at 8-10 degrees on all sides in the front.Rear sheet is 5 mm thick flat.	1.00	NOS		
20	TOUGHENGED GLASS WITH STEEL CLAMP(FOR E-LOBBY)	45	SQFT		
	TOTAL				



UCO BANK**LIST OF MATERIALS OF APPROVED BRAND AND/OR MANUFACTURER**

1. The contractor shall use materials in their work subject to inspection, prior to dispatch, by Owner or his authorized representative of any materials not otherwise specified, shall be in accordance with the following list. All materials not otherwise specified shall be in accordance with the latest Indian Standard Specifications, where such exists with prior approval of Owner /Architects. The contractor shall be bound to offer sample of materials, which are claimed to be conforming to I.S Specification, for testing at an approved testing laboratory.
2. Contractor shall purchase all materials from the makers or their authorized stockist only. Necessary documentary evidences must be produced to the Owner or their authorized representative on demand.
3. Contractor shall be bound to supply items or any make of the items as per the choice of the Owner/ Architects.

A FURNISHING WORK

S.No	Description	Approved Brand/ Manufacturer
1.	Texture /PAINT	Spectrum , Heritage, Acro paint
2.	Wood	First class Steam beach wood or as specified
3.	Polish	MRF Polyurethane
4.	Termite treatment	Chloroporyphos 20% concentration / Dusban /Terminator pidlite make
5.	Soft Board	Celotex
6.	Flase Ceiling and Sections	Grid Tiles ---Armstrong, St Gobain Gypsum India,
7.	Aluminium sections	Hindalco, Jindal, Indal
8.	Vitrified Floor tiles	RAK Asian, Regent, Kazaria, nitco
9.	Block boards / Plywood/Flush doors	M/s Green, Duro , M/s Archid, M/s Century, No alternate brands from the same manufacturer allowed
10.	Laminates	M/s Green, lam (New Mika),M/s Merino, M/s Heritage, M/s Century, M/s Archid SANMICA-1758,1213,1769,
11.	Hardware-(Aluminium)	Approved design, brand, quality & manufacture allowed
12.	Hardware	ALL HARDWARE TO ONLY GODREJ
13.	Drawer/ cabinet Handless/locks	Dorset / Kitch/ Godrej/ hettich
14.	Magnet Catcher	Supreme, Excel
15.	Drawer / cabinet shutter Accessories	Ebbco, Hettich, Hafele
16.	Synthetic Enamel Paints, Distemper or Plastic paint Best quality of make as approved	Asian Paints Ltd), Berger Paints (India) Ltd.(Luxol), ICI, Nerolac.
17.	Venetian blinds/ verticals	vista
18.	Glazing	M/s Modiguard, M/s asahi india, Saint Gobain.
19.	Door Closer/ floor spring	Godrej, Dorma, Ozone
20.	Glue Addhesive	Fevicole, Century
21.	Door handles/ Locks	Godrej
22.	Screw	Excel GKW
23.	Glass brass bracket	Flora, Perfect
24.	POP bag or readymade work	Diamond (Super fine quality)
25.	GI section for Partitions, Panel, false ceiling	Same Company as of Gypsum Bard or Mineral Fibre tiles
26.	Film	Alkor, Garware, 3M
27.	Plants	
28.	Wire management holes	Twinkle
29.	Cement Board	E board, Bison,
30.	Vitrified floor tiles adhesive / Grout	Bal Endura, Dr. Fixit Fevimate XL with Polymer Modified Mortar, ROFF Granite tile adhesive

2

