

अंकावा/यो. एवं वि./ ZOV/P&D/2015-16 /
2015

Date 26-08-

निविदा सूचना / TENDER NOTICE

विनिर्दिष्ट के अनुसार वस्तुओं के दर हेतु मुहरबन्द निविदायें आमंत्रित हैं/ Sealed items rate tenders are invited for the works noted hereunder:

अ.क्र./S.N	कार्य का विवरण Name of work	कार्य- स्थल/Location of work	अनुमानित लागत/Estimated cost
1.	बालापुर, रानीगंज कैथोला, अमरगढ़, पहाड़पुर, अर्रो, लवाना और मऊ के एंटी-एम० में आंतरिक साज-सज्जा का कार्य/ Interior & furniture work at Balapur, Raniganjkaithola, Amargarh, Paharpur, Arro, Lavana and Mau ATM	बालापुर, रानीगंज कैथोला, अमरगढ़, पहाड़पुर, अर्रो, लवाना और मऊ / At Balapur, Raniganj kaithola, Amargarh, Paharpur, Arro, Lavana and Mau	Rs38,000/- (+applicable service tax) for each ATM of 80sqft approx which may vary as per actual size of ATM room on spot.
2.	बालापुर, रानीगंज कैथोला, अमरगढ़, पहाड़पुर, अर्रो, लवाना और मऊ एंटी-एम० में विद्युत कार्य/Electrical work at Balapur, Raniganj, Amargarh, Paharpur, Arro, Lavana and Mau ATM	राबर्टसगंज, जनपद सोनभद्र बालापुर, रानीगंज कैथोला, अमरगढ़, पहाड़पुर, अर्रो, लवाना और मऊ / At Balapur, Raniganj, Amargarh, Paharpur, Arro, Lavana and Mau	Rs26,000/- (+applicable service tax) for each ATM of 80sqft approx which may vary as per actual size of ATM room on spot.

निबन्धक एवं शर्तें/Terms and conditions:

- सभी एंटी-एम० का कार्य की पूर्ति हेतु समय : 15 दिन / Time of completion of work : 15 days.
- अर्नेस्ट मनी डिपोजिट: निविदा जमा करने के समय पे आर्डर/डी.डी./बैंकर्स चेक के रूप में अनुमानित लागत का 1% Earnest money deposit : 1% of estimated value at the time of submission of tender in the form of Pay order/ DD/Banker's cheque.
- आरम्भिक अभिरक्षा जमाराशि : सफल बोली लगाने वाले की अर्नेस्ट डिपोजिट मनी को शामिल करते हुये अनुबन्ध राशि का 2% / Initial security deposit : 2% of the contract value including the EMD by successful bidder.
- सफल बोली लगाने वाले के द्वारा जमा अर्नेस्ट मनी डिपोजिट एवं आरम्भिक अभिरक्षा जमा राशि, अनुबन्ध की अभिरक्षा राशि व रिटेंशन मनी के एवज में समायोजित कर ली जायेगी / The EMD and ISD so deposited by the successful bidder, will be adjusted with the security deposit/ retention money for the contract.
- क्षतिपूर्ति वहन अवधि : कार्य के वास्तविक समापन से छ माह की अवधि तक / Defects liability period : 6 months from date of virtual completion of work.
- निविदा के जमा करने का अंतिम समय एवं तिथि : 11-09-2015 को अपरान्ह 2.00 बजे / Time and last date of submission of tenders : 2.00 PM on 11-09-2015
- निविदा खोलने का अंतिम समय एवं तिथि : 11-09-15 अपरान्ह 4.00 बजे / Time and last date of opening the tenders : 4.00PM on 11-09-15
- जमा करने का स्थान : यूको बैंक , अंचल कार्यालय, डी-63/8-1, एम, धनश्री काम्प्लेक्स, महमूरगंज, वाराणसी-221010 / Place of submission : Uco Bank , Zonal Office D-63/8-1-M, Dhanshree complex, Mahmoorganj-Varanasi-221010.
- बिना कोई कारण बताये किसी व सभी निविदाओं को स्थगित करने व निरस्त करने का अपना अधिकार बैंक के पास सुरक्षित है । सभी निविदाये, जिसमें निर्दिष्ट कोई शर्त पूरी नहीं है या किसी भी रूप में अपूर्ण है, निरस्त की जा सकती हैं / Bank reserves its right to postpone / reject any or all the tenders without assigning any reason what so ever. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- सेवा कर नियमानुसार लागू होगा Service tax applicable as per norms.
- Only empanelled contractors can submit tenders.

अंचल प्रबन्धक/Zonal Manager

यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010

UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi – 221010

Phone: 0542-2221723, 2223323, Fax – 0542- 2223123

e-mail: zo.varanasi@ucobank.co.in

Ref No.: BA/41/4018/2015-16

Dated :

**DETAILED ESTIMATE / SPECIFICATION OF ATM
FURNISHING & ELECTRICAL WORK OF UCO
BANK(Various Branches)**

A- FURNISHING WORK :

Sl.no	Description of items	Unit	Qty.	Rate	Amount
1.0	Providing and fixing Vitrified Tiled Flooring 1st quality polished 24"x24" with 4" skirting of Johnson /Bell/Naveen Ceramics or equivalent make fixing make. Fixing in cement sand ratio 1:5 in line and level inclusive of wastage, cutting and joints filling with white cement skirting to be flush with POP with 6mm groove between POP and skirting Johnson- (Parleto) Including	SFT	0.00		
2.0	P/F suspended False Ceiling Gyp Board with G.I. Perimeter channels G.I. Intermediate Channels Etc. properly suspended from ceiling with Nylon/G.I. strips sleeves and Screws 12.5 Mm tapered edge Gyp board (confirming To I.S.2095-1982) ceiling tiles to be screw Fixed to the ceiling section with 25mm dry Wall screw mechanically at 230C/C and Finished with jointing compound paper tape And two coats of primer and two coats Of plastic paint complete as per design Including perimeter channels required for	SFT	75.00		
3.0	Providing and fixing Glass Main Door at the entrance door (approx.size 3'-6"x7') made out of Sal wood with top and middle runner Of section size 4" X 1.5" while bottom Runner to be of 6"x1.5" size. The two vertical members shall be of 4"x1.5" section. The frame shall be covered with 4mm ply And 1.0 mm laminate. The glass shall be 8 mm th. Clear plain glass with anti shatter film fixed on it The door shall be fixed to floor on a floor spring. The work to include providing and fixing of Floor Spring & Handle – 2 nos.)	SFT	24.50		

4.0	Providing and fixing External Fixed Glazing made out of Sal wood with top runner of section size 4"x 1.5" while bottom runner to be of 6"x 1.5" size. The two vertical members shall be of 4"x 1.5" section. The frame shall be covered with 4 mm ply & 1 mm the laminate. The glass shall be 8 mm th clear plain glass with anti-shatter film fixed on it.	SFT	20.00		
5.0	Providing and fixing Card Access Pillar of size 6"x 6" (Out-out) dimension comprising of 12mm ply, finished with 1.0 mm laminate appropriate slot to be made for card access unit. Unit – nos.	No.	1.00		
6.0	P/ F wooden Cabinet 1'-0" deep to be fixed on the wall frame made out of 19mm thick commercial ply with hinge shutters made out of 12mm thick ply with 1.0mm laminate on the front & side other internal surface to be painted as complete with handle, lock, Magnet etc. size 1'-9" x 2'-3"x1'-0"	SFT	5.00		
7.0	Providing and fixing wooden shutter boxing comprising of 2"x 2"sal wood frame work,12mm marine plywood,trapdoor with sal wood lipping patti,flush tower bolt on trap door , shutter boxing finished with 1.0mm thk.Laminate fixed over it. The mode of measurement shall be of total running ft. Size	RFT	10.00		
8.0	Providing and placing in position Cheque Drop Box as /design made out of 3 layers of 4mm th.commercial ply on side walls and 19mm th.top and bottom surface. Height of the box to be 2'-6" with 4 no.spacer of 4 inch ht fixed on top to support 10mm th plain glass of 1'-6" dia over it. The box shall be covered on all surface with 1.0 mm thk laminate. It shall have slit have slit in the front for dropping cheque. door to provide on the back	No.	1.00		
9.0	Providing & applying Plaster of Paris of Superfine grade, average thickness 5mm on plastered wall, level pads to be made before application to be done with aluminium pipe	SFT	298.00		

10.0	Providing and applying Plastic Paint on wall & Ceiling surface with three coats of Asian / Nerolac/ ICI / JNN with surface preparation primer And putty complte. as directed by the Architect.	SFT	325.00		
11.0	Providing and applying Enamel paint three coats of 1st quality white enamel paint including scraping the surface clean, primer & putty complte.	SFT	80.00		
B- ELECTRICAL WORK :					
12.0	Providing & fixing Philips make recessed mounting lumineires with 595x595mm mirror optic design for ceiling mounting system tubelite (CAT. No.FBS 300/236 P5 – 2 X PL-L 36Watt) Philips Make.	No.	1.00		
13.0	P/F of point wiring 5Amp controlling switch modular type, including 1.5sqmx2 +1x1sqm multy stand red PVC insulated copper wire in suitable size PVC conduit & M.S box plate including 2x2.5+1x1sqmm circuit wiring switch	No.	5.00		
14.0	S/F 15Amp switch & 15 amp Socket including 2x2.5sqm +1x1sqm Multi standard copper wire in suitable size PVC conduit & M.S box front	No.	2.00		
15.0	S/F 3 No. 5 Amp socket & 3 No controlling switch including M.S box cover plate & top plate, 2x1.5sqm+1x1sqm multy stand Wire in suitable size PVC conduit, switch board to MCB MB(each switch board separate circuit.) with wiring	No.	2.00		
16.0	S/Laying 4sqmmx4core copper Armored Cable Branch Main Panel to ATM main panel.(ATM main cable connect to branch main panel DG Bus Bar & 2nd main cable connect to UPS.)	Mt.	20.00		
17.0	S/F of Down Light fitting Glass Type 2 x18 watt including CFL make Phiips	No.	2.00		
18.0	Providing & installation of 4 way SPN D.B. including 32 Amp DP & 2 No.16 Amp SP MCB .of Havell's MDS make.	No.	1.00		

19.0	S/F PVC Type 8" Dia Louver Type Fresh Air Fan Heavy Duty Make Havells, Khaitan	No.	1.00		
20.0	S/F of Ceiling Fan 24" Dia including down rod & regulator.	No.	1.00		
			Total Rs.	0.00	

Total Rs A+B

Say Total Rs.

Specifications of Materials

S.No.	Item	Make/ Specifications
1.0	Ply board	Green, Century, Archid 100% boiling water proof, 100% Termite proof
2.0	Laminate (Plane colour)	Greenlam, Century Mica, Archid Lam, Marino
3.0	Adhesive	Fevicol- SH
4.0	Aluminium section	Jindal, indal, Hindalco
5.0	Door closer/Floor spring	Everite, Henco, Hyper
6.0	Hinges/drawer slides	Earl-Bihari Pvt.ltd.
7.0	Vinyl flooring/Tiles	Bhor (Marblex), Armstrong.
	1'-0"x1'-0"	
8.0	Mortice latch and lock	Godrej
9.0	Venetian blinds (vertical/horizontal)	Vista, Luxaflex.
10.0	Upholstrey	Bhor Bilbio.
11.0	Exhaust fan	Usha
12.0	Glass.	Modi float- 6 mm thick.
13.0	White Cement	J.K. , Birla
14.0	P.V.C. Sleet Cistern	Hindware (15 Ltr. Capacity)- Public toilet Design No. 189229.
15.0	Paint, Primer	Nerolac ,Asian
16.0	Urinals	toilet- Hindware –60007 Senso Urinals.
		toilet - Hindware –60007 Senso Urinals.
17.0	Squatting Pans	For Public toilet - Hindware –20042 Orissa Pan 6 Ltr.
18.0	Towel Rods	MAOR – (Marc make)-4060
19.0	Mirror	Modi Guard- 6 m.m. thick.
20.0	M. S. Tor.	TATA.
21.0	Water proofing chemical	CECO NO. 1

22.0	Antitermite liquid	Dursban – T.C. (for wood and earth).
23.0	G.I Pipes	B -Class.
24.0	PVC Pipes.	Supreme/Prince
25.0	False Ceiling	India Gypsum, Armstrong
26.0	Timber	Salwood
26.0	vetrifiedTiles 2'x2'	Jhonsons , (Perlato)

Bharat & Associates