

यूको बैंक



UCO BANK

सम्मान आपके विश्वास का

Honors your trust

अंकवाZOV/यों एवं विP&D/2016-17/66

दिनांक/Date : 21.09.2016 निविदा

सूचना/TENDER NOTICE

विनिर्दिष्ट के अनुसार वस्तुओं के दर हेतु मुहरबंद निविदाये आमंत्रित हैं/ Sealed items rate tenders are invited for the works noted hereunder :

क्र. स. /S.N	कार्य का विवरण/Name of work	कार्य-स्थल/Location of work	अनुमानित लागत/Estimated Cost
1	शाखा बड़हलगंज , जनपद गोरखपुर में आंतरिक साज-सज्जा का कार्य/ interior & furniture work at Barhalganj branch Distt Gorakhpur	शाखा बड़हलगंज , जनपद गोरखपुर Barhalganj Branch Distt Gorakhpur	Rs 5,93,000/-
2	शाखा बड़हलगंज, जनपद गोरखपुर में विद्युत कार्य/ Electrical work at Barhalganj branch Distt Gorakhpur	शाखा बड़हलगंज , जनपद गोरखपुर Barhalganj Branch Distt Gorakhpur	Rs 2,69,000/-

निबंधन एवं शर्तें/ Terms and Conditions :

- कार्य की पूर्ति हेतु समय : 30 दिन / Time of completion of work : 30 days.
- अर्नेस्ट मनी डिपॉजिट : निविदा जमा करने के समय पे आर्डर/ डी डी / बैंकर्स चेक के रूप में अनुमानित लागत का 1%/Earnest Money epost : 1% of estimated value at the time of submission of tender in the form of pay order/DD/Banker's cheque.
- आरंभिक अभिरक्षा जमाराशि : सफल बोली लगाने वाले की अर्नेस्ट डिपॉजिट मनी को शामिल करते हुए अनुबंधित राशी का 2% / initial security deposit : 2% of the contract value including the EMD by successful bidder.
- सफल बोली लगाने वाले के द्वारा अर्नेस्ट मनी डिपॉजिट एवं आरंभिक अभिरक्षा जमा राशी, अनुबंध की अभिरक्षा राशी व रिटेंशन मनी के एवज में समायोजित कर ली जाएगी / The EMD and ISD so deposited by the successful bidder, will be adjusted with the security deposit/ retention money for the contract.
- क्षतिपूर्ति वहन अवधि : कार्य के वास्तविक समापन से छः माह की अवधि तक / Defects liability period : 6 months from date of virtual completion of work.
- निविदा के जमा करने का अंतिम समय एवं तिथि : 04.10.2016 को अपराह्न 2.00 बजे/ Time and last date of submission of tenders : 2:00PM on 04.10.2016.
- निविदा खोलने का अंतिम समय एवं तिथि : 05.10.2016 अपराह्न 4:00 बजे/ Time and last date of opening the tenders : 4:00PM on 05.10.2016.
- जमा करने का स्थान / Place of submission : यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010
UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi - 221010
- बिना कोई कारण बताये किसी व सभी निविदाओं को स्थगित करने व निरस्त करने का अपना अधिकार बैंक के पास सुरक्षित है। सभी निविदाये, जिसमे निर्दिष्ट कोई शर्त पूरी नहीं है या किसी भी रूप में अपूर्ण है, निरास्त की जा सकती है। / Bank reserves its right to postpone/ reject any or all the tenders without assigning any reason what so ever. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- सेवा कर नियमानुसार लगे होगा / Service tax applicable as per norms.
- केवल सूचीबद्ध कॉन्ट्रैक्टर्स ही सम्बिदा प्रस्तुत करे /Only empaneled contractors can submit tenders.

अंचल प्रबंधक / Zonal Manager

यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010
UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi - 221010

Phone: 0542-2221723, 2223323, Fax -0542- 2223123

e-mail: zo.varanasi@ucobank.co.in

Ref No :

Date:

Detailed Estimate / Schedule Of Quantity of furnishing work of UCO BANK BARHAHALGANJ BRANCH.

S.No.	Item's of Work	Qty.	Unit.	Rate.	Amount (Rs.)
1.	Bank Low ht. Counter 2'-6" wide made out of 19mm thick board with drawer unit and open able shutter in two part and front side 12mm thick Etching Glass Supported with Teak wood or Aluminum member with 1.0 mm thick laminate on the top & Front others internal surface to be painted /Polished with with key board sliding drawer On Roller and all edges teak wood beeding, Lipping / molded complete work as per branch Manager/ Architect Satisfaction	20'-0"	Rft		
2.	P/F of Bank Cash counter partition in two level cash counter 9'-0" long (with 3'-6" and 2'-6"height) counter for customer to be 1'-6"wide and counter to be 3'-0"wide with drawer unit made out of 19mm thick board with 1.0 mm thick laminate on top and front and other internal surface to be painted/polished complete as per item no.1	10.0	Rft		
3.	P/F of Cash cabin partition front-over the counter supported on 2"x1-1/2" salwood frame work cover with 8.0 mm thk. Ply with 8mm Etching glass supported of 1"x 1/2" beading with book window in size 5"x6" center of the counter with 2"x2" spacing Aluminium grill will be fixed in front of partition. Side partition supported 2"x1-1/2" sal wood well seasoned structure with a cost of antitermite treatment upto 3'-0" height framing of inside area with 2"x1-1/2" sal wood section 2'-0"c/c horizontal and vertical with bothside 6mm thick ply&1.0mm thick laminates both side. The upper portion upto 4'-0" height shall be of 2-1/2"x2"x2-1/2" Aluminum grill will be fixed complete with all accessories and labour.	297.0	Sft		
4.	P/F full height wooden Manager Cabin partly glazed/laminated wooden partition made out of sal wood well seasoned structure with a cost of antitermite treatment upto3'-0" ht. framing of inside area with 2"x 2"sal wood section 2'-0"c/c horizontal and vertical both side 6mm thk ply & 1.0mm thick laminates both side.& middle portion 6mm thk.Etching glass with teak wood beeding,liping/ moulded complete in all respect.	285.0	Sft		
5.	P/F Low height partition/Wicket gate all specification as item No.4	70.0	Sft		
6.	Providing and fixing in position double leaf powder coated Aluminum entrance door made of 14 gauge thick sheet. All member shall be of 4"x1-3/4"section and bottom rail shall be of 5"x1-3/4"section with 6mm thick clear sheet glass including 4"dia 2 Nos handles 10"long 2 Nos,Tower bolts,floor spring 2 Nos lock etc. complete.	115.00	Sft		
7.	Providing and fixing Writing desk in position box type Wooden writing in public space of approximate size 4'-0" x 2'-0" made out of 19mm thick good approved quality ply with 6" to 9" wide pigeon hole type compartments in the front facade boxing for keeping pay-in-ship, book literature etc. These Writing table's must have laminates 1.0mm thick on top writing desk and two sides of the Boxes. With beeding, lipping, moulding and painting /polishing complete.	1.00	No.		

8.	Providing and fixing in position Notice boards of approximate size 3'-0"x2'-0" and 6" deep made out of 19mm thick ply with fully glazed shutter in front and soft board with felt cloth lining at the back inclusive of good approved quality lock to this shutter, hinges, fixtures, handle etc. and front laminate /painted complete as directed by bank architect.	1.0	No.		
9.	Providing and fixing of Check Drop box size 1'-3" x 1'-6" with all specification as per item No.8.	1.0	No.		
10.	P/F of Godrej mortice lock	2.0	No.		
11.	P/F of Godrej Night latch .	2.0	No.		
12.	P/F of Door closer I.S.I mark	2.0	No.		
13.	Providing and fixing Column/Wall paneling paneling all specification as per item no.4.	270.0	Sft		
14.	Providing & fixing wooden Filling Cabinet 1'-6"deep to be fixed on the wall frame made out of 19mm thick commercial ply with sliding hinge shutters made out of 12mm thick ply with 1.5mm laminate on the front & side other internal surface to be painted as complete with handle, lock, wall catches etc.	158.0	Sft		
15.	Providing and placing in position Side units made out of 19mm board with 1.0mm laminate with sliding hinged shutters (made out of 12mm thick ply with 1.0mm thick laminate on it) complete with handles etc. size 4'-0"x1'-6"x2'-6"	2.0	No.		
16.	Providing and fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm dune supreme RH 99 prima tile with regular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting if any and necessary cutouts for diffusers and light fittings, taping and finishing to proper line and level including making grooves and trap doors for A.C. unit in 18 mm thick M.R. grade plywood with stainless steel hinges and licks with moulding 1" x 1" for edges including finishing with white plastic emulsion paint etc. complete in all respect . (Note :- only the plan area will be measured for payment no extra payment will be made for cutouts , grooves moulding etc.)	585.00	Sft		
17.	Providing and fixing in position dropped ceiling in two levels including vertical surface in between two level of ceiling surface with 12.5 mm thick tapered edge Gypsum Board conforming to IS:2095 including providing and fixing of frame work made of special sections power pressed from M.S.sheet and galvanized in accordance with zinc coating 600as per IS 277 and consisting of angle cleats of size 25mm wide x 16mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastner 12.5mm dia x 40mm long with 6mm dia bolts to the angle hangers of 25x25x5mm of required length and other end of angle hanger being fixed with nut and bolts to G.I.channels 45mmx 15mmx 0.9mm running at the rate of 1200mm centre to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in direction perpendicular to G.I.channel with connecting clips made out of 2.64 mm dia x 230mm long G.I.wire at every junction including fixing the gypsum board with ceiling section and perimeter channel. The perimeter of ceiling fixed to wall/partition with the help 25mm long drive all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square	350.0	Sft		

[illegible]

List of approved materials

Sl. No.	Materials	Approved manufacturers / suppliers
1.	Paint	I.C.I. (Dulex - Duco) / Asian paints / Goodlac Nerolac
2.	Plywood	Century plywood (BWR Grade)/ Green ply (BWR grade), Archid Ply
3.	Wood preservative	Sal Wood
4.	False ceiling	Armstrong , Indian gypsum board
5.	Laminates	B.O.I Guide Line (As per drawing)
6.	Screws	G.K.W./Nettle fold
7.	Adhesive	Fevicol SH
8.	Night latch	Godrej
9.	Locks	Godrej
10.	Aluminium door frame	Jindal
11.	Glass	Modi/Asahi/Saint Gobain
12.	Aluminium cladding	Eurobond/Altobond/Alukbond
13.	Key board drawer	EBCO
14.	Telescopic CPU stand	EBCO
15.	Cable organiser (wire manager)	EBCO
16.	Vitrified tiles	Jhonsions Perlato
17.	Venetion blind	Vista, Luxa flex

Note : Plywood mentioned in the drawings as well as in bill of quantities should be MR Grade only.

Ref No :

Date:

Detailed Estimate / Schedule Of Quantity of Electrical work of UCO BANK BARHAHALGANJ BRANCH.

Sl. No.	Item's of Work	Qty.	Unit.	Rate.	Amount (Rs.)
	Providing & fixing (Philips make) recessed mounting luminaries mirror optic fitting (CAT- No: 300/236 P5 – 2x PL-L 36W) along with 2 No 36 Watt PL-L lamp and attachment as per drawing.	12.0	No.		
	Providing & fixing of 1x18 watt Down light fitting (Philips Make) alongwith 1x18Watt holder type CFL as per drawing.	12.0	No.		
	S/F A.C. Box with 25 Amp SP MCB for UPS input & output, AC. concealed in walls.)	5.0	No.		
	Making point wiring for light & fan by 2x1.5Sqmm + 1x 1Sqmm FR PVC Multi standard wire in suitable PVC conduit.	N.A.			
a)	Single point controlled by single switch.	58.0	No.		
b)	plug point on switch board	6.0	No.		
	Supply and fixing 15Amp switch and socket alongwith MS board, cover plate, etc.	8.0	No.		
	Supply and fixing 5 Amp switch and socket along with MSboard, cover plate, etc	8.0	No.		
	Wiring point for computer 5 Amp switch 3 Nos and 5 Amp socket 3 Nos alongwith 3 x1.5 Sqmm multistandard wire in suitable size PVC conduit complete all in all respect. Each point MCB controlled.	10.0	No.		
	Supply and fixing Ceiling fan including Fan Regulator testing as per drawing.Make-Crompton & Anchor	8.0	No.		
	Supply and fixing cabin fan/ Wall Fan for cash counter.	6.0	No.		
	a) Supply and fixing 12 way double door MCB DB with 63 Amp DP MCB and 10 Nos SP MCB for light / fan	2.0	No.		
	b) Same as above but 8 way for UPS	2.0	No.		
	Wiring point for Telephone/Fax /Intercom with 1 st swin single core copper wire placed According to drawing with complete fitting with top & socket placed according to Drawing.	2.0	No.		
	Supply and lying PVC sheathed & pvc insulated armoured Al cable 50 Sqmm x 3.5 core alongwith 1 No 8 SWG GI wire on wall / ceiling by saddle at suitable interval termination of cable at both end by proper socket main pole to BO electrical panel.	40.0	Rmt.		
	Same as above but 10 Sqmm x 4 core for DG Set.	25.0	Rmt.		
	a) Supply and lying 2x 6 Sqmm + 1x1.5mm multistandard wire in suitable size PVC conduit for AC & UPS.	30.0	Rmt.		
	b) Same as above but 2 x 2.5 Sqmm + 1 x 1Sqmm for light / fan.	30.0	Rmt.		

	c) Same as above but 3 x 1.5 Sqmm for fire alarm system.	35.0	Rmt.		
	d) Same as above but 2 x4Sqmm for copper earthing (earth station to UPS room).	20.0	Rmt.		
	Earthing 600x600x3mm copper plate earthing stations with earthing resistance less than 2 Ohm including watering, PVC/G.I. Pipe with funnel, excavation till 8'-0" deep or as instructed by the Architect, back filling with compaction, 2Nos. copper flats 25mm x 3mm conn. Earthing copper wire in PVC conduit pipe from Earthing pit to UPS.	1.0	No.		
	Same as above but 600 x 600 x 6mm GI plate with 8 SWG GI wire earth station to main panel.	1.0	No.		
	A – Supplying and drawing lan cable cat - 5 d-link or eqv make by 19mm pvc pipe fully concealed.	150	Rmt		
	B- termination of lan cable in one end with RJ 45 computer jack of MK,Roma or Crab- tree make in suitable enclosures.	10.0	No.		
	C- termination of land cable in other end with RJ 45 socket.	10.0	No.		
	D- Supply & Fixing of 9 U Rack for Switch & other item.	N/A	No.		
	Supply and fixing electronic patty type fitting along with 36Watt tube.	6.0	No.		
	Supply, fabrication and installations of new panel board made by 16 gauge CRC sheet 410 volt 3 phase comprising of following including termination of the incoming and outgoing line by proper socket interconnection natural link and painting incoming 100 Amp TPN MCCB. (a) 63 Amp changer 4 pole –01 (b) 32 Amp DP MCB –12 No (c) 63 Amp DP MCB – 02 No (d) 100 amp copper busbar –02 No (e) Amp meter, Voltmeter, Fuse, CT Coil etc. (f) 100 Amp MCCB 35 K 4POLE – 01 No	1.0	No.		
	S/F 100 Amp cutout for main panel.	3.0	No.		
	Supply and fixing of Exhaust Fan 300mm heavy duty make Crompton.	2.0	No.		
	Supply and fixing 32Amp Changeover 2pole	1.0	No.		
	Supply and fixing Cash Cabin CFL 23Watt	4.0	No.		
	Call bell point with call bell in Manager Cabin	1.0	No.		

Add:S.T.@6%

Rs.

Total Rs.

Less: 50% of the Tax Amount (-)

Rs.

Net Total

Rs.

Say Rs.

(Rs.)For:-

SPECIFICATIONS OF ELECTRICAL MATERIALS

<i>.No.</i>	<i>Item</i>	<i>Make/ Specifications</i>
1.	FITTING	Philips & GE
2.	WIRE	Anchor, Havells, Finolex
3.	SWITCHES	Roma, M.K., Crabe Tee-Havells
4.	MCCB	Havells , L&T
5.	MCB DB	Havells, L&T
6.	Main Switch	HPL, L&T,
7.	Changeover	Havells , L&T,
8.	PVC Pipe	AKG, Plaza. 2mm thick
9.	Wall Fan	Crompton, Havells
10.	Ceiling Fan	Crompton, Havells
11.	Exhaust fan	Usha; Khaitan, Crompton.
12.	Cable	Gloster, Havells, National, Railisons.
13.	Telephone Wire	Delton, Anchor.
14.	Cat- 6 Cable	D - Link
15.	IO - Box	D - Link

16.	MCB	Havells, L&T
17.	CFL	Philips (Only)
18.	MS Pipe	AKG, MK,

Bharat & Associates