

ISSUED TO M/S_____

TENDER DOCUMENT

FOR

FURNISHING OF

PROPOSED E-LOBBY ,

UCO BANK

BRANCH AT SECTOR -8 ,

PANCHKULA .

**OFFICE OF THE
DEPUTY GENERAL MANAGER
UCO BANK, Z.O. S.C.O. NO. 55-57, 3rd FLOOR,
SECTOR 17-B, CHANDIGARH - 160017**

ARCHITECTS:

ATWAL & ASSOCIATES

S.C.O No. 1064-65, SECTOR 22-B,
CHANDIGARH – 160 022.

PHONE: 0172-2728405

MOBILE: +91 9814866116

DETAILS OF TENDER

**TENDER FOR PROPOSED E-LOBBY , UCO BANK BRANCH AT
SEC - 8 , PANCHKULA.**

- | | | | |
|-----|---|---|--|
| 1. | Details of work to be done | : | Interior / Furnishing & Allied
Electrical works for UCO Bank,
Currency Chest Branch |
| 2. | Form of Contract | : | Item wise rate |
| 3. | Earnest Money | : | Rs. 10,000/- (Ten thousand only)
in form of Demand draft in favor of
Uco Bank payable at Chandigarh. |
| 4. | Period of contract /
time of Completion | : | 4 Weeks |
| 5. | Last Date & time for receiving
of sealed tender. | : | __07.07.2015 at 17:00 p.m. |
| 6. | Liquidated damages for non-
completion of work in time | : | 1.0% of the contract value per week
subject to a max of 10% of the
Contract value. |
| 7. | Defect Liability Period | : | 12 months (Twelve months) from the
date of virtual completion as certified
by Architect / employer. |
| 8. | Retention amount for 12 months | : | 8% of the total bill. |
| 9. | Period of submitting of
Final bill. | : | 15 days from the date of completion. |
| 10. | Mobilization Advance /
Secured Advance | : | No. Mobilization Advance / secured
Advance will be given to the
Contractor. |
| 11. | Place and date of opening
of tender | : | UCO Bank Zonal Office, Haryana at 3:00 p.m.
in Office of the Chief Officer, Uco Bank,
S.C.O. 55-57, 3 rd Floor, Zonal Office,
Sector 17-B, Bank Square, Chandigarh |

**Chief Officer, Uco Bank,
S.C.O. 55-57, 3rd Floor, Zonal Office,
Sector 17-B, Bank Square, Chandigarh.**

**TENDER FOR PROPOSED E-LOBBY , UCO BANK BRANCH AT
SEC - 8 , PANCHKULA.**

GENERAL CONDITIONS

1. The Contractor shall sign each page of this tender.
2. Payment to the Contractor Agency shall be made as per actual work done at site.
3. Quantity of work may increase or decrease at site as per requirement, which shall not affect the rates quoted by the contractor.
4. Furnishing works including electrical works etc. shall be done to the complete satisfaction of Bank and Architect-in-charge.
5. All teak / Cedar wood / rubber wood to be used should be knotless which is to be polished with all background surface preparation coarses maintaining the visibility of wood grains.
6. The rates to be quoted shall include the cost of material, labour charges, carriage, sales tax, or any / all other taxes any required hardware etc.
7. The contractor agency shall keep particular vigil on his workers / carpenters / painters etc. to maintain very good workmanship of all items, failing which no payment shall be made and no claim of material / labour used shall be made to him in any case, and the same work shall be executed by him again without charging any extra cost.
8. All rates shall be quoted in words & figures & any cutting over writing shall be signed.
9. All items to be executed as per drawings, if any change is required, the same shall be brought to the notice of Architect-in-Charge.
10. Any tender / quotation containing clerical or arithmetical mistakes shall be rejected.
11. Any addition, alteration or correction shall be signed and stamped properly.
12. Contractor agencies are advised (before quoting the rates) to inspect the site of the proposed work. He must go through all drawings and specifications and documents.
13. The Bank reserves the right to accept / reject any tender / quotation without assigning any reason.
14. The Contractor agency should have already executed works of furnishing interiors & exterior, civil works of very good workmanship.
15. Quality of material and workmanship rejected by the Architect / Concerned Authorities shall be removed immediately by the contractor and rectified / replaced.
16. No advance payment shall be made to the Contractor on supply of any material supplied at site for execution. Payment shall only be made on execution of any concerned / particular item.
17. The rates shall include the cost of coat of anti termite treatment on all wooden frame work and all commercial ply / board used for partitions and paneling, furniture etc. The contractor/s shall have to dismantle & dispose the existing counters, tables & partitions within the quoted cost of the total furnishing works.

18. Rates for partitions, paneling, wall cladding and false ceiling shall include cutting and making good of necessary cut-outs/chiseling to be made for electrical conduits, switch boards etc.
19. Bank shall not be responsible for any loss or damage to the contractor/labour due to any natural calamity during the course of construction. Contractor is liable to make good all the damages if any, till the work is completed and handed over to the Bank authorities.
20. Any payment to the contractor on account of execution of work, whether it is running payment or final, shall be verified by the Architect-in-Charge.
21. Unless, otherwise mentioned all materials to be used shall be I.S.I. marked. Failure to do so, the work may be rejected and in that case contractor shall have to remove the defective materials and replace / re-do the work for which no claim shall be entertained.
22. The total work shall be supervised by the Architect-in-Charge and he/she shall be kept fully informed by the contractor regarding the progress of work.
23. Bank may award the work in part or whole to a single party or any other party.
24. It may please be noted that the Bank is not bound to allot the work to the lowest party. And as such, the allotment of work shall be based on workability of rates quoted by the contractor on account of quality work.
25. The bank reserves the right to reject any or all the tenders without assigning any reason whatsoever.
26. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful tenderers.
27. Earnest money paid by the contractor shall be forfeited by the Bank if contractor fails to undertake the job if he is communicated about acceptance his rates/tender.
28. The contractor shall take all the necessary precautions while working and to safe guard adjacent property, Bank's property, Bank's Employees, and traffic persons.
29. All the rates quoted are inclusive of removal of existing counters, partitions, wiring, rubbish/ debris collected during the progress of work, rejected materials etc.
30. The contractor shall not directly or indirectly sublet the work to other party without written permission of the Bank.
31. The quantities mentioned in schedule are provisional and likely to increase/decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit / business shall be entertained on this account.
32. The Bank reserves the right to distribute the work for which quotations have been called, among more than one parties, if found necessary. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the Bank.
33. All the workers of the contractor must be properly covered by an insurance policy under "Workman's Compensation act" and "Fatal Accidents Act". The contractor at his own expenses arrange to effect and maintain until the virtual completion of the contract, insurance policy in the joint name of Bank and the contractor against this risk to be retained by the Bank until the virtual completion of the work, and indemnify the Bank from all the liabilities arising out of such events. In case of delay, contractor shall arrange to extend insurance policy till work is completed.
34. All the work should be completed within the specified period in the tender. If the work is delayed due to the reasons beyond the control of the contractor, he should keep intimating the Bank

explaining, therein the reasons for such delays, immediately and if in the opinion Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.

35. The contractor shall furnish well in time before work commence at his own cost, colour samples, samples of materials or workmanship that may be called by Bank's Architect / Engineer for approval. Rates quoted shall cover for such preliminary work.
36. All the glass panes, door handles/ hinges, electric fittings, fans, furniture, records, floors etc. are to be thoroughly cleaned after the work is completed.
37. The rates quoted by the contractor shall be firm throughout the duration of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in cost of material and labour.
38. Conditional tenders are liable to be rejected.
39. The successful tenderer is bound to carry out any item of work necessary for the completion of the job even those such items are not included in schedule of quantities.
40. If in any case of work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period, if deemed fit.
41. Decision of the Bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on the terms and conditions of this contract. However, if the matter cannot be resolved then the same shall be referred to the respected qualified person in agreed to both the parties and his opinion shall be binding on both the parties. However, this is precourse to any legal action in this regard.
42. If at any stage during the progress of work, it is observed that the contractor is not progressing the work with due diligence, care of lagging much behind the schedule or fails to gear up the work despite instructions from Bank's Architect, the Employer (Bank) reserves the right to terminate the contract with 7 days notice. In such case the contractor shall be liable to pay the Employer any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposit held by the Bank will be forfeited.
43. Contractor shall follow all rules / regulations in force and should posses the license for employing labour and also follow all safety measures, labour bye laws and shall be responsible for any lapse.
44. At any stage i.e. during the execution of work, any kind of change reqd. whether it is in design or specification, the same has to be in-corporated by the contractor.

CONTRACTOR

ARCHITECT

UCO BANK

**TENDER FOR PROPOSED E-LOBBY , UCO BANK BRANCH AT
SEC - 8 , PANCHKULA.**

SPECIFICATIONS OF MATERIALS TO BE USED FOR FURNISHING WORK

<u>DESCRIPTION</u>	<u>BRAND</u>
a) Board / Ply :	COMMERCIAL BOARD, Greenply, Green Panel Max MDF board.
b) Laminate :	Century, Greenlam, Donear, Formica, 1 mm thk.
c) Door Closer / Floor spring Marked. :	Everite, Doorking, Sandhu ISI, Nitco.
d) Drawer & Keyboard, Slide Rails :	Earl Bihari, Ebco (Telescopic), Hettich
e) Glue for fixing commercial Board / Laminate :	Fevicol (Pidilite)
f) Glass :	Modi Float, Saint Gobain, Asahi.
g) Mortice Latch & Lock :	Godrej.
h) Vertical Blinds :	Vista Levelor / Mac.
i) Tapestry/leather foam :	Harmony, Vimal, Bhor or as approved
j) Aluminium Sections :	Jindal/Mahavir/Hindalco
k) False Ceiling :	Gypsum marked "Gypsteel"
l) Synthetic Enamel :	Asian, Nerolac, ICI, Berger, Dulux
m) Emulsion Paint/Plastic Paint :	Asian, Nerolac, ICI , Berger, Dulux
n) Vitrified Tile 2'x2' (600x600 mm) :	Johnson, Kajaria, Naveen,

SPECIFICATIONS / BRANDS / MAKE OF ITEMS FOR ELECTRICAL WORK TO BE USED.

- SFU/MCCB/ Change over switch/DB	:	Indo Asian / Havells / L & T / Clipsal / Schinder.
- Voltmeter/Amp meter	:	AE/L&T.
- Armoured Cable	:	Gloster/ CCI/Polycab.
- PVC Insulated Wires	:	Evershine KDK/Finolex/National.
- Telephone cable	:	Finolex/Evershine KDK/Delton.
- Data cables & I.O's	:	Lucent (Avaya)/D-link.
- Modular switch / socket / call Bell	:	North west/Crabtree/Anchor Roma/ L&T Oris.
- Light fittings & Lamps	:	Philips/Crompton/Wipro.
- Ceiling fan/Wall bracket fan/Exhaust fan	:	Bajaj / Khaitan
- Chairs	:	Godrej, Geeken or equivalent

CONTRACTOR

ARCHITECT

UCO BANK

**TENDER FOR PROPOSED E-LOBBY , UCO BANK BRANCH AT SEC
- 8 ,PANCHKULA.**

Sr. No.	Description of Item	Qty	Rate	Amount
1).	<u>WOODEN PARTITIONS :-</u> Providing and fixing wooden partitions of height 4'6" & upto false ceiling bottom (9'-0") made of 2" X 2" partal wood frame @ 2'0" c/c vertically & horizontally .The bottom member shall be of partal wood of size 2" x 4" . The partal wood frame should be fixed rigidly at floor level. The frame work to be cladded with 6 mm thick (I.S.I marked) phenol bonded boiling water proof Comm. Ply & then with 1 mm thk. Laminate with horizontal pin grooves. The rate of partition shall include providing & fixing door made as per partition specification along with complete hardware required as brass handles ,hinges & door stopper etc complete & also cheque transfer tray for Single window cabin . 5 mm glass with etching design is fitted as per drg. / design . All exposed surface to be laminate finished. All exposed edges shall have teakwood lipping 2.5" X 1¼" melamine polished or enamel painted. Size: - Length X Ht.	a) Full ht. partition Upto false ceiling bottom (9'-0" ht.) = 85 Sq.ft. b) Partition upto 4'-6" ht.= 40 Sq.ft.		
2).	<u>12 MM GLASS , LOW HT. PARTITION :-</u> Providing & fixing 12mm thick plain glass with acid wash / etching of semi circular or any other approved pattern / texture fixed to steel holders at appropriate distance sufficient in number so as to hold glass complete in all respects. All the visible edges of glass shall be grinded & polished & bevelled .The rates shall be inclusive of cost of all fitting, beadings , making suitable openings for transaction and voice communication etc. complete.	30 sq. ft.		
3).	<u>MAIN DOOR</u> -with customized door handle. Door size, Approx. 3'-0" x 7'-3 " Providing & fixing glass door comprising of approximate 33.5 vertical members, approximate 85-100mm top & bottom, approximate 83.5mm middle member, aluminium black powder coated members, door closure of Hemco, Everite, Hyper or equivalent ISI approved make with SS	25 sq.ft.		

	hinges, clip sections, 6mm clear glass of Modifloat, Saint Gobain, Asahi or equivalent make. Wool pile / Weather strip on one vertical member. Providing & fixing colour customized door handle to fit on glass.			
4).	External fixed glazing (Material & Labour) Providing and fixing external fixed glazing comprising of 12 mm Modifloat, Saint Gobain, Asahi make clear glass with top, bottom and vertical frame comprising of black powder coated aluminium members, glass to be laminated with clear antishatter film on one side. Approximate 85mm top & bottom member, approximate 85mm vertical members.	32 sq.ft		
5).	Chair, Dustbin & Footmat 1 no. Neelkamal make plastic chair or equivalent with handles for security guard and dustbin, foot mat	1 set		
6).	Visual Merchandising Information Panel (48" X 24"), Writing ledge (15" X 75") , Cheque deposit box (9" X 7" X 36") (one each)	1		
7).	Poster Frames - Wall Hung 2 sheets of 36" x 24" clear acrylic (poster to be sandwiched in between). Outer sheet is 5 mm thick and beveled crystal edge polished for 3/4" at 8-10 degrees on all sides in the front. Rear sheet is 5 mm thick flat. Rate inclusive of S1 grade aluminium.	2		
8).	Shutter Boxing in A.C.P. :- Providing & fixing in position Aluminum Composite Panel (ACP) with framing of Aluminium Tube sections of min. 1.5" X 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm., 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used. Shades to be as per bank's approval. Trap door will be 12 mm marine ply finished with ACP. Including CLADING : (Left , Right & above glazing)	Lumpsum		
9)	Color Sticker Set :- Colour Customized user stickers of good quality for ATM input / output devices, access lock / release bell, entrance door. Pull / Push etc	1		
10)	WALL PANELING 4'-6" HT. :- Providing , fabricating & fixing wall paneling in customer lobby by 50 mm X 25 mm first class hard wood/partial wood frame work at 600 mm c/c both ways with anti- termite treatment for the wood work with 6 mm thick phenol	130 Sq.ft.		

	formaldehyde bonded ply covered with 1 mm laminate finish of approved shade / finish as per the colour scheme including all incidentals etc complete as directed . Allow for 100 mm high 6 mm thick steam beach wood skirting . The fixing of ply & laminate to be as per the pattern approved by bank . Quoted rates shall include all necessary materials, accessories & labour & also allow provisions for electrical /telephone / computer wiring conduits & switch boxes etc. (materials for wiring / conduits & switch boxes shall be separately paid for).			
11.)	FALSE CEILING :- Plain false ceiling with 12.5 mm thick gypboard metal frame work of Indian gypsum Ltd. Paper tape, jointing compound, and G.I. sections marked. Gypsteel to be placed at 4.0” c/c and 1’-6” in other direction. Complete job including cutting opening in the existing ceiling for lighting fixtures, grilles/ diffusers, smoke detectors / security alarm system, etc. painting the surface of gypboard with three or more coats of plastic emulsion paint of colour/ make / sample/ quality approved by the consulting architects. False Ceiling Lvl. :- + 8’-6”	130 Sq.ft.		
12.)	BLACK GRANITE SLAB – P&F black granite slab 18-20 mm thick fixed to entrance door and glazed partition periphery walls front , side and lintel bottom. Fixing in cement mortar 1:5, complete with round moulding as per design to the edges and joints filling. Granite to be fixed under lintel so as to leave gap for free movement of rolling shutter .Nearest shade / spec, which is locally available as compared to the approved sample shall be used.	16 Sq.ft.		
13.)	P/F “Premium” quality vitrified tile flooring as per flooring pattern & colour scheme (with base filling of cem. conc. 1 : 3 : 6 for leveling) of size 2’x2’ Naveen/Marbonite of approved colours . Base flooring of PCC 1:4:8 to be provided as per site conditions , as required . All job to be done complete in all respects.	50 Sq.ft.		
14.)	CIVIL WORKS			
a)	9” thk. Brick masonry :- 230mm thk. (9”) brick masonry wall in cement mortar 1:5 using locally available bricks of class designation 75 (minimum) and conforming to I.S -1077 -986 including providing all openings and projections , raking the joints to 1 cm deep			

	, scaffolding , soaking of bricks in water prior to use and curing etc.all complete .Brick wall to be provided :- E- Lobby 9” thk. brick wall.	160 Sq.ft.		
b)	<u>PLASTERING :-</u> Providing and laying average 12 mm thk. Sand faced cement plaster in CM 1:4. Rate to include necessary scaffolding , chicken wire mesh at joints b/w brick and concrete and complete curing .Job includes cleaning , wetting of surface curing etc . all complete . Plastering to be provided :- On both sides of 9” thk. Brick wall.	300 Sq.ft.		
15)	Demolition of ATM 9” thk brick wall & disposal of its malba .Complete in all respects.	Lumpsum		
	TOTAL (FURNISHING WORKS)			

ELECTRICAL WORKS

	<u>CONSTRUCTION ASPECTS</u> <u>ELECTRICAL WORKS :- IMPORTANT</u> <u>NOTE :-</u> All electrical work to be done conforming to the relevant specifications of BUREAU OF INDIAN STANDARDS to the entire satisfaction of the architect / bank management.			
1)	<u>EARTHING :-</u> Gel type maintenance free chemical earthing. Supply & instalation of Terradine GI 30 mm dia. 10'0" long electrode filled with hydroscopic, noncrosive terasalt having breaching ports at top @ leakching ports at bottom with two bags of terafill. Rate should include earthing conductor, bore well, redimade chamber with cover of Altec corporation & all required civil & all allied works complete. (Including 4mm PVC copper wire)			
a)	ASH - 50, Length - 3000 mm outer dia for 60 - 63 – G.I. Gel earthing.	1 Nos.		
b)	SITC of engraved stainless steel earthing tag plate 150 x 150 sqmm to be fitted near respective earthing pits indicating pit no. user, type of earthing.	1 Nos.		
2.)	<u>ELECTRICAL WIRING AND POINTS</u>			
A (i)	FOR UPS Providing & laying copper wires 2.5 sq.mm 4.0 sq.mm in 25 mm x 2mm thk. PVC conduits for UPS & Main . UPS to have incoming / outgoing power	Lumpsum Industrial plug socket		

(ii)	supply through 20A heavy duty metal clad industrial plug sockets with MCBs . UPS to have single phase input and single phase output .	for UPS input / output :- 2 Nos.		
B)	Wiring in PVC insulated copper conductor in PVC pipe 12mm x 2mm with modular switches / plugs fitted in concealed zinc passivated boxes with moulded plates switches.			
(i)	For light pts. by laying 1.5 sqmm copper wire including Glow Sign Board wiring.	8 Nos.		
(ii)	For raw power plug points by laying 5 / 15 amp. copper wire 2.5 sqmm in 1" PVC conduit (2 raw power pts. in E - lobby & 2 in UPS)	4 Nos.		
(iii)	For UPS Plug point. (5/15 amp) by laying 1.5 sq.mm. copper wire from UPS output socket 4 UPS plug pts. in E-lobby & 4 in UPS room .	8 Nos. (2 groups of 4 each)		
(iv)	For light pts . by laying 1.5 sqmm copper wire from UPS to spotlight one each in E- lobby & UPS room .	3 Nos.		
3.)	<u>BRANCH LIGHTING :-</u> Providing & Fixing of following light fittings, ceiling mounted or surface mounted , complete job including reflector , CFL / FTL / GLS lamps , control gear, connections etc.			
a)	P / F Wipro make recessed mounted CFL light fixture 1 X 26 W Jupiter make : WCP 32126 (6" Dia)	2 Nos.		
b)	P/F Wipro make recessed mounted direct – indirect down lighter luminaire with paralite P5 louvers WVP 61236 (2' X 2')	2 Nos.		
4)	<u>CABIN FAN :-</u> Providing/ Erection / commissioning of Cabin fan of Philips / Orient / Khaitan make of size 16" dia complete in all respects.	2 Nos.		

5)	<u>COMPUTER / MACHINE POINTS :-</u> Supply of material, storing, handling, fixing and laying of 3x2.5 Sq.mm of PVC insulated PVC sheathed armoured cable of 1100V (IS 1554 Part 1) and fixing of cable on wall with suitable size of clamps saddles or laid in floor/ recess wall including cutting of wall/floor and making good the damages etc. For computer points in suitable size of GI box with modular plate and cover in front in recess including providing 1 no's 3 pin 5/6/15 amps modular sockets outlets controlled by 1 no 5/6/15 Amps modular switch, indicator and fuse connection etc. As required. Note:- only one computer/machine points are to be provided on one circuit .	7 Nos.		
6)	<u>NET WORKING :-</u> Wiring for computer net working starting from mounting rack with UTP Cat 5 / Cat 6 (as per bank instructions & specifications) cable in 2mm thick 25mm dia ISI marked PVC conduit pipe with accessories such as bends, junction boxes including providing and fixing I/O plates and SMB complete in all networking accessories etc. complete as required including Testing/Commissioning (One point needs 50 mts. Cat 6).	7 Nos.		
7.)	<u>PANEL BOARD</u> Supplying & fixing Metallic panel board of size 0.60 M x 0.60 M by using 20 swg. MS Sheet to accommodate ELCB / MCB / DP SWITCHES / and including all fittings. ELCB 1 Nos. 20 AMP 250 V SPMCB1 2 Nos. 32 AMP 250 V (for ACs) SPMCB2 2 Nos. 16 AMP 250 V (for light pts.) SPMCB3 2 Nos. 32 AMP 250 V (for power pts.) C.O. for Generator 20 AMP 250 V 2 POLE	Lumpsum		
9)	<u>Wiring for Lollypop</u> :- 2 core - 4mm 2 copper flexible cable.	30 mtr.		
10)	<u>ATM SUPPLY :-</u> P/F 16 mm 4-core Alum. Cable from bus-bar to ATM.	10 mtr.		
11)	Light Points provided for security purpose of outside the branch . Light pt. covered with jalli & fixed ceiling or wall as per site	2 Nos.		
12)	<u>GENERATOR CONNECTION :-</u> Providing & laying 16mm cable 4 core	1 Nos.		

	aluminium with 25mm x 2mm thk. PVC conduits complete in all aspects to be connected to Generator when required .			
	TOTAL (ELECTRICAL WORKS)			
<u>AIR - CONDITIONING WORKS</u>				
S.No	Description	Unit	Rate (Rs.)	Amount (Rs.)
1.)	Supplying , erection and commissioning of split type AC'S " Vertis plus " model of Voltas / Blue Star / Hitachi / Carrier make , M.S. stands including stabilizer with power point , insulated copper pipe and drainage PVC pipe with each AC. Copper, drain pipe length not exceeding to 10 R.ft.			
a)	Split AC'S 1.0 Ton	2 Nos.		
b)	Supplying , erection and commissioning of timer switch 240 volt single phase with 32 Amp single phase MCB 40 Amp. DP contactor to be installed in AC circuit . (for ATM)	1 No.		
2)	For A.C. points by laying 4 sqmm. copper wire. (for split A.C units)	2 Nos.		
	TOTAL (AC'S WORKS)			
	TOTAL (ALL COMBINED)			

TOTAL : - Rs.

(In words):-

Address of contractor

Signature of contractor