

NOTICE INVITING APPLICATIONS FOR CONTRACTORS/VENDORS FOR INTERIOR FURNISHINGS, ELECTRICAL WORK AND DATA CABLING

UCO Bank invites applications for contractors/vendors for works related to interior furnishing of branches and their electrical and data cabling. Full details and application forms along with tender documents can be downloaded from our website <u>www.ucobank.com</u> and submitted along with payment of Rs 750/- by Demand Draft (non-refundable) favouring "UCO Bank", payable at Suri. Last date for receipt of duly filled in application is 08.12.2017 within 05:00 p.m.

AGM & Zonal Head, Zonal Officer, Suri

Date:-23-11-2017

यूको बैंक,अंचल कार्यालय, सिउड़ी, सरकिट हाउस के पास,सिउड़ी, जिला -बीरभूम (प. बं.)–731101

UCO Bank, Zonal Office, Suri, Near Circuit House, Suri, Dist. - Birbhum (W.B.) – 731101

राजभाषा का प्रकाश – बैंक का विकास

ARCHI SPACE CONSULTANT

INVITATION TO TENDER

INSTRUCTION TO TENDERERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

INTERIOR FURNISHING & ELECTRICAL WORKS

AT

UCO BANK & ATM – RAGHUNATHGANJ BRANCH, MURSHIDABAD

NAME OF THE CONTRACTOR:

ADDRESS:

.....

ARCHITECT

ARCHI SPACE CONSULTANT 45B, BAGHJATIN PLACE 'AMELIA APPT.' – GR.FLOOR KOLKATA – 700086 CONTACT - 9830006396, 033-2425-0125

UCO BANK, ZONAL OFFICE, SURI NEAR CIRCUIT HOUSE, DIST-BIRBHUM (W.B.) – 731 101

ARCHI SPACE CONSULTANT

CONTENTS

SL NO	SECTION NO	DESCRIPTION
1	I	Tender Notice
2	п	General rules and instructions for The guidance of
3	III	Form of tender
4	IV	Articles of agreement
5	v	General conditions of contract With appendices.
6	VI	Special conditions
7	VII	Approved make of materials with bill of quantities for above mentioned works.
8	VIII	Summary

ARCHI SPACE CONSULTANT

SECTION - 1

TENDER NOTICE

Sealed item rate tenders under two bid systems are invited on behalf of:

The Deputy Zonal Head

UCO Bank, Zonal Office, Suri

Near Circuit House, Dist-Birbhum (W.B.) – 731 101

For the following work;

a)	Name of the Work	:	Interior & Electrical works of Existing UCO Bank & ATM AT RAGHUNATHGANJ BRANCH, MURSHIDABAD
b)	Location of Work	:	VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.SRAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,
c)	Time of Completion	:	: 15 days (Fifteen days)
d)	Earnest Money	•	Rs 20,000.00/ (Rupees Twenty Thousand only) to be deposited In the form of Bank Draft / Pay order drawn in favor of UCO BANK payable at SURI. [Without Earnest Money in proper form Tender will be rejected]
e)	Cost of Tender document	:	Rs .750 /-(Rupees Seven Hundred Fifty only) in cash which is not refundable.
f)	Availability of Tender Documents	•	UCO Bank, Zonal Office Suri, Near Circuit House, Dist-Birbhum (W.B.) – 731 101 and on payment in cash during working hours from 10 am up to 5 pm from 24-11-2017 to 08-12-2017 (Except Sunday & Bank Holidays)
g)	Submission of tenders to	:	UCO Bank, Zonal Office Suri, Near Circuit House, Dist-Birbhum (W.B.) – 731 101 and Within 11.00 am on 09-12-2017
h)	Opening of Tender	•	At 12:30.pm. On 09-12-2017 at the UCO Bank, Zonal Office, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

i)	Mode of submission of Tender		 The tender shall be submitted in accordance to the procedure detailed herein. Specified documents shall be sealed in envelope of appropriate size, each of which shall be sealed. i) Envelope marked No.1: Envelope marked no 1 shall contain earnest money deposit, pre- qualification forms, conditions of contract and technical specifications with covering letter furnished in the specified form. ii) Envelope marked No.2: Envelope marked no.2 shall contain the price bid and approved make of materials iii) no 3: Envelope marked no1&2 shall be put in a large envelope of adequate size marked no 3 which shall be properly sealed. This envelope, which shall be endorsed on the outside face. "Tender for Interior & Electrical works for UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD 	
j)	Clarification, if any to be Obtained from:	:	Obtained from : ARCHI SPACE CONSULTANT 45B, BAGHJATIN PLACE 'AMELIA APPT.' – GR.FLOOR KOLKATA-86 Contact : 9830006396, 033-2425-0125	
K)	Defect Liability Period:	:	12 months from the date of virtual completion of work.	
1)	Validity of tenders:	:	Three calendar months from the date of submission of tender.	
m)	Sales Tax, Work Contract Tax or any other tax on materials or on finished work in respect of this contract whether in vogue or likely to be imposed in future, shall be payable by the Contractor and the Employer will not entertain any claim whatsoever in this respect at any time. Rates should include all these taxes Etc.			
n)	All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected. Conditional tenders will be summarily rejected.			
o)	Delays in submission of any part arising out of the postal or any other irregularities at any stage will not be considered. The Bank will not be responsible for damage in transit incase of postal delivery/ courier service delivery.			
p)	The employer does not bind it to accept the lowest tender and reserves to itself the right to reject any or all the tenders received without assigning any reason/s thereof. The notification of award of contract will be made to the successful tendered in writing by the Bank.			

Yours faithfully

For and behalf of UCO BANK . The Deputy Zonal Head UCO Bank, Zonal Office, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

ARCHI SPACE CONSULTANT

SECTION - II

GENERAL RULES AND INSTRUCTIONS FOR THE GUIDANCE OF TENDERERS.

Tenders are invited on behalf of UCO BANK, SURI ZONAL OFFICE, for Interior, & Electrical works at UCO Bank & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD. Contract document consisting of the plans, specifications, bill of quantities and drawings of various classes of work to be performed and set of conditions of contract to be complied with can be purchased from the office of UCO Bank, Zonal Office, Suri, Near Circuit House, Dist Birbhum, (W.B.) – 731 101 on stipulated dates between the hrs.10.30 to 6.00 except Sundays and other bank holidays.

- It is proposed that the intending tenderers may contact at the office of the Architects of ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." – Gr. Floor, Kolkata - 700086. The site of the work is available. The intending tenderer shall visit the site and make himself thoroughly acquainted with the local site condition, nature and requirements of the work, facilities of the work, facilities of transport condition, effective labour and materials, access and storage for materials and removal of rubbish etc.
- 2. As the entire work is to be completed in all respects within the stipulated period of 15days and to achieve the target date of entire completion if be required /essential, the work for day and night shifts have to be carried out by the tenderer/contractor, for that at no extra cost, charges shall be paid to the contractor by the employer. While quoting rates, in addition to above, whether mentioned or not the rate shall always include the charges for day to day removal of debris/spoils from site in conformity with the local Municipal rules. Bank's normal work shall not be jeopardized in any way for undertaking the work. Contractor shall include in his quoted rate for supplying the plastic sheets/tarpaulin to cover Banks materials as protection against getting damaged either due to dust or water while executing the work. Tenders in only printed forms issued by the consultants should be placed in sealed covers addressed to. The tenderers should quote in figures as well as in words the rates, and amount. The language for filling tender documents shall be in English. The amount for each item should be marked out and requisite total given. The initials of the tenderers with the seal of the firm shall attest all corrections. In case any discrepancy /difference is found on checking between rates quoted by the contractor in words and figures or in the amount worked out by him, the following procedure shall be followed:

3.

- A. When there is a difference between the rates in figures and in words, the rate, which corresponds to, the amounts worked out by the contractor, shall be taken as correct.
- B. When the contractor does not work out the amount of any item or it does not correspond with the rate written either in figures or in words, then the rate quoted by the contractors in words shall be taken as correct.
- C. When the rate quoted by the contractor in figures and in words tallies but the amount is not worked out correctly rate quoted by the contractor shall be taken as correct and not the amount
- D. Amendments as mentioned above shall be based on the tender marked original only.

ARCHI SPACE CONSULTANT

- 4. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only. In such away that interpolation is not possible. Amount should be written in figures. In case of figures the words "RS". Should be written before the figures of rupees and words paise after the decimal figures, e.g. Rs 2.15 and in case of words, the word "Rupees" should precede and the word "Paise" should be written at the end, unless the rate is in whole rupees and followed by the words "only", it should invariably be up to two decimal places. While quoting the rate in schedule of quantities, the word "only" should be written closely following the amount and it should not be written in the next line.
- 5. The acceptance of a tender will rest with UCO Bank, Zonal Office, Suri, Near Circuit House, Dist Birbhum (W.B.) 731 101 which does not bind itself to accept the lowest tender and reserves to itself the authority to reject any or all the tenders received without assignment of any reason. All tenders in which any of the prescribed conditions are not fulfilled or incomplete in any respect are liable to be rejected. The bank reserves the right to accept the tender in full or in part and the tenderer shall have no claim for revision of rates or other conditions if his tender is accepted in parts.
- **6.** Canvassing in connection with tenders is strictly prohibited and tenders submitted by the contractors who resort to canvassing will be liable to rejection.
- **7.** An item rate tender containing percentage below /above will be summarily rejected. However, when a tenderer voluntarily offers a rebate for payment within a stipulated period, this may be considered.
- 8. On acceptance of the tender, the name of the accredited representative(s) of the Contractor who would be responsible for taking instructions from the Employer Consultant shall be communicated to the Employer / Consultant.
- **9.** Sales Tax, Work Contract Tax or any other tax on materials or on finished work in respect of this contract whether in vogue or likely to be imposed in future, shall be payable by the Contractor and the Employer will not entertain any claim whatsoever in this respect at any time. Rates should include all these taxes ------ Etc.
- **10.** No employee of the Employer is allowed to work as a Contractor for a period of two years of his retirement from Employer services, without the previous permission of the Employer. This contract is liable to be canceled if either the Contractor or any of his employees is found at any time to be such a person who had not obtained the permission of the Employer /Consultant as aforesaid before submission of the tender or engagement in the Contractor's service.
- **11.** The tender for work shall remain open for acceptance for a period of **3 months** from the date of opening tenders. If any tenderer withdraws his tender before the said period, then the employer shall be at liberty to forfeit the earnest money paid along with the tender.

ARCHI SPACE CONSULTANT

- 12. The tender for the work shall not be witnessed by a contractor or contractors who himself /themselves has / have tendered or who May and had/have tendered for the same work. Failure to observe this condition would render tenders of the contractors tendering as well as witnessing the tender liable to summary rejection.
- 13. It will be obligatory on the part of the tenderer to tender and sign the tender in all pages documents.
- **14.** The Earnest money deposit of the contractor whose tender is accepted shall be forfeited in full in case he does not start the work by the stipulated date mentioned in the letter of award.
- **15.** The Earnest money deposit of unsuccessful bidders will be refunded to them WITHOUT ANY INTEREST within 3 weeks from the date of award of work to the successful bidder.
- **16.** A certificate of completion shall accompany the final bill from the consultant. Payment of final bill shall be made after deduction of retention money as specified which sum will be refunded in the manner as stated conditions .In acceptance of payments of the final bill by the contractor would indicate that he will have no further claim in respect of the work executed.

17. CLEARING SITE ON COMPLETION

On completion of the work the contractor shall clear away and remove from the site all constructional plant, surplus materials, rubbish and temporary work of every kind and leave the whole of the site and the work clean and in workmanlike conditions to the satisfaction of the employer /consultant.

18. TERMS OF PAYMENT

- a) 85% can be claimed in phases in the form of two (2) running bills of the value of work
- b) 10% to be released after entire work is completed and handed over to the satisfaction and certification of the consultant.
- c) 5% to be released after the defect liability period of 12 months, without any interest.

19. IDLE LABOUR

Whatever the reasons may be no claim for idle labour; additional establishment cost of hire and labour charges of tools and plants would be entertained under any circumstances.

20. LIQUIDATED DAMAGE

The delivery and installation should be adhered to as stipulated time, failing which; liquidated damages @ 0.5% per week or part thereof subject to maximum of 10 % of the total order value shall be levied.

ARCHI SPACE CONSULTANT

21. TERMINATION OF CONTRACT BY EMPLOYER

If the contractor being a company go into liquidation whether voluntary or compulsory or being a firm shall be dissolved or being an individual shall be adjudicated insolvent or shall make an assignment or a composition for the benefit of the greater part, in number of amount of his creditors or shall enter into a deed or arrangement with his creditors, or if the Official Assignee in insolvency, or the Receiver of the Contractor in insolvency, shall repudiate the contract or, if a receiver of the contractor's firm appointed by the court shall be unable, within fourteen days after notice to him requiring him to do so, to show to the reasonable satisfaction of the Employer that he is able to carry out and fulfill the contract, and if so required by the Employer to give reasonable security there for, or if the Contractor shall suffer execution to be issued, or shall suffer any payment under this contract to be attached by or on behalf of and of the creditors of the Contractor, or shall assign, charge or encumber this contract or any payments due or which may become due to the contractor, there under or shall neglect or fail to observe and perform all or any of the acts matters of things by this contract, to be observed and performed by the contractor within three clear days after the notice shall have been given to the contractor observe or perform the same or shall use improper materials or workmanship in carrying on the work or shall in the opinion of the employer not exercise such due diligence and make such due progress as would enable the work to be completed within due time agreed upon and shall fail to proceed to the satisfaction of the employer after three clear days notice requiring the contractor so to do shall have been given to the contractor as hereinafter mentioned or shall abandon the contract, then and in any of the said cases, the employer may not withstanding previous waiver determine the contract by the notice in writing to the effect as hereinafter mentioned but without thereby affecting the powers of the employer of the obligations and liabilities of the contractor the whole of which shall continue in force as fully as if the contract had not been so determined as if the work subsequently executed had been executed by or on behalf of the contractor.

IF THE CONTRACT HAS BEEN TERMINATED THE EMPLOYER RESERVES THE RIGHT TO RECTIFY THE ITEMS AND COMPLETE THE JOB IN THE RISK AND COST OF THE TERMINATED VENDOR BY ANY OTHER APPROVED VENDOR.

ARCHI SPACE CONSULTANT

SECTION -III

FORM OF TENDER

То

The Deputy Zonal Head UCO Bank, Zonal Office, Suri Near Circuit House, Dist - Birbhum (W.B.) – 731 101

Sir,

Re: Interior Furnishing & Electrical work for the UCO BANK & ATM – RAGHUNATHGANJ BRANCH, MURSHIDABAD

- I/we refer to the tender notice issued by your consultants ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." – Gr. Floor, Kolkata – 700086 on your behalf for Interior & Electrical work in connection with the above.
- 2. I/We do hereby offer to perform, provide, execute, complete and maintain the work in conformity with drawings, conditions of contract specifications, bill of quantities for the sum of RS...... at the respective rates quoted in the schedule of quantities.
- **3.** I/We have satisfied myself/ourselves as to the site conditions, examined the drawings and all aspects of the site tender conditions. Subject to above, I/We do hereby agree, should this tender be accepted in whole or in part, to:
 - A: Abide by and fulfill all the terms and provisions of the said conditions annexed hereto
 - B: Complete the work within **15 days**, as stipulated in two or three shifts if considered necessary by the consultants at no extra cost to the Employer.
- 4. I/We have deposited earnest money of RS. _____ In the form of Crossed Demand draft / pay order /Banker's Cheque which, I/We note, will not bear any interest and is subject to forfeiture solely at Bank's discretion:
 - i. If the work is not commenced by me/us within 7(seven) days from the date of issue of formal work order

Or

- ii. If the offer is withdrawn within the validity period of acceptance.
- iii. If the contract is not executed within 90 days from award of contract.
- 5. I/We understand that you are not bound to accept the lowest or any tender you receive.

ARCHI SPACE CONSULTANT

- 6. The acceptance of this tender shall constitute a binding of any contract and any failure as mentioned in item 4. Above shall constitute a breach of contract by us and the tender accepting authority shall be entitled to have the work executed at our risk and to claim extra cost \ expenditure incurred by them from us.
- 7. Our Bankers

i)		
ii)		
iii)		

8. Name of partners / directors of our firm :

I.

II.

III.

IV.

Yours Faithfully
Signature
Name
Designation

ARCHI SPACE CONSULTANT

SECTION –IV ARTICLES OF AGREEMENT

Articles of agreement made the Day of Between the UCO Bank, Zonal Office, Suri, Near Circuit House, Dist -Birbhum (W.B.) - 731 101 (Hereinafter called the employer) which expression should include its successors and assignee of the one part and include its successor and assignee where as the employer is desirous of executing the Interior & Electrical works at UCO Bank & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD and has caused drawings and specifications describing the work to be prepared by ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." - Gr. Floor, Kolkata - 700086 (hereinafter called the consultants) and whereas the said drawings the Technical specifications and the schedule of items and quantities have been signed by and on behalf of the parties hereto. And whereas the contractor has agreed to execute upon and subject to the conditions set forth herein and schedule of items and quantities, General conditions of contract, special conditions including other conditions etc. technical specifications and all correspondences exchanged by or between the parties from the date of tender notice decision of negotiations meetings, if any, till the award of work, both letters inclusive, (all of which are collectively hereinafter referred to as the said conditions) the work shown upon the drawings and or described in the said specification and included in the schedule of items and quantities at the respective rates therein set forth amounting to the sum as therein arrived at or such other sum as shall become payable there under (Hereinafter referred to as the said contract amount)

NOW IT IS HEREBY AGREED AS FOLLOWS:

- 1. In consideration of the said contract amount to be paid at the times in the manner set forth in the said conditions, the contractor shall upon and subject to the said conditions execute and complete the work shown upon the drawings and described in the said specifications and the schedule of items and quantities.
- 2. The employer shall pay the contractor the said contract amount or such other sum as shall become payable, at the times and in the manner specified in the said conditions.
- 3. The consultant in the said conditions shall mean the said ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." Gr. Floor, Kolkata 700086 or in the event of their ceasing to be the consultant for the purpose if this contract for whatever reason such other person or persons as shall be nominated for that purpose by the Employer, provided always that the person subsequently appointed to be consultant under this contract shall be entitled to disregard or overrule any previous decision or approval or direction given or expressed in writing by the consultant for the time being.

ARCHI SPACE CONSULTANT

- 4. The said conditions and appendices thereto shall be read and considered as forming part of this agreement and the parties here to shall respectively abide by, submit themselves to the said conditions and perform the agreements on their part respectively in the said conditions contained.
- 5. The plan agreement and documents mentioned herein shall form the basis of this contract.
- 6. This contract is neither a fixed lump sum contract not a piece work in respect of **Interior & Electrical** works at **UCO Bank & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD** as per the scope described and to be paid for according to actual measured quantities at the rates contained in the schedule of rates probable quantities or as provided in the said conditions.
- 7. The employer reserves to itself the right of altering the drawings and nature of the work by adding to or omitting any items of work or having portions of the same carried out without prejudice to this contract.
- 8. Time shall be considered as the essence of this contract and the contractor hereby agrees to commence the work on the day on which he is instructed to take possession of the site, or from the 7th day after the date of issue of formal work order as provided for in the said conditions whichever is later and to complete the entire work within **30 days** subject nevertheless to the provisions for extension of time.
- 9. All payment by the Employer under this contract will be made only at UCO Bank, Zonal Office, Suri.
- 10. Any dispute arising under this agreement shall be referred to arbitration in accordance with the stipulation laid down in the general conditions of contract.
- 11. That the several parts of this contract have been read by the contractor and fully understood by the contractor.
- 12. This agreement can be terminated by either client on giving **3 months** notice normally however, in exigent circumstance; the services of the contractor can be terminated by giving notice of lesser period.

ARCHI SPACE CONSULTANT

IN WITNESS	WHEREOF the p	parties hereto	have hereunto	set their h	ands the day	y and year	r first a	bove
written.								

Signed, and delivered by	B	v the hands of	MR
orginea, and acrivered by	· D	y une nunus or	

(name and designation) it's-----and constituted attorney in the presence of

1. ----- 2. -----

Address-	Address-

Witness

Signed and delivered by the hands of MR Partner of					
in the presence of					
1	2				
Address-	Address				

ARCHI SPACE CONSULTANT

SECTION –V GENERAL CONDITIONS OF CONTRACT

Except where provided for in the description of the individual items in the schedule of quantities and in the specifications and conditions laid down hereinafter and in the drawings, the work shall be carried out as per standard specifications and under the direction of the employer /consultant.

1. INTERPRETATION:

In construing these conditions, the specifications the schedule of quantities tender and Agreement, the following words shall have the meaning herein assigned to them except where the subject or context otherwise requires.

2. EMPLOYER:

The term employer shall denote UCO Bank, Zonal Office, Suri, Near Circuit House, Dist –Birbhum (W.B.) – 731 101 or any of its employees representative authorized on their behalf.

3. CONSULTANT:

The term consultant shall mean ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." – Gr. Floor, Kolkata – 700086 or in the event of their ceasing to be consultant for the purpose of this contract such other persons /as the employer shall nominate for the purpose.

4. CONTRACTOR:

The term contractor shall mean the individual or firm or company whether incorporated or not, undertaking the work and shall include legal representative of such individual of such firm or company or successors of such firm or company as the case may be m and permitted assigns of such individual of firm or company.

5. SITE:

The site shall mean the site where the work is to be executed at UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD.

6. DRAWINGS:

The work is to be carried out in accordance with drawings, specification, the schedule of quantities and any further drawings, which may be supplied, or any other instructions, which may be given by the employer consultant during the execution of the work. All drawings relating to work given to the contractor together with a copy of specification and schedule of quantities are to be kept at site and the employer /consultant shall be given access to such drawings or schedule of quantities wherever necessary.

In case any detailed drawings are necessary contractor shall prepare such detailed drawings and or dimensions sketches there for and have it confirmed by the employer consultant prior to taking up such work. The contractor shall ask in writing for all clarifications on matters occurring anywhere in drawings, specifications and schedule of quantities or to additional instructions at least 20 days ahead from the time when it is required for implementation so that the employer /consultant may be able to give decision thereon. The work shall mean the work to be executed or done under this contract.

1. SCOPE:

The work consists of Interior, Civil & Electrical works for UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD. In accordance with the drawings, specifications and schedule of items and quantities. It includes furnishing all material, labour, tools and equipment and management necessary for and incidental to the construction and completion of the work. All work during its progress and upon completion, shall confirm to the lines, elevations and grades as shown on the drawings furnished by the employer /consultant and to furnish by the employer/consultant. Should any detail essential for efficient completion of the work be omitted from the drawings and specification it shall be the responsibility of the contractor to inform the employer /consultants concurrence, so that upon completion of the proposed work the same will be acceptable and ready for use.

Employer/consultant may in their absolute discretion issue further drawings and or written instructions, details, directions and explanations which are here after collectively referred to as the employer /consultants instructions in regard to:

A: The variation on modification of the design, quality or quantity of work or the addition or omission or substitution of any work:

B: Any discrepancy in the drawings or between the schedule of quantities and or drawings and or specification.

C: The removal from the site of any defective material brought thereon by the contractor and the substitution of any other material thereof.

D: The demolition removal and /or rejection of any work executed by the contractor /s

E: The dismissal from the work of any persons employed thereupon.

F: The opening up for inspection of any work covered up.

G: The rectification and making good of any defects under clauses hereinafter mentioned and those arising during the maintenance period (retention period)

The contractor shall forthwith comply with and duly execute any work comprised in such employer/consultants instructions provided always that verbal instruction direction and explanations given to the contractor or his representative upon the work by the employer/consultant shall if involving a variation be confirmed in writing to the contractor within seven days. No work for which rates are not specifically mentioned in the priced Schedule of quantities shall be taken up without written permission of the employer/consultant. The employer in consultation with the consultant shall fix rates of items not mentioned in the priced schedule of quantities.

ARCHI SPACE CONSULTANT

2. DETAILED DRAWINGS AND INSTRUCTIONS

The employer through its consultant shall furnish with reasonable promptness additional instructions by means of drawings or otherwise necessary for the proper execution of the work. All such drawings and instructions shall be consistent with the contract documents true developments thereof and reasonably inferable there from.

The work shall be executed in conformity therewith and the contractor shall not work without proper drawings and instructions.

Immediately after receipt of the work order of the contract the contractor shall prepare a program schedule and submit the same to the employer through the consultant for approval which shall indicate the dates for the starting and completion of the various activities at the stages of construction.

3. COPIES FURNISHED

The contractor on the signing hereof shall be furnished by the employer through its consultant free of charge with a copy of the priced schedule of quantities rates, two copies of each of the said drawings and one copy of specifications and two copies of all further drawings issued during the progress of the work. Any further copies of such drawings required by the contractor shall be supplied on payment of the charges thereof by the contractor.

4. OWNERSHIP OF DRAWINGS

All drawing specification and copies thereof furnished by the employer through its consultants are the property of the employer. They are not to be used on other work, and with the execution of the signed contract set are to be returned to the employer on request at the completion of the work.

5. FAILURE BY CONTRACTORS TO COMPLY WITH EMPLOYERS / CONSULTANTS INSTRUCTION

If the contractor after receipt of written notice from the employer and or the consultant requiring compliance within ten days fails to comply with such further drawings and or employer /consultant instructions, the employer through the consultant or other persons, may employ other persons to execute any such work whatsoever that may be necessary to give effect thereto and pay all cost incurred in connection therewith and same shall be recoverable from the contractor by the employer on the certificate of the consultant as a debt or shall have right to deduct same form any money due or to become due to the contractor.

6. TENDERER SHALL VISIT THE SITE

Intending tendered shall visit the site and make himself thoroughly acquainted with the local site condition, nature and requirements of the work, facilities of transport condition, effective labor and materials, access and storage for materials and removal of rubbish. The tenderer shall provide in their tender for cost carriage, freight and other charges including all taxes etc. as also for any special difficulties and including police restriction for transport etc for proper execution of work as indicated in the drawings. The successful tenderer will not be entitled to any claim of compensation for difficulties faced or losses incurred on account of any site condition which existed before the commencement of the work or which in the opinion of the employer /consultant might be deemed to have reasonably been inferred to be so existing before commencement of work.

ARCHI SPACE CONSULTANT

7. TENDERS

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initial/signature will indicate the acceptance of the tender papers by the tenderer.

The schedule of quantities shall be filled in as follows:

- 1. The Rate column to be legibly filled in ink in both English figures and English words.
- 2. Amount column to be filled in for each item and the amount for each subhead as detailed in the schedule of quantities.
- 3. All corrections overwriting are to be initialed with the seal of the firm.
- 4. In case of any errors/omissions in the quoted rates, the rates given in the tender.

No modification writing or corrections can be made in the tender papers by tenderer.

The employer reserves the right to reject the lowest or any tender and also to discharge any or all of the tenders for each section or to split up each and every item should be correct, workable and self-supporting. If called upon by the employer consultant detailed analysis of any or all the rates shall be submitted .The employer/consultant shall not be bound to recognize the contractor analysis.

The work will be paid for as measured work on the basis of actual work done and not as lump sum contract.

All items of work described in the schedule of quantities are to be deemed and paid as complete work in all respects and details including preparatory and finishing work involved, directly, related to and reasonably detectable from the drawings specification and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lum-sum charges in the tender in respect of any item or work, the payment of such time of work will be made for the actual work done the basis of lum-sum charges as will be assessed to be payable by the employer consultant.

The employer has power to add to omit from any work as shown in drawings or described in specifications or included in schedule of quantities and intimate the same in writing but no addition, omission or variation shall be made by the contractor without authorization from the employer no variation shall vitiate the contract.

8. AGREEMENT

The successful contractor shall sign the agreement as per draft agreement within 15 days from the date of issue of formal work order and he shall pay for all stamps and legal expenses, incidental thereto. However the written acceptance of the tender by the employer /consultant on behalf of employer will constitute a binding contract between the employer and the person so tendering whether such formal agreement is or is not subsequently executed.

9. ROYALTIES & PATENTS

The contractor shall pay all royalties and license fees. He shall defend all suits or claims for infringement of any patent rights and shall save the employer harmless from loss on account thereof.

ARCHI SPACE CONSULTANT

10. PERMITS AND LICENCES

Permits and licenses for release of materials which are under government control will be arranged by the contractor .The employer will render necessary assistance, sign any forms or applications that may be necessary.

11. GOVERNMENT AND LOCAL RULES

The contractor shall confirm to the provisions of all local to the provisions of all local bye-laws and acts relating to the work and to the regulations etc. of the government and local authorities and of any company with whose system the structure is proposed to be connected. The contractor shall give all notices required by the said act, rules, regulations and bye laws etc and pay all fees payable to such authority for execution of the work involved .The cost, if any shall be deemed to have been included in his quoted rates, taking into account all liabilities for licenses, fees for footpath encroachment and restorations etc. and shall indemnify the employer against such liabilities and shall defend all actions arising from such claims or liabilities.

12. TAXES AND DUTIES

The tenderers must include in their tender prices quoted for all duties, royalties, excise, sales tax, work contract tax or any other taxes or local charges if applicable. No extra claim on this account will in any case be entertained.

13. QUANTITY OF WORK TO BE EXECUTED

The quantities shown in the schedule of quantities are intended to cover the entire new structure indicated in the drawings but the employer reserves the right to execute only a part or the whole or any excess thereof without assigning any reason therefore. If at any after the commencement of the work, the employer consultant shall for any reason whatsoever not require the whole work thereof as specified in the tender to be carried out the consultant employer shall give notice in writing of the fact to the contractor who shall have no claim to any payment for compensation whatsoever on account of any profit or advantage with which he might have derived from the execution of the work in full, but which he did not derive in consequence of the full amount of the work not having been carried out, neither shall he have any claim for compensation by reason of any alterations having been made in the original specification ,drawings ,designs and instructions which shall involve any curtailment of the work as originally contemplated.

14. EARNEST MONEY /SECURITY DEPOSIT & RETENTION MONEY

The tenderer will have to deposit an amount of **Rs 20000.00/-** in the form of crossed demand Bank Draft/Pay Order/Banker's cheque drawn in favor of UCO payable at Suri from any nationalized Bank at the time of submission of tender as an earnest money. The employer is not liable to pay any interest on the earnest money. The earnest, money of the unsuccessful tenderers will be refunded without any interest 21 days after the decision to award the work is taken or after the expiry of the validity period of the tender, whichever is earlier.

Retention money will be deducted from interim bills @ 5 % of the accepted value of the tender. This retention money shall be refunded to the successful contractor without any interest 14 days after successful completion of the defects liability period of 12 months provided the contractor has satisfactorily carried out all the work and attended to all defects in accordance with the condition of the contract. In case the contractor fails to do so appropriate amount shall be deducted by the Bank from retention money.

ARCHI SPACE CONSULTANT

15. CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein the shall immediately and in writing refer the same to the employer /consultant whose decision shall be final and binding. The contractor shall provide himself for ground and fresh water for carrying out the work at his own cost. The employer shall on no account be responsible for the expenses incurred by the contractor for hired ground of fresh water obtained from elsewhere. The rates quoted against individual items will be inclusive of everything necessary to Complete the said items of work within the contemplation of the contract, and beyond the unit price no extra payment will be allowed for incidental or contingent work, Labour and /or materials inclusive of all tax and duties whatsoever except for specific items, if any stipulated in the tender documents.

The contractor shall supply fix and maintain at his own cost for the execution of any work all tools tackles machinery's and equipment's and all the necessary centering, scaffolding, staging, planking, timbering, strutting, shoring, pumping, fencing, boarding, watching and lighting by night as well as by day required not only for the proper execution and protection of the public and safety of any adjacent roads, streets, walls houses buildings all other erections matters and things and the contractor shall take down and remove any or all such centering ,scaffolding, planking ,timbering etc shall be required or when so to do and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of the employer/consultant.

16. TIME OF COMPLETION, EXTENSION OF TIME AND PROGRESS CHART

A. TIME OF COMPLETION:

The entire work is to be completed in all respects within the stipulated period of **15** days, from the date of issue of formal work order. Time is the essence of the contract and shall be strictly adhered to by the contractor.

The work shall not be considered as complete until the employer consultant have certified in writing that this has been completed and the defects liability period shall commence from the date of such certificate.

B. PROGRAMME CHART TO BE PROVIDED

During the period of construction the contractor shall maintain proportionate progress on the basis of the program chart submitted by the contractor immediately before commencement of work and agreed to by the employer consultant.

17. CLEARING SITE AND SETTING OUT WORK

The site shown on the plan shall be cleared of all obstruction, loose stone and materials rubbish of all kinds.

ARCHI SPACE CONSULTANT

18. MATERIALS WORKMENSHIP, SAMPLES, TESTING OF MATERIALS

All the materials specified to be maintained and the contractor shall have to carry out tests on materials and workmanship in approved materials testing laboratories or as prescribed by the employer.

19. REMOVAL OF IMPROPER WORK

The employer consultant shall during the progress of the work have power to order in writing from time to time the removal from the work within such reasonable time to times as may be specified in the order of any materials which in the opinion of the employer consultant are not in accordance with specifications or instruction. In case the contractor refuses to comply with the order the employer consultant shall have the power to employ and pay other agencies to carry out the work and all expenses consequent thereon or incidental thereto as certified by the employer consultant shall be borne by the contractor or may be deducted from any money due to or that may become due to the contractor .No certificate, which may be given by the consultant, shall relieve the contractor from his liability in respect or unsound work or bad materials.

20. MEASUREMENT

The consultant shall from time to time intimate to the contractor that he requires the work to be measured, and the contractor shall forthwith attend or send a qualified agent to assist the consultant or the consultants representative/employers representatives in taking such measurements and calculations and to furnish all particulars or to give all assistance required by either of them.

21. ACTION WHERE NO SPECIFICATION

In the case of any class of work for which there is no such specification in technical specification, such work shall be carried out in accordance with the I.S. specification and in the event of there being no I.S. specification, then in such case the work shall carried out in all respect in accordance with the instructions and requirements of the consultant /employer.

22. CONTRACTOR NOT TO DEPOSIT MATERIALS IN A MANNER THAT MAY CAUSE INCONVENIENCE TO THE PUBLIC.

The contractor (s) shall not deposit materials on any site, which will seriously cause inconvenience to the public. The Consultant may require the contractor to remove any materials, which are considered by him to be a danger or inconvenience to the public or cause them to be removed at the contractor's cost.

23. PAYMENTS

- a) All bills shall be prepared by the Contractor in the form prescribed by the Employer/Consultant, format enclosed. In the bill it has to be shown deductions for all previous payments, retention money, etc. Advance / adhoc payment for work actually executed will not be normally made. However, adhoc payment may be made at the discretion of Consultant /Employer in case of exigency.
- b) The Consultant /Employer shall issue a certificate after due scrutiny of the Contractor's bill stating the amount due to the Contractor from the Employer and the contractor shall be entitled to payment thereof, by the Employer.

ARCHI SPACE CONSULTANT

- 24. The contractor shall work in close co ordination with other agencies to avoid rework/damage and ensure timely completion.
- 25. Any damage to the work before the building is handed over is to be replaced or made good at contractor expense to the entire satisfaction of the consultant.
- 26. The quantities indicated are subject to change .The payment of the bill will be made as per actual measurement at site and will be certified by the Consultant and cleared by the employer.
- 27. The tender shall sign each and every page of the tender documents including the drawings attached hereto.
- 28. The consultant shall have power to insist to the contractor to submit the sample /color/ test certificate from any Govt. Authorized agent of any materials to be used in the work, where the expenditure is to be borne by the contractor.
- 29. 5 % of the total value of work will be retained as retention money from Contractor's bills which shall be released without any interest after the defect liability period of six months provided the contractor has satisfactorily attended to all defects if any, in this period.
- 30. In case of any dispute the matter will be referred to the Dy. General Manager, Head Office, Suri for an arbitration, whose decision shall be final and binding on both parties.
- 31. For litigation if any arising thereof, the competent court at Bombay alone will have jurisdiction.

ARCHI SPACE CONSULTANT

SECTION VI SPECIAL TERMS AND CONDITIONS

1. Name of the work :	Interior & Electrical works for UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD.
2. Location:	VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.SRAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,
3. Scope of Work :	As in 1 & 2 above and as further detailed in Instruction to Tender
4. Date of Commencement :	Within 3(Three) days from issue of work order.
5. Defect liability period :	12 (Twelve) months from the date of completion Certificate Issued by the consultant/employee
6. Earnest Money :	Rs20000.00 /-
7. Initial security deposit :	 a) the amount of initial security deposit shall be 2% of the accepted value of the tender including the earnest money deposit. b) The initial security deposit is to be paid by the Contractor to the bank within 14 days of Intimation to him of the acceptance of tender.
8. Limit of variation :	No extra /additional work should be carried out by the contractors without prior consent approval .Any sample to be made shall be At your cost for approval.
9. Validity of the tender :	3 (Three) months after opening the tender
10. Insurance :	Successful contractors shall have to take out statutory labour laws, workmen compensation Act, Insurance policy/Comprehensive Insurance policy for the duration of the work covering all aspects such as fire hazards, earthquake, third party risk etc. They should submit receipt of premium paid to the UCO BANK, Suri Zonal Office Prior to commencement of the work.

11. Completion time and Liquidated Damage :	The entire job will be completed within 15days (Fifteen days) from the date of the work order. In the event of your failure to complete the work In all respects including site clearance and Reinstatement of damaged proportion within The stipulated time. Liquidated damage @ 0.50% per week of delay or part thereof shall be levied subject to a maximum of 5% of the total order value.
12. Return of EMD to unsuccessful Bidders :	The Earnest money deposit of unsuccessful bidders will be refunded to them WITHOUT ANY INTEREST within 21days from the date of award of work to the successful bidder.
13. Force Majeure:	Any delay in or failure of the performance of either part hereto shall not constitute Default hereunder or give rise to any Damage, if any, to the extent such delay Or failure of performance is caused by occurrences such as Acts of god or an Enemy, expropriation or confiscation of facilities by Government authorities, Acts of war, rebellion, sabotage or fires, Floods, explosions, riots or strikes. The contractor shall keep records of the Circumstances referred to above and bring These to the notice of the Engineer-in-Charge / site – In charge in writing Immediately on such occurrences. The Amount of time, if any, lost on any of These Counts shall not be counted for the contract Period. One decision of the owner arrived. At after consultation with the contractor, shall be final and binding. Such a determined period of time shall extended by the owner to enable the contractor to complete the job within such extended period of time. If the contractor is prevented or delayed from performing any of his obligations under This agreement by force majeure, the contractor shall owner the circumstance constituting the force majeure and the obligations, performance of which is thereby delayed or prevented, within seven days of the occurrence of the events.

ARCHI SPACE CONSULTANT

CERTIFICATE

1.	The Measurement on the basis of which the above entries for the running bill
	nowere made have been taken jointly on
	and are recorded at pages
	toof measurement book no

2. The work recorded in the above mentioned measurement has been done at the site satisfactorily as per tender drawings, conditions and specifications.

Signature of the contractor consultant		Signature of the
Signature of the Employer		
Date:	Date:	Date:
Place:	Place:	Place:
We hereby certify that an amount (Rupees		
noDated	subject to verification of all other erials supplied to the contractor, i tal payment including this should	previous payments, if any made to if any ,and income tax and any other

SIGNATURE OF CONSULTANT

ARCHI SPACE CONSULTANT

PROFORMA FOR APPLICATION FOR EXTENSION OF THE TIME PERIOD

- 1. Name of the contractor:
- 2. Name of the work as given In the agreement:
- 3. Agreement No:
- 4. Estimated tender amount:
- 5. Date of commencement of work As per agreement:
- 6. Period for which extension of time Has been given previously:

Extension vide consultant's Employer's letter

No	Dated	Month	Days
A)			
B)			
C)			

- 7. Period for which extension is applied Is applied for:
- Hindrances on account of which Extension is applied for with dates on Which hindrances occurred and the Period for which these are likely to last:

a)	Serial	No.
----	--------	-----

b) Nature of hindrance	:
c) Date of occurrence	:
d) Period for which it is likely To last	:
e) Period for which extension Required for this particular Hindrance	:
f) Net extension applied for	:
g) Remarks if any	:
9. Extension of time required For extra work	:
10. Extension of time required For extra work	:
11. Details of extra work and The Amount involved	:
12. Proportionate period of Extension of time on estimated	
Amount put to tender 13. Total extension of time required for Submitted to the consultant / employ	

Date.....

Signature of the contractor DATE:

CONTRACTORS ARE REQUESTED TO VISIT THE SITE AND COLLECT ALL OTHER NECESSARY DETAIL DRAWINGS FROM THE CONSULTANTS OFFICE BEFORE QUOTING.

FOR ANY CONFUSION IN THE DRAWING AND SPECIFICATION PLEASE CLARIFY WITH THE CONSULTANT BEFORE THE TENDER OPEN.

NO EXTRA WILL BE PAID TO COMPLETE ONE SINGLE ITEM MENTIONED IN THE TENDER

B.O.Q. FOR ELECTRICAL WORKS OF PROPOSED BANK & ATM AT RAGHUNATHGANJ BRANCH, MURSHIDABAD

OWNER : UCO BANK

ZONAL OFFICE -UCO Bank, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

BRANCH ADDRESS :

VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.S.-RAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,

CONSULTING ARCHITECT - ARCHI SPACE CONSULTANT

ADDRESS: 45B, "AMELIA APARTMENT", GROUND FLOOR,

BINNAGAR, NEAR BAGHAJATIN STATION,

KOLKATA - 700086

CONTACT - 9830006396, 033-2425-0125

DATE : 11.08.17

	ELECTRICAL WORK OF BANK B.O.Q RAGHUNA	THGAI	NJ BR	ANCH.			
SR.NO		QTY.		RATE (Rs.			
	nstallations shall comply with the requirements of the Indian Electricity Ru						
	as per relevant clauses of National Electrical Code, 1985. Installations sho			•			
	Standard Code of Practice for electrical wiring installation IS. 732-1963 and IS 2274-1963. It shall also be in conformity with the regulations and requirements of the Local Electric Supply Authority. Wherever these specifications call for a						
	her standard of materials and / or workmanship than those required by an						
_	cification shall take precedence over the said regulations and workmans			-			
	firm to the Indian standards, unless otherwise called for. Equipment shall b	be given	tropic	al and fung	gicidal treatment		
as r	per IS – 3202						
a	MAIN PANEL : Supply, Installation, Testing, Erection and commissioning of Distribution Boa	rds Floo	r wall n	ounted in	cluding		
ŭ	transportation to site of erection, for phase, neutral & earth as required, all o				libuling		
	Distribution Boards (All MCbs "C" series)						
a.1	8 way TPN double door DB with in corner 63 Amps 10 KA TPN MCB	1	No.				
	Controlling 18 Nos. 10 Amps SPMCBs						
a.2	UPS DB : 8 way SPN MCB DB with incomer 25 Amps DP, MCB and	1	No.				
u.z	outgoing for 6 Nos. Of SP MCB set		INO.				
a.3	Supply & fixing of 25 Amps SP MCB with Metal Glad Plug and Socket	3	Nos.				
u.5	controlled with suitable metal enclosure box set etc.	3	1103.				
a.4	Supply & Fixing 40 A DP MCB with M/S encloser for UPS incoming &	2	Nos.				
	outgoing power supply.						
a.5	63 A. 4 pole changeover switch (on load type)	1	No.				
a.6	Phase indicating lamp & controls with wiring (15W lamp Red, yellow &	3	Nos.				
a.7	63 A. 4 pole moulded case circuit breaker	2	Nos.				
a.8	Supply & fixing 415 V grade 5 to 20 amp range TPN KWH meter	1	No.				
b.	POINT WIRING :		1	1			
	copper flexible wire maintaining the colour code as per direction in PVC wall thk. to conceal in wall partition mending good the damage, compl done as per drawing including 3 point ceiling rose where ever required. C conduit/ flexible pipe may use if required in partition wall. All pvc pipes s allowed inside pipe.Light, fan & plug point complete with modular type circuit line 2x2.5mmsq+1x1.5mmsq earth PVC insulated Cu. Wire, maintain lighting switch board ,6 Amps plug board are to be drawn from lighting E board, 6/16 Amps plug point line are to be drawn from power DB. 3 Nos libe connected from one circuit & 02 Nos. 6/16 plug to be connected from from floor).	ete with GI saddle hould be switch p ning the DB to Ligh ighting b	pvc ci e to be e with IS late & colour nting b	rcular box, used for fiz SI mark. No MS box. Ind code. Circ oard & 6A D3 Nos.6 Ar	bend to be king, pvc o joints will be cluding the main cuit line for plug point mps plug are to		
b.1	One Light point to be controlled by a 6A switch	25	Nos.				
b.2	Wall Mounting type fan Point controlled by 6A switch	15	Nos.				
b.3	Exhaust Fan Point controlled by a 6A switch	4	Nos.				
с.	POWER WIRING						
- 1	Supply, Laying of Circuit line2x2.5mmsq +1x 1mmsq VC insulated	400	ЪĤ				
c.1	copper wire form LDB to 6/16A or 6 Amps Plug point. Also note that 03 Nos 06 amps Plug to be connected from one circuit line	400	R.ft.				
c.2	Providing & fixing Computer Plug Points with 4 Nos. 16 Amp sockets. & 4 Nos. 16 AMP Switch complete with all necessary accessories.	6	Nos.				
c.3	Socket point wiring with 6 amps 5 pin with controlling switch on board	6	Nos.				
d.	UPS WIRING						
d.1	Supply laying of circuit line 2 x 2.5 Sq.mm + 1 x 1.5 Sq.mm MSCC PVC insulated wires drawn in 20 mm dia PVC conduit pipe with ISI mark from UPS DB to computer.	400	R.ft.				
d.2	Supply laying of circuit line 2 x 6 Sq.mm + 1 x 1.5 Sq.mm MSCC PVC insulated wire through suitable size PVC conduit pipe with ISI mark from main DB to UPS incoming power DP controlling MCB	50	R.ft.				
	Supply laying of circuit line 2 x 6 Sq.mm + 1 x 1.5 Sq.mm MSCC PVC	I	1	T			

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)
e.	UPS CLUSTER POINT	8	Nos.		
	Supply fixing of 2x6 Amps 5 pin socket + 1x16 amps 6 pin socket in with				
	controlling switch MS box front plate with inter connection complete				
	each work station				
f.	TELEPHONE WIRING :				
f.1	Telephone Wiring : Supply & laying of 2 pair PVC insulated wire , 0.5 mm down through PVC conduit pipe	100	R.ft.		
f.2	Supply & fixing of telephone outlet RJ-111 socket with suitable mounting box with front plate	2	Nos.		
f.3	Supply & fixing of telephone Junction box 10 pair krone type housed in MS box with Lock & key.	1	No.		
g.	A/C. ELECTRIFICATION :-				
g.1	Supply laying & connection of A/C. line for 1.0 TR A/C. window / split with 2x4 + 1x2.5 mmsq through 16 SWG pvc conduit with ISI Mark.	100	R.ft.		
g.2	Supply laying & connection of A/C. line for 2TR A/C. window / split with 2x6 + 1x4 mmsq through 16 SWG pvc conduit with ISI Mark.	150	R.ft.		
g.3	Supply, fixing of A/C. 11-18 Amps stator complete with 20 amps socket in modular type box for split / window unit at 4.5 Ft from floor.	2	unit		
g.4	Supply, fixing of A/C. 18-25 Amps stator complete with 20 amps socket in modular type box for split / window unit at 4.5 Ft from floor.	3	unit		
h.	GLOW SIGN BOARD WIRING :-				
h.1	Out door type Glow Sign board wiring :-Supply, laying of main line with 2x2.5 +1x1.5 mmsq through pvc conduit from main panel to glow sign	50	R.ft.		
	Supply installation of 16 amps DP mcb at main entrance Glow sign				
h.2	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original	1	Set		
h.2 i .		1	Set		
	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll	owing fi	xtures in		
	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore	owing fi scent fix	xtures in ctures (e	except dow	n lighters) to be
	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON	owing fi scent fix	xtures in ctures (e	except dow	n lighters) to be
i.	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods.	owing fi scent fi> False co	xtures in ttures (e eiling a	except dow	n lighters) to be
i .	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa	owing fi scent fix False co 2	xtures in tures (e eiling a Nos.	except dow	n lighters) to be
i . i.1 i.2	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5.	owing fi scent fix False co 2 18	xtures in tures (e eiling a Nos. Nos.	except dow	n lighters) to be
i. i.1 i.2 i.3	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5.	owing fi scent fix False co 2 18 2	xtures in ttures (e eiling a Nos. Nos.	except dow	n lighters) to be
i. i.1 i.2	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing 400 mm sweep Wall Mounting Fan	owing fi scent fix False co 2 18	xtures in tures (e eiling a Nos. Nos.	except dow	n lighters) to be
i. i.1 i.2 i.3 i.4 i.5	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing 400 mm sweep Wall Mounting Fan Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan	owing fi scent fix False co 2 18 2 15	xtures in ttures (e eiling a Nos. Nos. Nos. Nos.	except dow	n lighters) to be
i.1 i.2 i.3 i.4	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing 400 mm sweep Wall Mounting Fan Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION :	owing fi scent fix False co 18 2 15 4	xtures in tures (e eiling a Nos. Nos. Nos. Nos. Nos.	except dow rea they are	n lighters) to be to be hung by
i. i.1 i.2 i.3 i.4 i.5	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth	owing fi scent fix False co 2 18 2 15 4 station	xtures in tures (e eiling a Nos. Nos. Nos. Nos. Nos.	except dow rea they are	n lighters) to be to be hung by
i. i.1 i.2 i.3 i.4 i.5	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS-	owing fi scent fix False co 2 18 2 15 4 station 3043.	xtures in tures (e eiling a Nos. Nos. Nos. Nos. Nos.	except dow rea they are	n lighters) to be to be hung by
i. i.1 i.2 i.3 i.4 i.5	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth	owing fi scent fix False co 2 18 2 15 4 station 3043.	xtures in tures (e eiling a Nos. Nos. Nos. Nos. Nos.	except dow rea they are	n lighters) to be to be hung by
i. i.1 i.2 i.3 i.4 i.5 j.	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications.	owing fi scent fix False co 2 18 2 15 4 station 3043.	xtures in tures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch	except dow rea they are	n lighters) to be to be hung by
i. i.2 i.3 i.4 j.	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station	owing fi scent fix False co 2 18 2 15 4 station 3043. ing sizes	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos.	except dow rea they are	n lighters) to be to be hung by
i. i.2 i.3 i.4 i.5 j. j. j.1 j.2	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat	owing fi scent fix False co 18 2 15 4 station 3043. ing sizes 1	xtures in stures (e eiling a Nos. Nos. Nos. Nos. and Ch of con No.	except dow rea they are	n lighters) to be to be hung by
i. i.2 i.3 i.4 j.	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station	owing fi scent fix False co 2 18 2 15 4 5 4 5 4 5 4 5 4 5 4 5 4 5 4 5 4 5	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft.	except dow rea they are	n lighters) to be to be hung by
i. i.1 i.2 i.3 i.4 i.5 j. j. j.1 j.2 j.3	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire	owing fi scent fix False co 2 18 2 15 4 5 4 5 4 5 4 5 4 5 4 5 4 5 4 5 4 5	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft.	except dow rea they are	n lighters) to be to be hung by
i. i.2 i.3 i.4 i.5 j. j. j.1 j.2 j.3 k.	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire OTHER ITEMS Pump Line Wiring by 2x2.5 + 1x1.0 Sq mm PVC Copper wire and PVC	owing fi scent fix False co 18 2 15 4 3043. ing sizes 1 80 80	xtures in tures (e eiling an Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft. R.ft.	except dow rea they are	n lighters) to be to be hung by
 i.1 i.2 i.3 i.4 i.5 j.1 j.2 j.3 k. k.1 k.2 	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire OTHER ITEMS Pump Line Wiring by 2x2.5 + 1x1.0 Sq mm PVC Copper wire and PVC Cassing complete. Labour charges for removal of Existing Electric Fittings, fixtures & wiring including scrap removal etc. TOTAL ELECTRICAL WORKS	owing fi scent fix False co 2 18 2 15 4 station 3043. ing sizes 1 80 80 1 1	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft. R.ft. Job	except dow rea they are	n lighters) to be to be hung by
 i.1 i.2 i.3 i.4 i.5 j.1 j.2 j.3 k. k.1 k.2 	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire OTHER ITEMS Pump Line Wiring by 2x2.5 + 1x1.0 Sq mm PVC Copper wire and PVC Cassing complete. Labour charges for removal of Existing Electric Fittings, fixtures & wiring including scrap removal etc. TOTAL ELECTRICAL WORKS WORDS :	owing fi scent fix False co 2 18 2 15 4 station 3043. ing sizes 1 80 80 1 1	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft. R.ft. Job	except dow rea they are	n lighters) to be to be hung by
i. i.2 i.3 i.4 i.5 j. j. j.1 j.2 j.3 k. k.1 k.2	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (?") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire OTHER ITEMS Pump Line Wiring by 2x2.5 + 1x1.0 Sq mm PVC Copper wire and PVC Cassing complete. Labour charges for removal of Existing Electric Fittings, fixtures & wiring including scrap removal etc. TOTAL ELECTRICAL WORKS WORDS : Excluded Items	owing fi scent fix False co 2 18 2 15 4 station 3043. ing sizes 1 80 80 1 1	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft. R.ft. Job	except dow rea they are	n lighters) to be to be hung by
 i.1 i.2 i.3 i.4 i.5 j.1 j.2 j.3 k. k.1 k.2 IN V 1 	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (9") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire OTHER ITEMS Pump Line Wiring by 2x2.5 + 1x1.0 Sq mm PVC Copper wire and PVC Cassing complete. Labour charges for removal of Existing Electric Fittings, fixtures & wiring including scrap removal etc. TOTAL ELECTRICAL WORKS WORDS : Excluded Items U.P.S. server and LAN server machine	owing fi scent fix False co 2 18 2 15 4 station 3043. ing sizes 1 80 80 1 1	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft. R.ft. Job	except dow rea they are	n lighters) to be to be hung by
i. i.2 i.3 i.4 i.5 j. j.1 j.2 j.3 k. k.1 k.2 IN V	board complete with timer & contractor (2NO + 2NC). 24 Hrs in original ELECTRICAL FIXTURES : Item includes Providing , assembling , fixing , testing & commissioning foll lamps & extension chords as maybe necessary complete.All LED / Fluore hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON appropriate down rods. Buzzer or calling of Bajaj / Anchor / National / Homa Supply & Fixing of 4 ft Long light Fittings T-5. Supply & Fixing of 2 ft long Light Fittings T-5. Supply & Fixing of 225 mm (?") dia sweep Exhaust Fan EARTHING STATION : Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth complete with civil works, etc. as per specs in accordance with latest IS- Earthing conductors : Supply & laying of equipment earthing using follow accessories to erect/lay the conductor & as per specifications. 50 mm dia 3 mtr long pipe electrode earth station 25 x 3 mm Copper flat 8 SWG Copper bare wire OTHER ITEMS Pump Line Wiring by 2x2.5 + 1x1.0 Sq mm PVC Copper wire and PVC Cassing complete. Labour charges for removal of Existing Electric Fittings, fixtures & wiring including scrap removal etc. TOTAL ELECTRICAL WORKS WORDS : Excluded Items	owing fi scent fix False co 2 18 2 15 4 station 3043. ing sizes 1 80 80 1 1	xtures in stures (e eiling a Nos. Nos. Nos. Nos. Nos. and Ch of con R.ft. R.ft. Job	except dow rea they are	n lighters) to be to be hung by

-

	ELECTRICAL WORK OF ATM B.O.Q RAGHUNATH	IGANJ	BRAN	CH.	
SR.NO	DESCRIPTION	QTY.	UNIT	RATE (R	s. AMOUNT (Rs.)
as per Code regula stand take p	tallations shall comply with the requirements of the Indian Electricity Rules r relevant clauses of National Electrical Code, 1985. Installations shall conf of Practice for electrical wiring installation IS. 732-1963 and IS 2274-1963. In ations and requirements of the Local Electric Supply Authority. Wherever the ard of materials and / or workmanship than those required by any of the corecedence over the said regulations and workmanship not covered by the ards, unless otherwise called for. Equipment shall be given tropical and func-	form in a t shall al nese spe above re ne above	II respe so be ir cificati gulatio e shall o	cts to Inc n conform ons call fo ns, this sp confirm to	lian Standard hity with the or a higher ecification shall o the Indian
а.	Distribution Boards :	1			
a.1	UPS input output : 63 AMP / 40 AMP DP MCB box	2	No.		
a.2	ATM : 63 Amps/40 Amps DP MCB in MS enclosure box.	1	No.		
a.3	Supply & fixing 250 V grade 5 to 20 amp range single phase KWH meter in ATM.	1	No.		
a.4	Distribution Boards (All MCbs "C" series) : Providing and fixing 6 way TPN double door DB for light points with 63 Amps 10KA TPN MCB Controlling 18 Nos. 10 Amps SPMCBs.	1	No.		
b.	POINT WIRING : ply,laying, connection & testing of light, fan point, wiring by 2x1.5mmsq(2)				
ma & p 2x2 ,6Ai are	wing including 3 point ceiling rose where ever required. GI saddle to be u y use if required in partition wall. All pvc pipes should be with ISI mark. No lug point complete with modular type switch plate & MS box. Including t .5mmsq+1x1.5mmsq earth PVC insulated Cu. Wire, maintaining the colour mps plug board are to be drawn from lighting DB to Lighting board & 6A p to be drawn from power DB. 3Nos lighting board/ 03 Nos.6Amps plug are	joints wi he mair code. C blug poir to be co	ill be al n circuit ircuit lir nt board onnect	lowed ins [.] line ne for ligh d, 6/16 Ar	ide pipe.Light, fan ting switch board nps plug point line
b.1	5. 6/16 plug to be connected from one circuit (Lighting S.Board height-32" One light Point controlled by a 16A switch	trom floo	or). Nos.		<u> </u>
0.1		5	1103.		
c.	POWER WIRING				
c.1	Socket point wiring with 6 amps 5 pin with controlling switch on board	2	Nos.		
c.2	Providing & fixing Computer Plug Poi nts with 4 Nos. 16 Amp sockets. & 4 Nos. 16 AMP Switch complete with all necessary accessories.	1	No.		
c.3	Supply, Laying of Circuit line2x2.5mmsq +1x 1mmsq VC insulated copper wire form LDB to 6/16A or 6Amps Plug point. Also note that 03 Nos 06 amps Plug to be connected from one circuit line	45	R.ft.		
d.	UPS WIRING				
d.1	Supply fixing & connection of UPS circuit line with 2x2.5+1x1.5mmsq through pvc conduite 20mmdia 16 SWG wall thickness, with ISI mark, to lay from UPS MCB DB to plug point board. Two nos separate circuit to be	45	R.ft.		
d.2	Providing & fixing Raw Power Point includes 2x6/16, 6pin socket with 2nos.16A switch to provide behind ATM at 12" ht. from FFL.to be connected from UPS power.	3	Nos.		
<u> </u>					
e.	A/C. electrification :-				
e.1	Supply laying & connection of A/C. line for 1.0 TR A/C. window / split with 2x4 + 1x2.5 mmsq through 16 SWG pvc conduite with ISI Mark.	20	R.ft.		
e.2	Supply, fixing of A/C. 11-18 Amps stator complete with 20 amps socket in modular type box for split / window unit at 4.5 Ft from floor.	1	unit		

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)	
f.	ELECTRICAL FIXTURES :					
& e the	Item includes Providing, assembling, fixing, testing & commissioning following fixtures including all accessories, lamps & extension chords as maybe necessary complete.All CFL / Fluroscent fixtures (except down lighters) to be hung from the RCC ceiling by 20 KG grade adjustable GI chain & in NON False ceiling area they are to be hung by appropriate down rods.Work to be done as per drawing and instruction of the architect.(Including material, labour					
f.1	600mm X 600mm 2 x 36 wt LED light.	2	Nos.			
f.2	Supply & Fixing of 4 ft Long light Fittings T-5.	1	Nos.			
g.	Glow Sign board wiring :-					
g.1	Out door type Glow Sign board wiring :-Supply, laying of main line with 2x2.5 +1x1.5 mmsq through pvc conduite from main panel to glow sign	20	R.ft.			
g.2	Supply installation of 16 amps DP mcb at main entrance Glow sign board complete with timer & contractor (2NO + 2NC). 24 Hrs in orginal	1	Set			
h.	EARTHING STATION :					
cor Earl	Earthing : Supply, Erection, Testing & Commissioning of 'Ashlok' Pipe earth station and Chemical compound bag, complete with civil works, etc. as per specs in accordance with latest IS-3043. Earthing conductors : Supply & laying of equipment earthing using following sizes of conductors/tapes including all accessories to erect/lay the conductor & as per specifications.					
h.1	50 mm dia 3 mtr long pipe electrode earth station	1	No.			
h.2	25 x 3 mm Copper flat	25	R.ft.			
h.3	8 SWG Copper bare wire	25	R.ft.			
	TOTAL ELECTRICAL WORKS					
IN V	VORDS :					
1 2 3	2 Any type of A.C. and CCTV Camera3 Glow sign board.					
4	Excess Card Pillar.					

B.O.Q. FOR UCO BANK RAGHUNATHGANJ BRANCH, MURSHIDABAD

ARCHI SPACE CONSULTANT

<u>SUMMARY</u>

SL. NO.	DESCRIPTION	AMOUNT (Rs.)
1	ELECTRICAL WORKS OF BANKING AREA	
2	ELECTRICAL WORKS OF ATM	
	TOTAL (1+2)	
	Note: Cost including all material, labour and Transport cho work to be completed as per design, specification c	•

UCO BANK - RAGHUNATHGANJ BRANCH, MURSHIDABAD LIST OF APPROVED MATERIALS FOR ELECTRICAL WORK SI.No Items Approved make 1 MS pipe ISI mark. 16 Swg BEC / NIC MS fittings. BEC / NIC 2 Wire PVC insulated copper flexiable wire. Finolex/Havells/Gerard 3 4 North west / Havells A.C. stator. 5 Switch, socket modular plate. Crabtree(Sapphire)/MDS/Anchore AVE 6 Armoured cable. Nicco/Glostar/KDK/Havells. 7 Crabtree/MDS Telephone Socket RJ -11. 8 MCB, DB. MDS/Havells/L&T Hagger. 9 Telephone cable (0.51mmsq). Netco/Delton. Wipro/Philips/Crompton 10 Light fittings. 11 Lugs. Dowells. 12 Terminals Connector. **ESSEN** 13 Exhust fan. GEC/ EPC. 14 Ceiling Fan/wall mounted fan. Orient / Crompton / Havells SFU/SPN/TPN S.M. housing /Open 15 Havells/ L&T/ Semeins. execution fronthandle. 16 Telephone connector. KORN type. 17 Volt Meter / Amps Meter. 96x96 mm. AE / L&T. Current transformer. Kuppa / L&T. 18 19 Selector switch. Kaycee. 20 Sliding fuse / DZ fuse. Bharat Lender/ BCH. Steel grip/ Anchore. 21 PVC tape. 22 Join Box. 6"x4" MS box Heavey type. Joiti make. Bearer Call Bell. 23 Max / Homa. 24 Cable Gland Brass make. Arun (heavey type). 25 Speaker. Philips / Bosh. 26 LED incator. 20 dia. (Bright type). Mikadov / L&T/ MDS. 27 CD palayer. Philips / Sony. 28 Amplifier Philips / Sony. 29 Speaker wire. Finolex. PL /TL lamp. Philips. 30 PVC flexiable Pipe. 31 Hunuman. 32 Smoke / heat Detector. Appolo / Dats. 33 Manual call point. Minimax/Dats. 34 Security Alam Hooter. Philips/Dats. 35 PVC Regid pipe. MMS. Precession / AKG / Pesto As per sample approved by 36 All other items not covered above

ARCHI SPACE CONSULTANT

INVITATION TO TENDER

INSTRUCTION TO TENDERERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

DATA CABLING WORKS

AT

UCO BANK & ATM – RAGHUNATHGANJ BRANCH, MURSHIDABAD

NAME OF THE CONTRACTOR:

.....

ARCHITECT

ARCHI SPACE CONSULTANT 45B, BAGHJATIN PLACE 'AMELIA APPT.' – GR.FLOOR KOLKATA – 700086 CONTACT - 9830006396, 033-2425-0125

UCO BANK, ZONAL OFFICE, SURI NEAR CIRCUIT HOUSE, DIST-BIRBHUM (W.B.) – 731 101

ARCHI SPACE CONSULTANT

CONTENTS

SL NO	SECTION NO	DESCRIPTION
1	I	Tender Notice
2	II	General rules and instructions for The guidance of
3	III	Form of tender
4	IV	Articles of agreement
5	v	General conditions of contract With appendices.
6	VI	Special conditions
7	VII	Approved make of materials with bill of quantities for above mentioned works.
8	VIII	Summary

ARCHI SPACE CONSULTANT

SECTION - 1

TENDER NOTICE

Sealed item rate tenders under two bid systems are invited on behalf of:

The Deputy Zonal Head

UCO Bank, Zonal Office, Suri

Near Circuit House, Dist-Birbhum (W.B.) – 731 101

For the following work;

a)	Name of the Work	:	DATA CABLING works of Existing UCO Bank & ATM AT RAGHUNATHGANJ BRANCH, MURSHIDABAD
b)	Location of Work	:	VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.SRAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,
c)	Time of Completion	:	: 15 days (Fifteen days)
d)	Earnest Money	•	Rs 20,000.00/ (Rupees Twenty Thousand only) to be deposited In the form of Bank Draft / Pay order drawn in favour of UCO BANK payable at SURI. [Without Earnest Money in proper form Tender will be rejected]
e)	Cost of Tender document	:	Rs .750 /-(Rupees Seven Hundred Fifty only) in cash which is not refundable.
f)	Availability of Tender Documents	:	UCO Bank, Zonal Office Suri, Near Circuit House, Dist-Birbhum (W.B.) – 731 101 and on payment in cash during working hours from 10 am up to 5 pm from 24-11-2017 to 08-12-2017 (Except Sunday & Bank Holidays)
g)	Submission of tenders to	:	UCO Bank, Zonal Office Suri, Near Circuit House, Dist-Birbhum (W.B.) – 731 101 and Within 05.00 pm on 08-12-2017
h)	Opening of Tender	:	At Suri Zonal Office 12:30 pm. On 09-12-2017at the UCO Bank, Zonal Office, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

i)	Mode of submission of Tender	:	 The tender shall be submitted in accordance to the procedure detailed herein. Specified documents shall be sealed in envelope of appropriate size, each of which shall be sealed. i) Envelope marked No.1: Envelope marked no 1 shall contain earnest money deposit, pre- qualification forms, conditions of contract and technical specifications with covering letter furnished in the specified form. ii) Envelope marked No.2: Envelope marked no.2 shall contain the price bid and approved make of materials iii) no 3: Envelope marked no1&2 shall be put in a large envelope of adequate size marked no 3 which shall be properly sealed. This envelope, which shall be endorsed on the outside face. "Tender for DATA CABLING works for UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD 		
j)	Clarification, if any to be Obtained from:	Obtained from : ARCHI SPACE CONSULTANT 45B, BAGHJATIN PLACE 'AMELIA APPT.' – GR.FLOOR KOLKATA-86 Contact : 9830006396, 033-2425-0125			
K)	Defect Liability Period:	:	: 12 months from the date of virtual completion of work.		
1)	Validity of tenders: : Three calendar months from the date of submission of tender.				
m)	Sales Tax, Work Contract Tax or any other tax on materials or on finished work in respect of this contract whether in vogue or likely to be imposed in future, shall be payable by the Contractor and the Employer will not entertain any claim whatsoever in this respect at any time. Rates should include all these taxes Etc.				
n)	All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected. Conditional tenders will be summarily rejected.				
0)	Delays in submission of any part arising out of the postal or any other irregularities at any stage will not be considered. The Bank will not be responsible for damage in transit incase of postal delivery/ courier service delivery.				
p)	The employer does not bind it to accept the lowest tender and reserves to itself the right to reject any or all the tenders received without assigning any reason/s thereof. The notification of award of contract will be made to the successful tendered in writing by the Bank.				

Yours faithfully

For and behalf of UCO BANK . The Deputy Zonal Head UCO Bank, Zonal Office, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

ARCHI SPACE CONSULTANT

SECTION - II

GENERAL RULES AND INSTRUCTIONS FOR THE GUIDANCE OF TENDERERS.

Tenders are invited on behalf of **UCO BANK, SURI ZONAL OFFICE**, for DATA CABLING works at **UCO Bank & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD.** Contract document consisting of the plans, specifications, bill of quantities and drawings of various classes of work to be performed and set of conditions of contract to be complied with can be purchased from the office of UCO Bank, Zonal Office, Suri, Near Circuit House, Dist Birbhum, (W.B.) – **731 101** on stipulated dates between the hrs.10.30 to 6.00 except Sundays and other bank holidays.

- It is proposed that the intending tenderers may contact at the office of the Architects of ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." – Gr. Floor, Kolkata - 700086. The site of the work is available. The intending tenderer shall visit the site and make himself thoroughly acquainted with the local site condition, nature and requirements of the work, facilities of the work, facilities of transport condition, effective labour and materials, access and storage for materials and removal of rubbish etc.
- 2. As the entire work is to be completed in all respects within the stipulated period of **15 days** and to achieve the target date of entire completion if be required /essential, the work for day and night shifts have to be carried out by the tenderer/contractor, for that at no extra cost, charges shall be paid to the contractor by the employer. While quoting rates, in addition to above, whether mentioned or not the rate shall always include the charges for day to day removal of debris/spoils from site in conformity with the local Municipal rules. Bank's normal work shall not be jeopardized in any way for undertaking the work. Contractor shall include in his quoted rate for supplying the plastic sheets/tarpaulin to cover Banks materials as protection against getting damaged either due to dust or water while executing the work. Tenders in only printed forms issued by the consultants should be placed in sealed covers addressed to. The tenderers should quote in figures as well as in words the rates, and amount. The language for filling tender documents shall be in English. The amount for each item should be marked out and requisite total given. The initials of the tenderers with the seal of the firm shall attest all corrections. In case any discrepancy /difference is found on checking between rates quoted by the contractor in words and figures or in the amount worked out by him, the following procedure shall be followed:

3.

- A. When there is a difference between the rates in figures and in words, the rate, which corresponds to, the amounts worked out by the contractor, shall be taken as correct.
- B. When the contractor does not work out the amount of any item or it does not correspond with the rate written either in figures or in words, then the rate quoted by the contractors in words shall be taken as correct.
- C. When the rate quoted by the contractor in figures and in words tallies but the amount is not worked out correctly rate quoted by the contractor shall be taken as correct and not the amount
- D. Amendments as mentioned above shall be based on the tender marked original only.

ARCHI SPACE CONSULTANT

- 4. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only. In such away that interpolation is not possible. Amount should be written in figures. In case of figures the words "RS". Should be written before the figures of rupees and words paise after the decimal figures, e.g. Rs 2.15 and in case of words, the word "Rupees" should precede and the word "Paise" should be written at the end, unless the rate is in whole rupees and followed by the words "only", it should invariably be up to two decimal places. While quoting the rate in schedule of quantities, the word "only" should be written closely following the amount and it should not be written in the next line.
- 5. The acceptance of a tender will rest with UCO Bank, Zonal Office, Suri, Near Circuit House, Dist Birbhum (W.B.) 731 101 which does not bind itself to accept the lowest tender and reserves to itself the authority to reject any or all the tenders received without assignment of any reason. All tenders in which any of the prescribed conditions are not fulfilled or incomplete in any respect are liable to be rejected. The bank reserves the right to accept the tender in full or in part and the tenderer shall have no claim for revision of rates or other conditions if his tender is accepted in parts.
- **6.** Canvassing in connection with tenders is strictly prohibited and tenders submitted by the contractors who resort to canvassing will be liable to rejection.
- **7.** An item rate tender containing percentage below /above will be summarily rejected. However, when a tenderer voluntarily offers a rebate for payment within a stipulated period, this may be considered.
- 8. On acceptance of the tender, the name of the accredited representative(s) of the Contractor who would be responsible for taking instructions from the Employer Consultant shall be communicated to the Employer / Consultant.
- **9.** Sales Tax, Work Contract Tax or any other tax on materials or on finished work in respect of this contract whether in vogue or likely to be imposed in future, shall be payable by the Contractor and the Employer will not entertain any claim whatsoever in this respect at any time. Rates should include all these taxes --------- Etc.
- 10. No employee of the Employer is allowed to work as a Contractor for a period of two years of his retirement from Employer services, without the previous permission of the Employer. This contract is liable to be canceled if either the Contractor or any of his employees is found at any time to be such a person who had not obtained the permission of the Employer /Consultant as aforesaid before submission of the tender or engagement in the Contractor's service.
- 11. The tender for work shall remain open for acceptance for a period of 3 months from the date of opening tenders. If any tenderer withdraws his tender before the said period, then the employer shall be at liberty to forfeit the earnest money paid along with the tender.

ARCHI SPACE CONSULTANT

- 12. The tender for the work shall not be witnessed by a contractor or contractors who himself /themselves has / have tendered or who May and had/have tendered for the same work. Failure to observe this condition would render tenders of the contractors tendering as well as witnessing the tender liable to summary rejection.
- 13. It will be obligatory on the part of the tenderer to tender and sign the tender in all pages documents.
- **14.** The Earnest money deposit of the contractor whose tender is accepted shall be forfeited in full in case he does not start the work by the stipulated date mentioned in the letter of award.
- **15.** The Earnest money deposit of unsuccessful bidders will be refunded to them WITHOUT ANY INTEREST within 3 weeks from the date of award of work to the successful bidder.
- **16.** A certificate of completion shall accompany the final bill from the consultant. Payment of final bill shall be made after deduction of retention money as specified which sum will be refunded in the manner as stated conditions .In acceptance of payments of the final bill by the contractor would indicate that he will have no further claim in respect of the work executed.

17. CLEARING SITE ON COMPLETION

On completion of the work the contractor shall clear away and remove from the site all constructional plant, surplus materials, rubbish and temporary work of every kind and leave the whole of the site and the work clean and in workmanlike conditions to the satisfaction of the employer /consultant.

18. TERMS OF PAYMENT

- a) 85% can be claimed in phases in the form of two (2) running bills of the value of work
- b) 10% to be released after entire work is completed and handed over to the satisfaction and certification of the consultant.
- c) 5% to be released after the defect liability period of 12 months, without any interest.

19. IDLE LABOUR

Whatever the reasons may be no claim for idle labour; additional establishment cost of hire and labour charges of tools and plants would be entertained under any circumstances.

20. LIQUIDATED DAMAGE

The delivery and installation should be adhered to as stipulated time, failing which; liquidated damages @ 0.5% per week or part thereof subject to maximum of 10 % of the total order value shall be levied.

ARCHI SPACE CONSULTANT

21. TERMINATION OF CONTRACT BY EMPLOYER

If the contractor being a company go into liquidation whether voluntary or compulsory or being a firm shall be dissolved or being an individual shall be adjudicated insolvent or shall make an assignment or a composition for the benefit of the greater part, in number of amount of his creditors or shall enter into a deed or arrangement with his creditors, or if the Official Assignee in insolvency, or the Receiver of the Contractor in insolvency, shall repudiate the contract or, if a receiver of the contractor's firm appointed by the court shall be unable, within fourteen days after notice to him requiring him to do so, to show to the reasonable satisfaction of the Employer that he is able to carry out and fulfill the contract, and if so required by the Employer to give reasonable security there for, or if the Contractor shall suffer execution to be issued, or shall suffer any payment under this contract to be attached by or on behalf of and of the creditors of the Contractor, or shall assign, charge or encumber this contract or any payments due or which may become due to the contractor, there under or shall neglect or fail to observe and perform all or any of the acts matters of things by this contract, to be observed and performed by the contractor within three clear days after the notice shall have been given to the contractor observe or perform the same or shall use improper materials or workmanship in carrying on the work or shall in the opinion of the employer not exercise such due diligence and make such due progress as would enable the work to be completed within due time agreed upon and shall fail to proceed to the satisfaction of the employer after three clear days notice requiring the contractor so to do shall have been given to the contractor as hereinafter mentioned or shall abandon the contract, then and in any of the said cases, the employer may not withstanding previous waiver determine the contract by the notice in writing to the effect as hereinafter mentioned but without thereby affecting the powers of the employer of the obligations and liabilities of the contractor the whole of which shall continue in force as fully as if the contract had not been so determined as if the work subsequently executed had been executed by or on behalf of the contractor.

IF THE CONTRACT HAS BEEN TERMINATED THE EMPLOYER RESERVES THE RIGHT TO RECTIFY THE ITEMS AND COMPLETE THE JOB IN THE RISK AND COST OF THE TERMINATED VENDOR BY ANY OTHER APPROVED VENDOR.

ARCHI SPACE CONSULTANT

SECTION -III

FORM OF TENDER

То

The Deputy Zonal Head UCO Bank, Zonal Office, Suri Near Circuit House, Dist - Birbhum (W.B.) – 731 101

Sir,

Re: DATA CABLING work for the UCO BANK & ATM – RAGHUNATHGANJ BRANCH, MURSHIDABAD

- I/we refer to the tender notice issued by your consultants ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." – Gr. Floor, Kolkata – 700086 on your behalf for DATA CABLING work in connection with the above.
- 2. I/We do hereby offer to perform, provide, execute, complete and maintain the work in conformity with drawings, conditions of contract specifications, bill of quantities for the sum of RS...... at the respective rates quoted in the schedule of quantities.
- **3.** I/We have satisfied myself/ourselves as to the site conditions, examined the drawings and all aspects of the site tender conditions. Subject to above, I/We do hereby agree, should this tender be accepted in whole or in part, to:
 - A: Abide by and fulfill all the terms and provisions of the said conditions annexed hereto
 - B: Complete the work within **15 days**, as stipulated in two or three shifts if considered necessary by the consultants at no extra cost to the Employer.
- 4. I/We have deposited earnest money of RS. 20000/- In the form of Crossed Demand draft / pay order /Banker's Cheque which, I/We note, will not bear any interest and is subject to forfeiture solely at Bank's discretion:
 - i. If the work is not commenced by me/us within 7(seven) days from the date of issue of formal work order

Or

- ii. If the offer is withdrawn within the validity period of acceptance.
- iii. If the contract is not executed within 90 days from award of contract.
- 5. I/We understand that you are not bound to accept the lowest or any tender you receive.

ARCHI SPACE CONSULTANT

- 6. The acceptance of this tender shall constitute a binding of any contract and any failure as mentioned in item 4. Above shall constitute a breach of contract by us and the tender accepting authority shall be entitled to have the work executed at our risk and to claim extra cost \ expenditure incurred by them from us.
- 7. Our Bankers

i)		
ii)		
iii)		

8. Name of partners / directors of our firm :

I.

II.

III.

IV.

Yours Faithfully
Signature
Name
Designation

ARCHI SPACE CONSULTANT

SECTION –IV ARTICLES OF AGREEMENT

Articles of agreement made the Day of Between the UCO Bank, Zonal Office, Suri, Near Circuit House, Dist -Birbhum (W.B.) - 731 101 (Hereinafter called the employer) which expression should include its successors and assignee of the one part and include its successor and assignee where as the employer is desirous of executing the DATA CABLING works at UCO Bank & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD and has caused drawings and specifications describing the work to be prepared by ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." - Gr. Floor, Kolkata - 700086 (hereinafter called the consultants) and whereas the said drawings the Technical specifications and the schedule of items and quantities have been signed by and on behalf of the parties hereto. And whereas the contractor has agreed to execute upon and subject to the conditions set forth herein and schedule of items and quantities, General conditions of contract, special conditions including other conditions etc. technical specifications and all correspondences exchanged by or between the parties from the date of tender notice decision of negotiations meetings, if any, till the award of work, both letters inclusive, (all of which are collectively hereinafter referred to as the said conditions) the work shown upon the drawings and or described in the said specification and included in the schedule of items and quantities at the respective rates therein set forth amounting to the sum as therein arrived at or such other sum as shall become payable there under (Hereinafter referred to as the said contract amount)

NOW IT IS HEREBY AGREED AS FOLLOWS:

- 1. In consideration of the said contract amount to be paid at the times in the manner set forth in the said conditions, the contractor shall upon and subject to the said conditions execute and complete the work shown upon the drawings and described in the said specifications and the schedule of items and quantities.
- 2. The employer shall pay the contractor the said contract amount or such other sum as shall become payable, at the times and in the manner specified in the said conditions.
- 3. The consultant in the said conditions shall mean the said ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." Gr. Floor, Kolkata 700086 or in the event of their ceasing to be the consultant for the purpose if this contract for whatever reason such other person or persons as shall be nominated for that purpose by the Employer, provided always that the person subsequently appointed to be consultant under this contract shall be entitled to disregard or overrule any previous decision or approval or direction given or expressed in writing by the consultant for the time being.

ARCHI SPACE CONSULTANT

- 4. The said conditions and appendices thereto shall be read and considered as forming part of this agreement and the parties here to shall respectively abide by, submit themselves to the said conditions and perform the agreements on their part respectively in the said conditions contained.
- 5. The plan agreement and documents mentioned herein shall form the basis of this contract.
- 6. This contract is neither a fixed lump sum contract not a piece work in respect of **DATA CABLING** works at **UCO Bank & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD** as per the scope described and to be paid for according to actual measured quantities at the rates contained in the schedule of rates probable quantities or as provided in the said conditions.
- 7. The employer reserves to itself the right of altering the drawings and nature of the work by adding to or omitting any items of work or having portions of the same carried out without prejudice to this contract.
- 8. Time shall be considered as the essence of this contract and the contractor hereby agrees to commence the work on the day on which he is instructed to take possession of the site, or from the 7th day after the date of issue of formal work order as provided for in the said conditions whichever is later and to complete the entire work within **15 days** subject nevertheless to the provisions for extension of time.
- 9. All payment by the Employer under this contract will be made only at UCO Bank, Zonal Office, Suri.
- 10. Any dispute arising under this agreement shall be referred to arbitration in accordance with the stipulation laid down in the general conditions of contract.
- 11. That the several parts of this contract have been read by the contractor and fully understood by the contractor.
- 12. This agreement can be terminated by either client on giving **3 months** notice normally however, in exigent circumstance; the services of the contractor can be terminated by giving notice of lesser period.

ARCHI SPACE CONSULTANT

IN WITNESS	WHEREOF the p	parties hereto	have hereunto	set their h	nands the da	y and yea	ır first above
written.							

	Signed, and delivered by	v By	y the hands of MR
--	--------------------------	------	-------------------

(name and designation) it's-----and constituted attorney in the presence of

1. ----- 2. -----

Address-	Address-

Witness

Signed and delivered by the hands of MR.	Partner of
in the presence of	
1	2
Address-	Address

ARCHI SPACE CONSULTANT

SECTION –V GENERAL CONDITIONS OF CONTRACT

Except where provided for in the description of the individual items in the schedule of quantities and in the specifications and conditions laid down hereinafter and in the drawings, the work shall be carried out as per standard specifications and under the direction of the employer /consultant.

1. INTERPRETATION:

In construing these conditions, the specifications the schedule of quantities tender and Agreement, the following words shall have the meaning herein assigned to them except where the subject or context otherwise requires.

2. EMPLOYER:

The term employer shall denote UCO Bank, Zonal Office, Suri, Near Circuit House, Dist –Birbhum (W.B.) – 731 101 or any of its employees representative authorized on their behalf.

3. CONSULTANT:

The term consultant shall mean ARCHI SPACE CONSULTANT, 45B, Baghjatin Place, 'Amelia Appt." – Gr. Floor, Kolkata – 700086 or in the event of their ceasing to be consultant for the purpose of this contract such other persons /as the employer shall nominate for the purpose.

4. CONTRACTOR:

The term contractor shall mean the individual or firm or company whether incorporated or not, undertaking the work and shall include legal representative of such individual of such firm or company or successors of such firm or company as the case may be m and permitted assigns of such individual of firm or company.

5. SITE:

The site shall mean the site where the work is to be executed at UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD.

6. DRAWINGS:

The work is to be carried out in accordance with drawings, specification, the schedule of quantities and any further drawings, which may be supplied, or any other instructions, which may be given by the employer consultant during the execution of the work. All drawings relating to work given to the contractor together with a copy of specification and schedule of quantities are to be kept at site and the employer /consultant shall be given access to such drawings or schedule of quantities wherever necessary.

In case any detailed drawings are necessary contractor shall prepare such detailed drawings and or dimensions sketches there for and have it confirmed by the employer consultant prior to taking up such work. The contractor shall ask in writing for all clarifications on matters occurring anywhere in drawings, specifications and schedule of quantities or to additional instructions at least 20 days ahead from the time when it is required for implementation so that the employer /consultant may be able to give decision thereon. The work shall mean the work to be executed or done under this contract.

1. SCOPE:

The work consists of DATA CABLING works for UCO BANK & ATM, RAGHUNATHGANJ

BRANCH, MURSHIDABAD. In accordance with the drawings, specifications and schedule of items and quantities. It includes furnishing all material, labour, tools and equipment and management necessary for and incidental to the construction and completion of the work. All work during its progress and upon completion, shall confirm to the lines, elevations and grades as shown on the drawings furnished by the employer /consultant and to furnish by the employer/consultant. Should any detail essential for efficient completion of the work be omitted from the drawings and specification it shall be the responsibility of the contractor to inform the employer /consultants concurrence, so that upon completion of the proposed work the same will be acceptable and ready for use.

Employer/consultant may in their absolute discretion issue further drawings and or written instructions, details, directions and explanations which are here after collectively referred to as the employer /consultants instructions in regard to:

A: The variation on modification of the design, quality or quantity of work or the addition or omission or substitution of any work:

B: Any discrepancy in the drawings or between the schedule of quantities and or drawings and or specification.

C: The removal from the site of any defective material brought thereon by the contractor and the substitution of any other material thereof.

D: The demolition removal and /or rejection of any work executed by the contractor /s

E: The dismissal from the work of any persons employed thereupon.

F: The opening up for inspection of any work covered up.

G: The rectification and making good of any defects under clauses hereinafter mentioned and those arising during the maintenance period (retention period)

The contractor shall forthwith comply with and duly execute any work comprised in such employer/consultants instructions provided always that verbal instruction direction and explanations given to the contractor or his representative upon the work by the employer/consultant shall if involving a variation be confirmed in writing to the contractor within seven days. No work for which rates are not specifically mentioned in the priced Schedule of quantities shall be taken up without written permission of the employer/consultant. The employer in consultation with the consultant shall fix rates of items not mentioned in the priced schedule of quantities.

ARCHI SPACE CONSULTANT

2. DETAILED DRAWINGS AND INSTRUCTIONS

The employer through its consultant shall furnish with reasonable promptness additional instructions by means of drawings or otherwise necessary for the proper execution of the work. All such drawings and instructions shall be consistent with the contract documents true developments thereof and reasonably inferable there from.

The work shall be executed in conformity therewith and the contractor shall not work without proper drawings and instructions.

Immediately after receipt of the work order of the contract the contractor shall prepare a program schedule and submit the same to the employer through the consultant for approval which shall indicate the dates for the starting and completion of the various activities at the stages of construction.

3. COPIES FURNISHED

The contractor on the signing hereof shall be furnished by the employer through its consultant free of charge with a copy of the priced schedule of quantities rates, two copies of each of the said drawings and one copy of specifications and two copies of all further drawings issued during the progress of the work. Any further copies of such drawings required by the contractor shall be supplied on payment of the charges thereof by the contractor.

4. OWNERSHIP OF DRAWINGS

All drawing specification and copies thereof furnished by the employer through its consultants are the property of the employer. They are not to be used on other work, and with the execution of the signed contract set are to be returned to the employer on request at the completion of the work.

5. FAILURE BY CONTRACTORS TO COMPLY WITH EMPLOYERS / CONSULTANTS INSTRUCTION

If the contractor after receipt of written notice from the employer and or the consultant requiring compliance within ten days fails to comply with such further drawings and or employer /consultant instructions, the employer through the consultant or other persons, may employ other persons to execute any such work whatsoever that may be necessary to give effect thereto and pay all cost incurred in connection therewith and same shall be recoverable from the contractor by the employer on the certificate of the consultant as a debt or shall have right to deduct same form any money due or to become due to the contractor.

6. TENDERER SHALL VISIT THE SITE

Intending tendered shall visit the site and make himself thoroughly acquainted with the local site condition, nature and requirements of the work, facilities of transport condition, effective labor and materials, access and storage for materials and removal of rubbish. The tenderer shall provide in their tender for cost carriage, freight and other charges including all taxes etc. as also for any special difficulties and including police restriction for transport etc for proper execution of work as indicated in the drawings. The successful tenderer will not be entitled to any claim of compensation for difficulties faced or losses incurred on account of any site condition which existed before the commencement of the work or which in the opinion of the employer /consultant might be deemed to have reasonably been inferred to be so existing before commencement of work.

7. TENDERS

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initial/signature will indicate the acceptance of the tender papers by the tenderer.

The schedule of quantities shall be filled in as follows:

- 1. The Rate column to be legibly filled in ink in both English figures and English words.
- 2. Amount column to be filled in for each item and the amount for each subhead as detailed in the schedule of quantities.
- 3. All corrections overwriting are to be initialed with the seal of the firm.
- 4. In case of any errors/omissions in the quoted rates, the rates given in the tender.

No modification writing or corrections can be made in the tender papers by tenderer.

The employer reserves the right to reject the lowest or any tender and also to discharge any or all of the tenders for each section or to split up each and every item should be correct, workable and self-supporting. If called upon by the employer consultant detailed analysis of any or all the rates shall be submitted .The employer/consultant shall not be bound to recognize the contractor analysis.

The work will be paid for as measured work on the basis of actual work done and not as lump sum contract.

All items of work described in the schedule of quantities are to be deemed and paid as complete work in all respects and details including preparatory and finishing work involved, directly, related to and reasonably detectable from the drawings specification and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lum-sum charges in the tender in respect of any item or work, the payment of such time of work will be made for the actual work done the basis of lum-sum charges as will be assessed to be payable by the employer consultant.

The employer has power to add to omit from any work as shown in drawings or described in specifications or included in schedule of quantities and intimate the same in writing but no addition, omission or variation shall be made by the contractor without authorization from the employer no variation shall vitiate the contract.

8. AGREEMENT

The successful contractor shall sign the agreement as per draft agreement within 15 days from the date of issue of formal work order and he shall pay for all stamps and legal expenses, incidental thereto. However the written acceptance of the tender by the employer /consultant on behalf of employer will constitute a binding contract between the employer and the person so tendering whether such formal agreement is or is not subsequently executed.

9. ROYALTIES & PATENTS

The contractor shall pay all royalties and license fees. He shall defend all suits or claims for infringement of any patent rights and shall save the employer harmless from loss on account thereof.

10. PERMITS AND LICENCES

Permits and licenses for release of materials which are under government control will be arranged by the contractor .The employer will render necessary assistance, sign any forms or applications that may be necessary.

11. GOVERNMENT AND LOCAL RULES

The contractor shall confirm to the provisions of all local to the provisions of all local bye-laws and acts relating to the work and to the regulations etc. of the government and local authorities and of any company with whose system the structure is proposed to be connected. The contractor shall give all notices required by the said act, rules, regulations and bye laws etc and pay all fees payable to such authority for execution of the work involved .The cost, if any shall be deemed to have been included in his quoted rates, taking into account all liabilities for licenses, fees for footpath encroachment and restorations etc. and shall indemnify the employer against such liabilities and shall defend all actions arising from such claims or liabilities.

12. TAXES AND DUTIES

The tenderers must include in their tender prices quoted for all duties, royalties, excise, sales tax, work contract tax or any other taxes or local charges if applicable. No extra claim on this account will in any case be entertained.

13. QUANTITY OF WORK TO BE EXECUTED

The quantities shown in the schedule of quantities are intended to cover the entire new structure indicated in the drawings but the employer reserves the right to execute only a part or the whole or any excess thereof without assigning any reason therefore. If at any after the commencement of the work, the employer consultant shall for any reason whatsoever not require the whole work thereof as specified in the tender to be carried out the consultant employer shall give notice in writing of the fact to the contractor who shall have no claim to any payment for compensation whatsoever on account of any profit or advantage with which he might have derived from the execution of the work in full, but which he did not derive in consequence of the full amount of the work not having been carried out, neither shall he have any claim for compensation by reason of any alterations having been made in the original specification ,drawings ,designs and instructions which shall involve any curtailment of the work as originally contemplated.

14. EARNEST MONEY /SECURITY DEPOSIT & RETENTION MONEY

The tenderer will have to deposit an amount of **Rs 20000.00/-** in the form of crossed demand Bank Draft/Pay Order/Banker's cheque drawn in favor of UCO payable at Suri from any nationalized Bank at the time of submission of tender as an earnest money. The employer is not liable to pay any interest on the earnest money. The earnest, money of the unsuccessful tenderers will be refunded without any interest 21 days after the decision to award the work is taken or after the expiry of the validity period of the tender, whichever is earlier.

Retention money will be deducted from interim bills @ 5 % of the accepted value of the tender. This retention money shall be refunded to the successful contractor without any interest 14 days after successful completion of the defects liability period of 12 months provided the contractor has satisfactorily carried out all the work and attended to all defects in accordance with the condition of the contract. In case the contractor fails to do so appropriate amount shall be deducted by the Bank from retention money.

ARCHI SPACE CONSULTANT

15. CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein the shall immediately and in writing refer the same to the employer /consultant whose decision shall be final and binding. The contractor shall provide himself for ground and fresh water for carrying out the work at his own cost. The employer shall on no account be responsible for the expenses incurred by the contractor for hired ground of fresh water obtained from elsewhere. The rates quoted against individual items will be inclusive of everything necessary to Complete the said items of work within the contemplation of the contract, and beyond the unit price no extra payment will be allowed for incidental or contingent work, Labour and /or materials inclusive of all tax and duties whatsoever except for specific items, if any stipulated in the tender documents.

The contractor shall supply fix and maintain at his own cost for the execution of any work all tools tackles machinery's and equipment's and all the necessary centering, scaffolding, staging, planking, timbering, strutting, shoring, pumping, fencing, boarding, watching and lighting by night as well as by day required not only for the proper execution and protection of the public and safety of any adjacent roads, streets, walls houses buildings all other erections matters and things and the contractor shall take down and remove any or all such centering ,scaffolding, planking ,timbering etc shall be required or when so to do and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of the employer/consultant.

16. TIME OF COMPLETION, EXTENSION OF TIME AND PROGRESS CHART

A. TIME OF COMPLETION:

The entire work is to be completed in all respects within the stipulated period of **15** days, from the date of issue of formal work order. Time is the essence of the contract and shall be strictly adhered to by the contractor.

The work shall not be considered as complete until the employer consultant have certified in writing that this has been completed and the defects liability period shall commence from the date of such certificate.

B. PROGRAMME CHART TO BE PROVIDED

During the period of construction the contractor shall maintain proportionate progress on the basis of the program chart submitted by the contractor immediately before commencement of work and agreed to by the employer consultant.

17. CLEARING SITE AND SETTING OUT WORK

The site shown on the plan shall be cleared of all obstruction, loose stone and materials rubbish of all kinds.

ARCHI SPACE CONSULTANT

18. MATERIALS WORKMENSHIP, SAMPLES, TESTING OF MATERIALS

All the materials specified to be maintained and the contractor shall have to carry out tests on materials and workmanship in approved materials testing laboratories or as prescribed by the employer.

19. REMOVAL OF IMPROPER WORK

The employer consultant shall during the progress of the work have power to order in writing from time to time the removal from the work within such reasonable time to times as may be specified in the order of any materials which in the opinion of the employer consultant are not in accordance with specifications or instruction. In case the contractor refuses to comply with the order the employer consultant shall have the power to employ and pay other agencies to carry out the work and all expenses consequent thereon or incidental thereto as certified by the employer consultant shall be borne by the contractor or may be deducted from any money due to or that may become due to the contractor .No certificate, which may be given by the consultant, shall relieve the contractor from his liability in respect or unsound work or bad materials.

20. MEASUREMENT

The consultant shall from time to time intimate to the contractor that he requires the work to be measured, and the contractor shall forthwith attend or send a qualified agent to assist the consultant or the consultants representative/employers representatives in taking such measurements and calculations and to furnish all particulars or to give all assistance required by either of them.

21. ACTION WHERE NO SPECIFICATION

In the case of any class of work for which there is no such specification in technical specification, such work shall be carried out in accordance with the I.S. specification and in the event of there being no I.S. specification, then in such case the work shall carried out in all respect in accordance with the instructions and requirements of the consultant /employer.

22. CONTRACTOR NOT TO DEPOSIT MATERIALS IN A MANNER THAT MAY CAUSE INCONVENIENCE TO THE PUBLIC.

The contractor (s) shall not deposit materials on any site, which will seriously cause inconvenience to the public. The Consultant may require the contractor to remove any materials, which are considered by him to be a danger or inconvenience to the public or cause them to be removed at the contractor's cost.

23. PAYMENTS

- a) All bills shall be prepared by the Contractor in the form prescribed by the Employer/Consultant, format enclosed. In the bill it has to be shown deductions for all previous payments, retention money, etc.
 Advance / adhoc payment for work actually executed will not be normally made. However, adhoc payment may be made at the discretion of Consultant /Employer in case of exigency.
- b) The Consultant /Employer shall issue a certificate after due scrutiny of the Contractor's bill stating the amount due to the Contractor from the Employer and the contractor shall be entitled to payment thereof, by the Employer.

ARCHI SPACE CONSULTANT

- 24. The contractor shall work in close co ordination with other agencies to avoid rework/damage and ensure timely completion.
- 25. Any damage to the work before the building is handed over is to be replaced or made good at contractor expense to the entire satisfaction of the consultant.
- 26. The quantities indicated are subject to change .The payment of the bill will be made as per actual measurement at site and will be certified by the Consultant and cleared by the employer.
- 27. The tender shall sign each and every page of the tender documents including the drawings attached hereto.
- 28. The consultant shall have power to insist to the contractor to submit the sample /color/ test certificate from any Govt. Authorized agent of any materials to be used in the work, where the expenditure is to be borne by the contractor.
- 29. 5 % of the total value of work will be retained as retention money from Contractor's bills which shall be released without any interest after the defect liability period of six months provided the contractor has satisfactorily attended to all defects if any, in this period.
- 30. In case of any dispute the matter will be referred to the Asst. General Manager, Zonal Office, Suri for an arbitration, whose decision shall be final and binding on both parties.
- 31. For litigation if any arising thereof, the competent court at Bombay alone will have jurisdiction.

ARCHI SPACE CONSULTANT

SECTION VI SPECIAL TERMS AND CONDITIONS

1. Name of the work :	DATA CABLING works for UCO BANK & ATM, RAGHUNATHGANJ BRANCH, MURSHIDABAD.
2. Location:	VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.SRAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,
3. Scope of Work :	As in 1 & 2 above and as further detailed in Instruction to Tender
4. Date of Commencement :	Within 3(Three) days from issue of work order.
5. Defect liability period :	12 (Twelve) months from the date of completion Certificate Issued by the consultant/employee
6. Earnest Money :	Rs 20000.00 /-
7. Initial security deposit :	 a) the amount of initial security deposit shall be 2% of the accepted value of the tender including the earnest money deposit. b) The initial security deposit is to be paid by the Contractor to the bank within 14 days of Intimation to him of the acceptance of tender.
8. Limit of variation :	No extra /additional work should be carried out by the contractors without prior consent approval .Any sample to be made shall be At your cost for approval.
9. Validity of the tender :	3 (Three) months after opening the tender
10. Insurance :	Successful contractors shall have to take out statutory labour laws, workmen compensation Act, Insurance policy/Comprehensive Insurance policy for the duration of the work covering all aspects such as fire hazards, earthquake, third party risk etc. They should submit receipt of premium paid to the UCO BANK, Suri Zonal Office Prior to commencement of the work.

11. Completion time and Liquidated Damage :	The entire job will be completed within 15 days (Fifteen days) from the date of the work order. In the event of your failure to complete the work In all respects including site clearance and Reinstatement of damaged proportion within The stipulated time. Liquidated damage @ 0.50% per week of delay or part thereof shall be levied subject to a maximum of 5% of the total order value.
12. Return of EMD to unsuccessful Bidders :	The Earnest money deposit of unsuccessful bidders will be refunded to them WITHOUT ANY INTEREST within 21days from the date of award of work to the successful bidder.
13. Force Majeure:	Any delay in or failure of the performance of either part hereto shall not constitute Default hereunder or give rise to any Damage, if any, to the extent such delay Or failure of performance is caused by occurrences such as Acts of god or an Enemy, expropriation or confiscation of facilities by Government authorities, Acts of war, rebellion, sabotage or fires, Floods, explosions, riots or strikes. The contractor shall keep records of the Circumstances referred to above and bring These to the notice of the Engineer-in-Charge / site – In charge in writing Immediately on such occurrences. The Amount of time, if any, lost on any of These Counts shall not be counted for the contract Period. One decision of the owner arrived. At after consultation with the contractor, shall be final and binding. Such a determined period of time shall extended by the owner to enable the contractor to complete the job within such extended period of time. If the contractor is prevented or delayed from performing any of his obligations under This agreement by force majeure, the contractor shall owner the circumstance constituting the force majeure and the obligations, performance of which is thereby delayed or prevented, within seven days of the occurrence of the events.

ARCHI SPACE CONSULTANT

CERTIFICATE

1.	The Measurement on the basis of which the above entries for the running bill
	nowere made have been taken jointly on
	and are recorded at pages
	toof measurement book no

2. The work recorded in the above mentioned measurement has been done at the site satisfactorily as per tender drawings, conditions and specifications.

Signature of the contractor consultant		Signature of the
Signature of the Employer		
Date:	Date:	Date:
Place:	Place:	Place:
We hereby certify that an amount of (Rupees		
noDateds	ubject to verification of all other tials supplied to the contractor, i l payment including this should	previous payments, if any made to if any ,and income tax and any other not, however, exceed

SIGNATURE OF CONSULTANT

ARCHI SPACE CONSULTANT

PROFORMA FOR APPLICATION FOR EXTENSION OF THE TIME PERIOD

- 1. Name of the contractor:
- 2. Name of the work as given In the agreement:
- 3. Agreement No:
- 4. Estimated tender amount:
- 5. Date of commencement of work As per agreement:
- 6. Period for which extension of time Has been given previously:

Extension vide consultant's Employer's letter

No	Dated	Month	Days
A)			
B)			
2)			
C)			
()			

- 7. Period for which extension is applied Is applied for:
- Hindrances on account of which Extension is applied for with dates on Which hindrances occurred and the Period for which these are likely to last:

a)	Serial	No.
----	--------	-----

b) Nature of hindrance	:
c) Date of occurrence	:
d) Period for which it is likely To last	:
e) Period for which extension Required for this particular Hindrance	:
f) Net extension applied for	:
g) Remarks if any	:
9. Extension of time required For extra work	:
10. Extension of time required For extra work	:
11. Details of extra work and The Amount involved	:
12. Proportionate period of Extension of time on estimated Amount put to tender	
13. Total extension of time required for Submitted to the consultant / employ	

Date.....

Signature of the contractor DATE:

CONTRACTORS ARE REQUESTED TO VISIT THE SITE AND COLLECT ALL OTHER NECESSARY DETAIL DRAWINGS FROM THE CONSULTANTS OFFICE BEFORE QUOTING.

FOR ANY CONFUSION IN THE DRAWING AND SPECIFICATION PLEASE CLARIFY WITH THE CONSULTANT BEFORE THE TENDER OPEN.

NO EXTRA WILL BE PAID TO COMPLETE ONE SINGLE ITEM MENTIONED IN THE TENDER

B.O.Q. FOR DATA CABLING WORKS OF PROPOSED BANK & ATM AT RAGHUNATHGANJ BRANCH, MURSHIDABAD

OWNER : UCO BANK

ZONAL OFFICE -UCO Bank, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

BRANCH ADDRESS :

VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.S.-RAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,

CONSULTING ARCHITECT - ARCHI SPACE CONSULTANT

ADDRESS: 45B, "AMELIA APARTMENT", GROUND FLOOR,

BINNAGAR, NEAR BAGHAJATIN STATION,

KOLKATA - 700086

CONTACT - 9830006396, 033-2425-0125

DATE: 11.08.17

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)
1	9 u rack Digi Link / Lucent/ HCL co. make supply & installation type Cat 6 PDU - box 1 no., Fan set complete unit.	1	Unit		
2	Digi Link / Lucent/ HCL make Patch panel Unit Supply and Installation of Cat 6, 24 ports Gigabit 10/100/1000 Rack mountable Unmanged Switch	1	Unit		
3	Digi Link / Lucent/ HCL make Patch Cord Cat 6 face plate - 2 port including mounting box for each workstation.	7	Nos.		
4	Supply & Laying of Cat 6 cables 4 Core through pr-laid rigid PVC conduit from server to computer data socket including interconnection mending good, etc. as required (Digi Link / Lucent/ HCL make)	500	R.ft.		
5	Digi Link / Lucent/ HCL make Single Ported RJ 45 IO BOX	7	Nos.		
6	Installation, Transpotation & Misc. Charges	1	Job		
	TOTAL DATA CABLING WORKS				

B.O.Q. FOR INTERIOR FURNISHING WORKS OF PROPOSED BANK & ATM AT RAGHUNATHGANJ BRANCH, MURSHIDABAD

OWNER : UCO BANK

ZONAL OFFICE -UCO Bank, Suri Near Circuit House, Dist-Birbhum (W.B.) – 731 101

BRANCH ADDRESS :

VILL-JANGIPARA, SAHEBPUR BAZAR (1ST FLOOR), P.S.-RAGHUNATHGANJ, MURSHIDABAD, WEST BENGAL, PIN-742213,

CONSULTING ARCHITECT - ARCHI SPACE CONSULTANT

ADDRESS: 45B, "AMELIA APARTMENT", GROUND FLOOR,

BINNAGAR, NEAR BAGHAJATIN STATION,

KOLKATA - 700086

CONTACT - 9830006396, 033-2425-0125

DATE : 11.08.17

.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.
۹.	WOODEN PARTITIONS				
\. 1	Wooden Double Skin Solid Partition With Both Sides Laminate Finish	250	Sq.ft.		
	 Supply & Erecting Solid Partition as per drawing & conforming to the for Basic Framework: Well seasoned Malaysian Sall wood sections, treated 50 x 50 mm (minimum) at maximum 2 ft horizontal and vertical spacing shall be suitably anchored at floor level to ensure rigidity Skin Membrane: 6 mm BWR grade Ply wood on each face with 2 mm Finishing: 1.0 mm thk. laminate sheet of combination shades as per instace Skirting: The Partition will be finished with 4" wide Skirting finished with 1 laminate of approved make on both sides. Note: Quoted Rates shall include all necessary material, accessories and Telephone / Computer wiring conduits and switch boxes etc. (Material) 	d with tw g as per groves a struction .0 mm t .0 mm t nd also a s of wiri	vo coa site cc as per o n (as ap hick Bo allow p	ts of wood ondition. Ve drawing / ir oproved me ank's appro provisions fo	rtical membe nstruction. ake) on both ved colour or electrical /
	shall be separately paid for) The work to be completed as per instruction	on.			
. .2	Wooden Partly Glazed Partition	175	Sq.ft.		
	 Skirting: The Partition will be finished with 4" wide Skirting Finished with 1 m Colour. Glazing: 8 mm. thk. Clear float glass with pencil polish edges from 3'-0" to wenge. It should be fixed with teak wood beading (size - 30mm x 20mm) polished. Polishing will be the same colour as that lamination i. e. cedar to of decorative etching on on side of the glass. All complete. Note: Quoted Rates shall include all necessary material, accessories and Telephone / Computer wiring conduits and switch boxes etc. (Materials of be separately paid for). The erection of partition shall include for expansion rivets and other accessories, all complete. as per instruction. 	6'-6" fixe all arou inished. also allc of of wiri	ed with nd, fini The rat ow prov ng con	continuous shed with n e should be visions for el duits and sy	wall nut / nelamine including cos ectrical / witch boxes sh
				1	
	CASH PARTITION (Side and intermediate partitions)	120	Sq.ft.		
\. 3	Same as - Wooden Double Skin Partly Glazed Partition. Glazing : Strips of 12 mm. thk. clear float glass with pencil polish edges fro			d, finished v	

	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)
В.	GLASS DIVIDER	18	R.ft.		
	8mm. thk. 18" ht. clear float glass divider on table top for separation of each should be fixed on table (front side) & between two tableswith teak word around, finished with melamine polished. Polishing will be the same cold The erection of divider shall include for expansion bolts cleats, clamps be accessories. The rate should be including cost of decorative etching on or to be completed as per instruction of the Architect.	od bead our as the olts, nuts,	ing (size at lamin screws	e - 30mm x 2 nation i. e. c s, rivets and	20mm) all cedar finished. other
C.	WRITING DESK (5'-0" X 1'-6" X 1'-6")	10	Sq.ft.		
	Providing & fixing cheque writing desk made out of 19 mm BWR ply fram Laminate of approved make / colour 1.0 mm thk laminate. 12mm thick (level with polish at exposed sides. 12mm thick CLEAR Glass shall be fixed polishing at 4 sides and instructions of the Architect.	CLEAR G	lass sha	III be fixed o	at top & side
D.	DOOR				
	shape s/s handle (Kitch), dead lock, key hole cover, tower bolt, door clo door to be covered with necessary lipping with polish. The work should b				suges of the
	and approval of Architect. Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wo natural polish. The doors fitted with door closers shall be provided 3" x 11, natural polish for door frame work.	od / sal v /2" white	wood (s beech	seasoned) s	ication, design ection with
D.1	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wo natural polish. The doors fitted with door closers shall be provided 3" x 11,	od / sal v	wood (s	seasoned) s	ication, design ection with
	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wo natural polish. The doors fitted with door closers shall be provided 3" x 11, natural polish for door frame work. Wooden partition door with vision panel (with frame work) -	od / sal v /2" white	wood (s beech	seasoned) s	ication, design ection with
D.2	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wo natural polish. The doors fitted with door closers shall be provided 3" x 11, natural polish for door frame work. Wooden partition door with vision panel (with frame work) - (WPD-1)- 2'-8" x 6'-6"	od / sal v /2" white 2	wood (s beech Nos.	seasoned) s	ication, design ection with
D.2 D.3	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wo natural polish. The doors fitted with door closers shall be provided 3" x 11, natural polish for door frame work. Wooden partition door with vision panel (with frame work) - (WPD-1)- 2'-8" x 6'-6" Partly glazed door -(WPGD-1) - 2'-8" x 6'-6"	od / sal v /2" white 2 1	wood (s beech Nos. Nos.	seasoned) s	ication, design ection with
D.2 D.3	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wo natural polish. The doors fitted with door closers shall be provided 3" x 11, natural polish for door frame work. Wooden partition door with vision panel (with frame work) - (WPD-1)- 2'-8" x 6'-6" Partly glazed door -(WPGD-1) - 2'-8" x 6'-6" Partly glazed door -(WPGD-2) - 2'-6" x 6'-6"	od / sal v /2" white 2 1 3	wood (s beech Nos. Nos.	seasoned) s	ication, design ection with

	ARCHI SPACE CONSULTANT	UCO BANK	BRANC	H INTER	IOR FURNISH	IING WORK
R.NO	DESCRIPT	ION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.
E.	TABLE					
	Providing, fixing and fittings in position t thk BWR block board for top, sides and visible areas. The table will be supported on right side filing drawer and foot rest on the other board, other sides made out of 12 mm All exposed surfaces are finished with 1 will be 1 coat primer and 2 coat synthe moulding, lipping with melamine polish finish. The drawers and shutters to be pr etc all necessary accessories. Wire mar NOTE : First drawer at each work station etc. Drawer at each workstation to divit these to be divided into 3 equal partition	front of approved make finish be by a 1'-4" wide & 2'-0" deep side. The front of the drawer u thk BWR ply and 4" skirting thro .0 mm thk. Laminate of appro- etic enamel paint. All exposed hed. Polishing will be of the sar rovided with drawer sliding ch nager for each (approved color n must have shelves for segreg ided in 2 equal parts by a hori	ed with 1.0 r drawer unit unit will be m bughout (Foo ved make 8 l edge finish me color as iannels, S/S 4 our) will be p ating currer	mm lam consisti nade ou ot rest). colour ed with that of 4" long f provide ncy note	ninate as pe ng of one c ut of 19 mm shade and white bea lamination nandles, s/s d, all comp es pens/stap	er design in all drawer and one thk. BWR block inner surface ch/teak wood i.e., of Cedar hinges, locks lete. plers / stamps
E.1	Manager Table with Glass Top		5	R.ft.		
E.2	Officer Table		12	R.ft.		
E.3	Black powder coated key board tray w	vith slide channel	4	Nos.		
F.	CASH COUNTER					
	Providing and fixing the cash counters of Providing & fixing 2'-6" (w) x 2'-6" (h) wor It should have a customer transaction t table. Above the customer transaction will be placed on transaction top which transaction top will be rested & support thick. Laminate as per instruction. Below the Working table will be 1'-4" wi other side. The front of the drawer unit w mm thk BWR ply and 4" skirting through of approved make & colour shade and exposed edge finished with white bear the same color as that of lamination i.e sliding channels, S/S 4" long handles, s/s	rking table top made of 19 mr top, 6" projecting on the custo top does making a total heig ch is cut and shaped with edge ted together by a front apron ide & 2'-0" deep drawer unit co will be made out of 19 mm the out (Foot rest). All exposed sur d inner surface will be 1 coat p ch/teak wood moulding, lippin e., of Cedar finish. The drawers	m thick. BWR omer side at tht 4'-0".Gran es round pol (Double skir onsisting of k. BWR block faces are fin orimer and 2 ng with mel- and shutter	a heigh iite top ished. E Partitio Three c board nished v coat sy amine p s to be	nt of 1'-6" fro (Black galo Both the wo on) finished arawers and , other sides with 1.0 mm enthetic enc polished. Po provided w	m working (xy) 3/4" thick. rking table and with 1.0 mm foot rest on the made out of 1 thk. Laminate amel paint. All plishing will be a ith drawer

(approved colour) will be provided, all complete.

Providing and Fixing glass barrier in front of cash counter (above the the transaction top) made out of 12 mm thick polished edged float glass. It shall have 25mm x 20mm teakwood beading (as approved) to hold the glass from sides and top (optional). Etching to be done wherever required. The rates shall include for cutting (in geometrical shape, center bottom part of the transaction top) and polishing the edges. The rate should be including cost of decorative etching on on side of the glass, all complete to the satisfaction.

NOTE: First drawer at each work station must have shelves for segregating currency notes pens/staplers / stamps etc. Drawer at each workstation to divided in 2 equal parts by a horizontal partition and the front partition among these to be divided into 3 equal partitions by vertical partitions.

F.1	2 nos. Table	10	R.ft.	
F.2	Glass Barrier (Front)	30	Sq.ft.	
F.3	Black powder coated ready made key board tray with slide channel	2	Nos.	

6. Side Unit of Size 3'-6" x 1'-6" x 2'-6" (For Monoger) 10 Sq.ft. Providing and fining Side Unit made out of 19 mm BWB pity, 6 mm thk. Phy for back finished and 4" skirling. Throughout: There will be vertical dividers of same block bacads of maximum 1'-6" c/c. All seposed surface are finished with 10 mm thk. Lominote of approved made & colour source and a coard synthetic ename point. All exposed edge finished with white beach/readward on which the shurders will be 1 coart prime making will be of the same color as that all forminotion i.e., of Ceder finish. Cast of all fitti like s/s Hinges, Locks, magnetic catches, hower ball, "D" type Matt finish S.S. Hondles and all necessary hardware shall be inclusive, all complete. As par drawing and instruction. H. PULL HT. STORAGE 100 Sq.ft. H. Providing and fising full height Cobinet made out of 19 mm BWR pity A mm BWR pity. A mm Thk. Pity for back finish and 4" skifting throughout. There will be vertical divides of same block boards at maximum 41.4 gapat on which the shurders will be the color down and all necessary hardware shall be inclusive, all complete the same color as that of lamination i.e., of Ceder finish. Cast of all fitting like s/s Hinges, locks, magnetic catches, tower bot, TV pet Matt finish S.S. Hondles and all necessary hardware shall be inclusive, all complete are drawing and finish and brieght Cabinet made out of 19 mm BWR pity. A mm thk. Pity for back finish and 4" skifting throughout. Division of shutters shall be made ead on an euclassing hardware shall be inclusive, all complete catches, tower bot, TV pet Matt finish S.S. Hondles and all necessary hardware shall be inclusive, all complete catches. Hexposed surfaces a finished with 1.5 mm BWR pity wood to the length of the strange. All exposed surface a finished	SR.NC	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)
throughout, There Will be vertical divides of same block boards at maximum 41t apart on which the shuffers with statiles steel thinge and intermediate sheves (file divide) at maximum -6**/c. All exposed surface are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface will be 1 cost prime and 2 cost synthetic encent/eak wood moulding, lipping melamine polished. Polishing will be of the same color as that of tamination i.e., of Cedar finish. Cost of all fittil like s/s Hinges, locks, magnetic catches, tower bait, 'D' type Matt finish S.S. Handles and all necessary hardwore shall be inclusive, all complete. As per drawing and fistil.ctfon. H. RULHT. STORAGE 100 Sq.ft. Providing and fitting frugit height Cabinet made out of made out of 19 mm BWR ply, 6 mm thk. Pur back fittils and 4* shifting throughout. There will be vertical divides of same block boards at maximum 41 apart on which shuffers will be fitted with stainless steel hinge. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and immer surface will not madify and the same color as that of lamination i.e., of Cedar finish. Cost of all fitting like s/s Hinges. Locks. magnetic catches, tower boit, 'D' type Matt fittish's S. Handles and all necessary hardwore shall be inclusive, all comple per drawing and fitting throughout. Division of shufters shall be made equally according to the length of the storage. A mm thk. Evel the storage. A mm thk. Evel the storage. A mm thk. Evel the storage. A mm thk. Rev Next Mills with the storage will be of the same color as that of lamination i.e., of Cedar finish. Cast of all fitting like s/s Hinges. Incks. magnetic acthes, tower bit, 'D' type Matt Hinks and all necessary hardwore shall be inclusive, all complete as a finished with table. The storage. A speris stafface and the storage. A mm thk. Evel the storage	G.	Side Unit of Size 3'-6" x 1'-6" x 2'-6" (For Manager)	10	Sq.ft.			
Providing and King Full height Cabinet made out of made out of 19 mm BWR ply 6 mm kr. Ply for back finish and 4" skirling throughout. There will be vertical dividers of same block boards at maximum 4 ft apart on which shufters will be fitted with stainless steel hinge. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel pa All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel pa be of the same color as that of lamination i.e., of Cedar finish. Cast of all fitting like s/s hillinges, locks, magnetic catches, tower bolt."D" type Matt finish S.S. Handles and all necessary hardware shall be inclusive, all comple part drawing and fising Law height Cabinet made out of made out of 19 mm BWR Ply 6 nm thk. Ply for back finish and 4" skifting throughout. Division of shutter shall be made equally according to the length of the storage. A mm thk, Exe MWR Ply shelf on batters shall be provided at 16" intervals from the base. All exposed surfaces a finished with 1. Cam thk. Laminate of approved make & colour shade and lamination i.e., of Cedar finish. Cast of all fill like s/s Hings, locks. magnetic catches, tower bolt."D" type Matt finish S.S. Handles and all necessary hardwa shall be inclusive, all complete. As per drawing and instruction. J. SOFT BOARD 20 Sq.ft. J. Soft Board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with 1 dbric with necessary mouding duly polished along the periphery. K. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt 1 Nos. L. PLYWOOD CLADDING 20 Sq.ft.		throughout. There will be vertical dividers of same block boards at maxim fitted with stainless steel hinge and intermediate shelves (file divider) at r are finished with 1.0 mm thk. Laminate of approved make & colour shade and 2 coat synthetic enamel paint. All exposed edge finished with white melamine polished. Polishing will be of the same color as that of laminat like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S	num 4 ft naximur e and in beach/ ion i.e., o	apart c n 1'-6" c ner surf 'teak w of Cede	n which c/c. All e ace will ood mc ar finish.	n the expo be ouldi Cos	e shutters will be osed surfaces 1 coat primer ng, lipping with of all fitting
Providing and King Full height Cabinet made out of made out of 19 mm BWR ply 6 mm kr. Ply for back finish and 4" skirling throughout. There will be vertical dividers of same block boards at maximum 4 ft apart on which shufters will be fitted with stainless steel hinge. All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel pa All exposed surfaces are finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat primer and 2 coat synthetic enamel pa be of the same color as that of lamination i.e., of Cedar finish. Cast of all fitting like s/s hillinges, locks, magnetic catches, tower bolt."D" type Matt finish S.S. Handles and all necessary hardware shall be inclusive, all comple part drawing and fising Law height Cabinet made out of made out of 19 mm BWR Ply 6 nm thk. Ply for back finish and 4" skifting throughout. Division of shutter shall be made equally according to the length of the storage. A mm thk, Exe MWR Ply shelf on batters shall be provided at 16" intervals from the base. All exposed surfaces a finished with 1. Cam thk. Laminate of approved make & colour shade and lamination i.e., of Cedar finish. Cast of all fill like s/s Hings, locks. magnetic catches, tower bolt."D" type Matt finish S.S. Handles and all necessary hardwa shall be inclusive, all complete. As per drawing and instruction. J. SOFT BOARD 20 Sq.ft. J. Soft Board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with 1 dbric with necessary mouding duly polished along the periphery. K. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt 1 Nos. L. PLYWOOD CLADDING 20 Sq.ft.				0 11			
Providing and fixing Low height Cabinet made out of made out of 19 mm BWR ply, 6 mm thk. Ply for back finist and 4" skirling throughout. Division of shutters shall be made equally according to the length of the storage. A mm thk. Fixed BWR Ply shelf on battens shall be provided at 16" intervols from the base. All exposed surfaces a finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat p and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping melamine polished. Polishing will be of the same color as that of tamination i.e., of Cedar finish. Cost of all fittil like s/s Hinges, locks magnetic catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary hardwa shall be inclusive, all complete. As per drawing and instruction. J. SOFT BOARD 20 Sq.ft. J. Soft Board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with fabric with necessary moulding duly polished along the periphery. Image: Color of the same color as that of tamination i.e., of Cedar finished with fabric with necessary moulding duly polished along the periphery. L. PLYWOOD CLADDING 1 Nos. L.1 Banking & Customer Area (5-0" height) 600 Sq.ft. Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm the comproved make & color) on faces with 0.5" moulding on top. Image: Complete as directed by Architect. M. P.O.P & PAINTING Image: Complete as directed by Architect. Image: Complete as directed by Archit		Providing and fixing Full height Cabinet made out of made out of 19 mm and 4" skirting throughout. There will be vertical dividers of same block be shutters will be fitted with stainless steel hinge. All exposed surfaces are fi approved make & colour shade and inner surface finished with 1 coat pr All exposed edge finished with white beach/teak wood moulding, lippin be of the same color as that of lamination i.e., of Cedar finish. Cost of all catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary ho	BWR ply pards at nished w imer and g with m fitting lil	v, 6 mm maxim vith 1.0 d 2 coa nelamir ke s/s H	um 4 ft mm thk t synthe ne polish inges, lo	apa . Lar tic e ned. ocks,	rt on which the minate of enamel paint. Polishing will magnetic
Providing and fixing Low height Cabinet made out of made out of 19 mm BWR ply, 6 mm thk. Ply for back finist and 4" skirling throughout. Division of shutters shall be made equally according to the length of the storage. A mm thk. Fixed BWR Ply shell fon battens shall be provided at 16" intervols from the base. All exposed surfaces a finished with 1.0 mm thk. Laminate of approved make & colour shade and inner surface finished with 1 coat p and 2 coat synthetic enamel paint. All exposed edge finished with white beach/teak wood moulding, lipping melamine polished. Polishing will be of the same color as that of tamination i.e., of Cedar finish. Cost of all fitti like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary hardwa shall be inclusive, all complete. As per drawing and instruction. J. SOFI BOARD 20 Sq.ft. Soft board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with fabric with necessary moulding duly polished along the periphery. Image: Color of the same color on top 12 jolly board to be fixed finished with fabric with necessary moulding duly polished along the periphery. L. PLYWOOD CLADDING 1 Nos. L.1 Banking & Customer Area (5-0" height) 600 Sq.ft. Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm th Laminate (approved make & color) on faces with 0.5" moulding on top. Image: Complete as directed by Architect. M. P.O.P & PAINTING Image: Complete as directed by Architect. Imagning as P.O.P. : Providing & applying Three c		IOW HT STORAGES (1'-4" DEPTH X 2'-4" HT) (BACK CREDENZA)	75	Sa ft			
Soft board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with fabric with necessary moulding duly polished along the periphery. K. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt 1 Nos. L. PLYWOOD CLADDING 1 Nos. L.1 Banking & Customer Area (5'-0" height) 600 Sq.ft. Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm the Laminate (approved make & colour) on faces with 0.5" moulding on top. 1 No M. P.O.P & PAINTING 1 1 No Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approven make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface free from water / mortar dropping other forging matter and sand paper smooth, complete as per manufacturers specifications and as directed. M.I Celling Painting & P.O.P. (without strong room) 250 Sq.ft.		and 2 coat synthetic enamel paint. All exposed edge finished with white melamine polished. Polishing will be of the same color as that of laminat like s/s Hinges, locks, magnetic catches, tower bolt, "D" type Matt finish S.	beach/ ion i.e., ('teak w of Cede	ood ma ar finish.	ouldi Cos	ng, lipping with at of all fitting
Soft board with necessary framework with 12 mm BWR plywood on top 12 jolly board to be fixed finished with fabric with necessary moulding duly polished along the periphery. K. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt 1 Nos. L. PLYWOOD CLADDING 1 Nos. L.1 Banking & Customer Area (5'-0" height) 600 Sq.ft. Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm the Laminate (approved make & colour) on faces with 0.5" moulding on top. 1 No M. P.O.P & PAINTING 1 1 No Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approven make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface free from water / mortar dropping other forging matter and sand paper smooth, complete as per manufacturers specifications and as directed. M.I Celling Painting & P.O.P. (without strong room) 250 Sq.ft.		shall be inclusive, all complete. As per drawing and instruction.					ry hardware
Image:			20	Sa ft			ry naraware
L.1 Banking & Customer Area (5'-0" height) 600 Sq.ft. Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm th Laminate (approved make & colour) on faces with 0.5" moulding on top. M. P.O.P & PAINTING Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approve make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface free from water / mortar dropping or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface including thoroughly brushing the surface free from water / mortar dropping or other forging matter and sand paper smooth, complete as per manufacturers specifications and as directed. M.1 Celling Painting & P.O.P. (without strong room) 250 Sq.ft.	J.	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 13					
L.1 Banking & Customer Area (5'-0" height) 600 Sq.ft. Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm th Laminate (approved make & colour) on faces with 0.5" moulding on top. M. P.O.P & PAINTING Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approve make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface free from water / mortar dropping or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface including thoroughly brushing the surface free from water / mortar dropping or other forging matter and sand paper smooth, complete as per manufacturers specifications and as directed. M.1 Celling Painting & P.O.P. (without strong room) 250 Sq.ft.		SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 1 fabric with necessary moulding duly polished along the periphery.	2 jolly bo	pard to			
Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwalls and Columns finished with 1 mm th Laminate (approved make & colour) on faces with 0.5" moulding on top. M. P.O.P & PAINTING Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approved make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface including thoroughly brushing the surface free from water / mortar dropping or other forging matter and sand paper smooth, complete as per manufacturers specifications and as directed. M.1 Celling Painting & P.O.P. (without strong room) 250 Sq.ft.	К.	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 13 fabric with necessary moulding duly polished along the periphery. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt	2 jolly bo	pard to			
Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect.Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approved make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied or coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface including thoroughly brushing the surface free from water / mortar dropping on the forging matter and sand paper smooth, complete as per manufacturers specifications and as directed.M.1Celling Painting & P.O.P. (without strong room)250Sq.ft.	K.	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 13 fabric with necessary moulding duly polished along the periphery. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt PLYWOOD CLADDING	2 jolly bo	Nos.			
Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emulsion paint of approved make to interceiling in approved colour over a coat of water based primer including preparation of surface by thorough cleaning as per manufacturers specifications to give a smooth and even surface. Complete as directed by Architect.Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion paint of desired shade, of approved make on internal wall surfaces wherever required at all heights to give an even and uniform shade , applied o coat of primer and putty "Alter or Wall care "or approved equivalent as per manufactured specification fully the give a smooth and even surface including thoroughly brushing the surface free from water / mortar dropping on the forging matter and sand paper smooth, complete as per manufacturers specifications and as directed.M.1Celling Painting & P.O.P. (without strong room)	K.	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 11 fabric with necessary moulding duly polished along the periphery. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt PLYWOOD CLADDING Banking & Customer Area (5'-0" height) Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwa	2 jolly bo	Nos.	be fixed	d fini	shed with
M.1 Celling Painting & P.O.P. (without strong room) 250 Sq.ft.	К. L.1	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 11 fabric with necessary moulding duly polished along the periphery. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt PLYWOOD CLADDING Banking & Customer Area (5'-0" height) Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwa Laminate (approved make & colour) on faces with 0.5" moulding on top.	2 jolly bo	Nos.	be fixed	d fini	shed with
M.2 Wall Painting & P.O.P. 1400 Sq.ft.	К . L.1	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 11 fabric with necessary moulding duly polished along the periphery. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt PLYWOOD CLADDING Banking & Customer Area (5'-0" height) Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwa Laminate (approved make & colour) on faces with 0.5" moulding on top. P.O.P & PAINTING Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emuceiling in approved colour over a coat of water based primer including p cleaning as per manufacturers specifications to give a smooth and even Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsi make on internal wall surfaces wherever required at all heights to give ar coat of primer and putty "Alter or Wall care "or approved equivalent as p give a smooth and even surface including thoroughly brushing the surface	2 jolly bo 1 600 Ils and C Ulsion po preparat surface on paint n even c per manu e free free	Nos. Nos. Sq.ft. Column: int of c ion of s . Comp t of des ind unif ufacture om wa	be fixed be fixed s finished upprove urface k olete as ired sha orm sha ed spec ter / mo	d fini d wi d wi d wi dire, ificc rtar	shed with shed with th 1 mm thk. ake to internal norough cted by of approved applied over c ation fully to dropping and
	к. L.1 М.	SOFT BOARD Soft board with necessary framework with 12 mm BWR plywood on top 11 fabric with necessary moulding duly polished along the periphery. Notice Board 3' x 2' Acrylic 6 mm sheet with SS Bolt PLYWOOD CLADDING Banking & Customer Area (5'-0" height) Providing and fixing 18 mm. thk. Plywood cladding to all internal brickwa Laminate (approved make & colour) on faces with 0.5" moulding on top. P.O.P & PAINTING Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emuceiling in approved colour over a coat of water based primer including period cleaning as per manufacturers specifications to give a smooth and even Architect. Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsi make on internal wall surfaces wherever required at all heights to give ar coat of primer and putty "Alter or Wall care "or approved equivalent as p give a smooth and even surface including thoroughly brushing the surface other forging matter and sand paper smooth, complete as per manufactions and paper smooth.	2 jolly bo 2 jolly bo 1 600 Ils and C ulsion po preparat surface on paint n even co per manu e free fro turers spo	Nos. Nos. Sq.ft. Column: int of c ion of s . Comp t of des ind unif ufacture om wa ecificat	be fixed be fixed s finished upprove urface k olete as ired sha orm sha ed spec ter / mo	d fini d wi d wi d wi dire, ificc rtar	shed with shed with th 1 mm thk. ake to internal norough cted by of approved applied over c ation fully to dropping and

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)
N.	SUGGESTION BOX & CHEQUE DEPOSIT BOX				
	Providing and fixing suggestion box & cheque deposit box 1'-6" x 1'-6" x 6" letters (individual) made out of 18 mm BWR block board and finished wit synthetic enamel painted.A 1" high slit & small door with key and locking taking out the slips, all complete as per instruction.	h 1.0 mr	m thk Ic	iminate & ir	nside to be
N.1	Suggestion box	1	No.		
N.2	Cheque deposit box	1	No.		
О.	TRAP DOOR & BOXING FOR ROLLING SHUTTERS	30	Sq.ft.		
	Providing and fixing trap doors consisting of 1/4" thk. Marine ply shutters w smooth operation of shutters and rest is closed with mirror screws (for ope finished with approved 2.0 mm Aluminium composite sheet, frame of 2" x provided for proper supprot and strength. Rate shall be inclusive of neces tower bolts, etc. Complete as per the instructions of Architect.	ning for 1 ½" te	servicir ak woo	ng). The shu od sections	tters shall be shall be
P.	MAIN PANEL ENCASEMENT	35	Sq.ft.	180	
	Providing & Fixing 3" X 1 1/2" c.p.t.wood frame work to the wall along with mm thick of approved make/color laminate with teak wood battens strip shade fixed with box hinges & bedding patti finish with 3 coats of polish & approved make/design colour etc. Complete as per instructions of Archir	os of 1" X & provid	(1" in to	apered fash	ion of approved
	TOTAL INTERIO	R FURN	ISHING	WORKS	
		-			
IN \	WORDS :				
IN 1	WORDS : Excluded Items				
1	WORDS : Excluded Items All civil works including demolish work, brick work , Plastering, Flooring wo				
1 2	WORDS : Excluded Items All civil works including demolish work, brick work , Plastering, Flooring wo Grill, Collapsible gate & Rolling shutter				
1	WORDS : Excluded Items All civil works including demolish work, brick work , Plastering, Flooring wo Grill, Collapsible gate & Rolling shutter Plumbing & Sanitary work and Sanitary fittings & fixture work.				
1 2	WORDS : Excluded Items All civil works including demolish work, brick work , Plastering, Flooring wo Grill, Collapsible gate & Rolling shutter				
1 2 3	WORDS : Excluded Items All civil works including demolish work, brick work , Plastering, Flooring wo Grill, Collapsible gate & Rolling shutter Plumbing & Sanitary work and Sanitary fittings & fixture work.				

INTERIOR FURNISHING WORK OF ATM B.O.Q. - RAGHUNATHGANJ BRANCH.

SR.NO	DESCRIPTION	QTY.	UNIT	RATE	(Rs.	AMOUNT (Rs.)
A. 1	False Ceiling - Gypsum Board:	35	Sq.ft.			
	Providing & Fixing suspended gypsum false ceiling, which includes provid size 0.55mm thick having one flange of 20mm and another flange of 30m of ceiling screws fixed to brick wall / partition with the help of nylon sleev suspending G.I. Intermediate channels of size 45mm X 0.9mm thick with 2 1220mm centers with ceiling angle of width 25 X 10mm X 0.55mm thick fix fastners only, "Fastners" shall be used for ceiling supports. Ceiling section of 51.5mm & two flanges of 26mm each with lips of 10.5mm are then fixed t of connecting clips & in direction perpendicular to the intermediate chan edge gyp board (Conforming to IS-2095-1982) is then screws fixed to ceiling are to be jointed and finish so as having a flush look, which includes filling edges of the boards with jointing compound, paper tape & two coats of light fittings, grills diffusers and cutouts, speakers, fire detectors etc. have channels of size 20 X 27 X 30mm X 0.545mm thick, supported suitably as pconsultants & shown as per detail drawing without additional payments. coats of ICI. Plastic emulsion paint with necessary scraping, putty, levelin cleaning etc.	m & a w res and s 2 flanges ked to sc of 0.55mr o the inte- nnel at 4 ng to ce rructions hine with g and fini primer si to be mo er directi Entire fa g & smoo	eb of 2 crews of 15m offit wit n thick ermed 57mm illing se and A souitable ade wi ion of <i>i</i> ilse cei oth fini	27mm c at 600n am eac h G.I. 8 ness hc iate ch center cction v C Plan ble attc he tappe for Gy th the f Archited ling sho sh with	alon and b fro c stee aving anne s. 12 / Sec achm p bo fram- ct, El all be sca	g with perimeter centers then om the soffit at el expansion g knurled verb of el with the help .5mm tapered 25mm dry wait ction / Layout. hent. The boards and square bard. Note :- For e of perimeter ectric or A.C. e finish with 3 ffolding,
	removed along with debris out of compound without any extra charge.					
B.	Wooden Double Skin Solid Partition With Both Sides Laminate Finish	85	Sq.ft.			
	Supply & Erecting Solid Partition as per drawing & conforming to the follow Basic Framework: Well seasoned Malaysian Sall wood sections, treated w 50 mm (minimum) at maximum 2 ft horizontal and vertical spacing as per suitably anchored at floor level to ensure rigidity Skin Membrane: 6 mm BWR grade Ply wood on each face with 2 mm gra Finishing: 1.0 mm thk. Iaminate sheet of combination shades as per instru Skirting: The Partition will be finished with 4" wide Skirting finished with 1.0 laminate of approved make on both sides. Note: Quoted Rates shall include all necessary material, accessories and Telephone / Computer wiring conduits and switch boxes etc. (Materials of be separately paid for) The work to be completed as per instruction.	ith two c r site cor oves as p action (as mm thic also allo	coats c ndition. er drav s appro k Bank w prov	of wood Vertice wing / i byed m 's appro	al m nstru ake) ovec or ele	ember shall be ction. on both face I colour ectrical /
C.						
		25	So ft			
	STORAGE UNIT Providing and fixing Full height Cabinet made out of made out of 19 mm and 4" skirting throughout. There will be vertical dividers of same block bo shutters will be fitted with stainless steel hinge. All exposed surfaces are fin approved make & colour shade and inner surface finished with 1 coat pri All exposed edge finished with white beach/teak wood moulding, lipping be of the same color as that of lamination i.e., of Cedar finish. Cost of all catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary ha per drawing and instruction.	pards at i nished w mer and g with m fitting lik	maxim ith 1.0 I 2 coa elamir e s/s H	um 4 ft mm thl t synthe ne polis inges, l	apc k. La etic hed. ocks	It on which the minate of enamel paint. Polishing will , magnetic
	Providing and fixing Full height Cabinet made out of made out of 19 mm and 4" skirting throughout. There will be vertical dividers of same block be shutters will be fitted with stainless steel hinge. All exposed surfaces are fin approved make & colour shade and inner surface finished with 1 coat pri All exposed edge finished with white beach/teak wood moulding, lipping be of the same color as that of lamination i.e., of Cedar finish. Cost of all catches, tower bolt, "D" type Matt finish S.S. Handles and all necessary ha	BWR ply, bards at i nished w mer and g with m fitting lik	, 6 mm maxim ith 1.0 I 2 coa elamir e s/s H	um 4 ft mm thl t synthe ne polis inges, l	apc k. La etic hed. ocks	It on which the minate of enamel paint. Polishing will , magnetic

SR.NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.	AMOUNT (Rs.)			
	Providing and fixing solid core flush door of 38 mm thk. Finished with 1 mm thk. approved colour laminate . A wooden cover moulding of 3"x3/4" thk. white beech /teak wood with polish shall be provided. 8 mm thk. clear							
	float glass with etching (approved design) shall be provided with 1 1/2"x3		•					
	moulding with polish for partly glazed door. In case of vision panel door 18"x9" made out of 8 mm thk. Clear glass							
	with moulding with polish to be provided. The rate shall be inclusive of 4" s/s hinges, door stopper, screws,10" 'H'							
		hape s/s handle (Kitch), dead lock, key hole cover, tower bolt, door closer of approved make. All edges of the door to be covered with necessary lipping with polish. The work should be completed as per specification, design						
	and approval of Architect.				_			
	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak woo							
	natural polish. The doors fitted with door closers shall be provided 3" x 11/2 natural polish for door frame work.	2" white	beech	/ leak woo	d section with			
D.1	Wooden partition door with vision panel - (WPD-2)- 2'-6" x 6'-6"	1	Nos.					
D.2	MAIN ENTRANCE DOOR CUM FIXED GLAZING							
D.2	with sticker design bank's name,logo,eatching,band etc							
	a) Openable Portion	20	Sq.ft.					
	b) Fixed Portion	30	Sq.ft.					
		Providing & fixing fully glazed pivoted door at the main entrance consists of 6"x2" c.p.t. wood frame for top rail and 4"x2" c.p.t. wood frame for bottom rail finished with 1.0 mm thk laminate, sides with 1" X 1" c.p.t.wood mouldings of						
	approved design. 12mm thk. toughened glass with sand blasting /etching							
	outside) to be fixed on both sides & proper locking arrangement in bottor	m rail to	be dor	ne. The rate	should include			
	lipping, moulding, beading, sticker design bank's name, logo, Pull & Push		heavy	duty floor s	pring of			
	approved make. The work to be completed as per drawing and instruction	Dri.						
E.	ACP PANELING	150	Sq.ft.					
	Supplying , fabricating and installing Aluminium Composite Panel (as per	approve		ours) Claddii	ng to walls and			
	door , comprising of 4mm thick (0.5 mm + 3 mm + 0.5 mm) approved bra	nd acp i	materi	al with bac	Al frame work			
	in 0 level with joints and sizes as per front elevation working drawing. All c structure, aluminium brackets ,silicon sealants(all the joints shall in 5 mm g							
	sealant), gaskets, PVDF coating etc. all compete including bird / vermin							
F.	Display Boards for Bank's Advertisement	1	Nos.					
	Providing & fixing in position fameless double Acrylic transparent sheets 2'-6" x 1'-6" mounted with studs on the wall							
	(poster to be sandwiched in between) for display of Bank's advertisement inserted on it. Outer sheet is 5 mm thick and beveled crystal edge polished for ¾" at 8-10 degrees on all sides in the front. Rear sheet is 5 mm thick flat. Rate							
	inclusive of \$1 grade aluminium.							
G.	PAINTING & P.O.P.	135	Sq.ft.					
0.	Ceiling painting & P.O.P. : Providing & applying Three coats of Plastic Emu			approved m	ake to internal			
	ceiling in approved colour over a coat of water based primer including p	reparati	on of s	urface by th	norough			
	cleaning as per manufacturers specifications to give a smooth and even Architect.	surface.	Comp	olete as dire	cted by			
	Wall painting & P.O.P. : Providing & applying three coats of Acrylic Emulsion	on paint	of des	ired shade,	of approved			
	make on internal wall surfaces wherever required at all heights to give an	even a	nd unif	orm shade ,	applied over a			
	coat of primer and putty "Alter or Wall care "or approved equivalent as p give a smooth and even surface including thoroughly brushing the surface							
	other forging matter and sand paper smooth, complete as per manufact							
H.	TRAP DOOR &BOXING FOR ROLLING SHUTTERS	30	Sq.ft.		oponing for			
	Providing and fixing trap doors consisting of 1/4" thk. Marine ply shutters w smooth operation of shutters and rest is closed with mirror screws (for ope							
	finished with approved 2.0 mm Aluminium composite sheet, frame of 2" x 1 $\frac{1}{2}$ " teak wood sections shall be							
	provided for proper supprot and strength. Rate shall be inclusive of necessary fittings like hinges, ball catches,							
	ower bolts, etc. Complete as per the instructions of Architect.							
	TOTAL INTERIOR FURNISHING WORKS							
IN \	VORDS :							
	Excluded Items							
1	All civil works including demolish work, brick work , Plastering, Flooring work, Tiles Work , R.C.C. work.							
2	2 Grill, Collapsible gate & Rolling shutter & Any type Metal Paint							


B.O.Q. FOR UCO BANK RAGHUNATHGANJ BRANCH, MURSHIDABAD

ARCHI SPACE CONSULTANT

<u>SUMMARY</u>

SL. NO.	DESCRIPTION	AMOUNT (Rs.)			
1	INTERIOR WORKS OF BANKING AREA				
2	INTERIOR WORKS OF ATM				
	TOTAL (1+2)				
Note: Cost including all material, labour and Transport charges etc., all comple work to be completed as per design, specification and approval of the					

<u></u>	LIST OF APPROVED MATERIALS FOR INTERIOR FURNISHING WORK				
SI.No.	Items	Approved make			
1	False Ceiling	Armstrong / India Gypsum			
2	Wood Frame Work / Wood Section	Malaysian Sal			
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Ceder			
4	Door frame	Teak wood /Sal Wood			
5	BWR Ply / Block board with ISI mark	Alishan/ Sylvan/ Green/ Century/ Avenger/ Satabdi/ Globe			
6	Flush Door	Alishan/ Sylvan/ Green/ Century/ Avenger/ Satabdi/ Globe			
7	Laminate (1.0 mm thk.)	Sunmica / Euromica / Green Iam /Merino / Century/ Airolam			
8	Door Closure (Heavy Duty)	Godrej / Archi / Sterling (DC 2000)			
9	Floor Spring (Heavy Duty)	Godrej / Archi / Sterling (FS 3000)			
10	Door Lock (Dead)	Godrej / Hafele /Hettich / Kich /Doorset / 4C Acme (ML – REG – SS)			
11	Door Handles ('H' Shape)	Godrej / Hafele /Hettich / Kich /Doorset / 4C Acme (PHG – HSS)			
12	Drawer / Storage Handle (4"/ 6")	Kich /Neki / Hassley/EGL (HMS –B – 9122 / 9123)			
13	Drawer / Storage Lock (Multipurpose)	Ebco / Hafele /Hettich / Doorset / Godrej / Kombo (502)			
14	Screws	GKW / Nettle fold			
15	Hinges	CIEF			
16	Sliding Telescopic Drawer Channel	Ebco / Kombo			
17	Key Board Tray (Metal)	Ebco / Innofitt Systems (KD 510. M)			
18	Cable Organiser	Ebco / Innofitt Systems (CM 63.C)			
19	Adhesive	Fevicol SH / Fevimate TL			
20	Aluminium Door Frame	Jindal			
21	Soft Board	Jolly Board			
22	Vertical Blinds	Mac / Annums / Window Fashion			
23	Glass	Modi /Ashai / Saint Gobain			
24	A.C.P	Alu Decor / Alu Bond / Alstone/ Wonder Alu board Accura			
25	Paints	(Synthetic Enamel / Acrylic Emulsion) Asain Paints (Colour World) / Berger (Colour Bank)			
26	All other items not covered above	As per sample approved by Employer/Consultant			



					EW1	Existing window	4'-5" x 3'-9"	1		
]					EW2	Existing window	2'-6" x 2'-0"	2	T 1 4	
TO RAGHUNATHGANJ	DOAD TO JANG		TDCT		EW3	Existing window	4'-11" x 3'-9"	3	Existing window	
	ROAD	\rightarrow <u>F</u>	IKS	Γ FLOOR	EW4	Existing window	2'-4" x 3'-4"	1	Aluminium frame with	
			P	LAN	EW5	Ext. Louver window	2'-0" x 3'-0"	2	grill fitting	
					Refer	Reference :				
GROUND FLOOR				1. Site	1. Site visit of the Architect on 19.01.17					
PLAN										
						2. Submission of Preliminary				
					Drawing on 24.01.17					
UCO BANK Vill-Jangipara, Sahebpur Bazar(1st floor),	DRG NO UCO/ RAG	HUNATHGANJ/RE-05		ARCHI SI	TIN PLACE	, "AMELLIA A	PARTMEN	T", (C	G FLOOR),	
P.SRaghunathganj, Murshidabad, PIN742213, W.B.	DATE : 11.08.17	DRAWN BY : Sayarti Ghosh	N	BINNAGAR, NE MOB NO (+91)	AR BAGHA	AJATIN STAT	ION, KOLKA	4ŤÀ	- 700086.	