

Tender/ATM/UCO/Oct-07/2022/2678-2020

19.10.2022

**SUMMARY**

**UCO BANK**

**PARTAPUR BRANCH, DISTT. MEERUT**

sno	Description		Amount of Tender
1.	Furnishing works		
2.	Electricals works		
3.	Air Conditioners Works		
	TOTAL		
	GST 18% (+)		
	GRAND TOTAL		

**Note :-**

1. All materials to be used strictly follow the list of approved materials.
2. Any deviation in the use of materials at site other than approved materials list will not be permitted and the bank may cancel the contract at any time for any such misconduct.
3. The workman ship and quality of work should be of good quality and to be satisfaction level of the bank's architect and bank



Tender/ATM/UCO/Oct-07/2022/2678-2020

19.10.2022

**TENDER FOR FURNISHING & ELECTRICAL WORKS FOR ATM OF UCO BANK PARTAPUR BRANCH, DISTT. MEERUT.**

**A. FURNISHING WORKS:-**

SNO	ITEMS	QTY	UNIT	RATE	AMOUNT
1.A	<b>FALSE CEILING:-</b> Providing & fixing white mineral fiber tile (size 24" x 24") / equaling false ceiling with G.I. frame T angle (size 24" x 24") aluminum frame work. The frame channel should be suspended from the R.C.C. slab strap hangers. 12 mm thick board panels shall be screwed to the frame work with steel screws. All additional frame work required for light points. Fitting shall be provided.	16.00	SQ.FT.		
	<b>FALSE CEILING (Gyp board):-</b>				
b.	Providing and fixing Gypsum false ceiling as per India Gypsum specification for ceiling with drops as per drawing including of providing and fixing G.I. Frame work as per specification of India gypsum at a distance of 2'0"c/c both ways complete with 12.5 mm board and all necessary perimeter channels etc. No extra payment will be made for the cutting of light points, stained glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required.	90.00	SQ.FT.		
2.	<b>ACP WALL PANELING:-</b> P/f ACP Panel laminate finished Single face wall paneling on existing wall surface, using 1"x2" G.I. framing vertical & horizontal member at 2'0" c/c on both ways with cross halve joints including screwing and the same fixed rigidly to floor, wall. Frame covered with ACP Panel finished with matching	250.00	SQ.FT.		





	as per detail/ instruction complete. The edge to be finished with Aluminium Composite Panel.  <b>Note:-</b> <b><u>only ACP work to be done.</u></b> <b>ACP (Aluminium Composite Panel)</b> <b>Paneling is in colour as per brand manual.</b>				
3.	<b><u>CUSTOMER DESK:-</u></b>  Making and supplying writing desk made out of 19 mm thk marine ply having internal division for loose slips. The size of box 1'-0" x 1'-6", 6" Depth has got 12 mm clear glass top. The total box sides, bottom are polished fixed to wall. Complete.	1.00	EACH		
4.	<b><u>ROOLING SHUTTER BOX IN ACP :-</u></b>  SIZE 10'-0" Lx1'-3"W x 3'-0"H:-  SPECIFICATIONS SAME AS ITEM NO. 2	30.00	SQ.FT.		
5.	Card Reader Pillar each:-	1.00	EACH		
6.	<b><u>PARTITION FOR UPS ROOM:-</u></b> Providing and fixing partition in position as per design with 2" x 2" Aluminum section finished frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats. The measurement will be taken upto the false ceiling visible height in case of full height partition. The frame work will be clad with 12 mm thick comm. Ply both sides and to be finished with approved 1 mm laminate (color with vertical grain) as per design with adhesive. 3" high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing glass. In the glazed partition 10mm thick.	72.00	SQ.FT.		
7	A.C. LOUVER'S	1.00	EACH		
8	<b>SUGGESTION/COMPLAINT DROP</b>	2.00	NOS.		



<b>BOX:-</b> P/F a suggestion box of size up to 1'-0"x1'-6"x6" made out of 3/4" commercial board with 1.0mm laminate on top as per design.				
<b>TOTAL</b>			Rs.	

**B. ELECTRIC ESTIMATE:-**

<u>S.NO</u>	<u>PARTICULARS</u>	<u>QTY</u>	<u>RATE</u>	<u>AMOUNT</u>
(1)	Supply & fitting of all electrical point complete with testing, commissioning, handling, storing, all material for wiring of light point, fan, exhaust fan, socket, & bell point 5 amp with 1.0, 1.5 sq mm cu wire in PVC pipe with accessories i.e. bend JB, tee etc concealed/ surface on wall with saddle screw etc. controlled by 5 amp switch on plate with box in wall.	05 no		
(2)	Same as above but for 15 amp switch/socket with 2 x 2.5 + 1 x 1.0 sq mm cu wire in PVC pipe	03 no		
<b>Note:-</b> <b>ALL WIRING AND CIRCUIT TAKEN FROM L.T. PANEL and LT PANEL FIXED IN INFORNT OF MAIN ENT. GATE OF BRANCH.</b>				
(3)	G.I. Earthing with 50 x 3 M. ear thing electrode With chemical as specified items instructed by the Architect.	01 no		
(4)	Supplying & Fixing 2' x 2' LED fittings with Crompton /Philips/ Bajaj Make	02 no		
(5)	Supplying & Fixing LED down light fittings with Philips or Crompton or Bajaj make	06 nos		
(6)	LED Strip Light (Cove Light)	20.00 RFT.		
(7)	A.C. points i/c Box, MCB, Socket, Switch i/c 32 C MCB Complete i/c wiring and complete with necessary items.	2 nos.		
(8)	Split A.C. Gas Pipe line copper with wire	60 rft.		
(9)	PVC pipe drain for A.C.	50 rft.		





Tender/ATM/UCO/Oct-07/2022/2678-2020

19.10.2022

(10)	Ups point i/c wiring and necessary items	3 nos	
(11)	Data points i/c wiring and necessary items	6 nos	
(12)	12" Exhaust fan of Commercial / Industrial Quality.	1 no.	
(13)	Earthling wire	25 Mt	-----
		Total	Rs.

<b><u>AIR CONDITIONER WORKS UCO BANK ATM PARTAPUR BRANCH, DISTT. MEERUT</u></b>					
S.no	Particulars	qty	Unit	Rate	Amount
1	Split AC 1.0 ton in ATM  <u>copper make Five Star Rated inverter A.C.</u> <u>Make Voltas, Hitachi &amp; Blue star,</u> Complete with Outdoor Units, Indoor Units, Mounting Racks, Copper Insulated Tubing, Wiring, which is standard with equipment <b><u>Note:-</u></b> <b><u>Out of these three companies selection of brand</u></b> <b><u>will be at sole discretion of bank</u></b>	2	Nos.		
2	Supply & Fixing with installation of stabilizer (having capability to work from 90 Volts) of copper wiring for Split and Cassette A.C.	2	Nos		
3	Supply/fixing of stand for external unit of A.C. for Split	2	nos		
	<b>TOTAL</b>				



**Note:-**

1. *Final Amount in words filled in Tender will be considered. No further discount written in numerical or words will be considered. After Tender has been filled. No condition or % of discount etc. will be considered which dictates re-calculation of any kind.*
2. *GST Extra.*
3. *All switches will be modular switches.*
4. *All electrical fittings will be Modern as per latest circular, brand manual & actual sample photographs.*
5. *Before filling tender please go through attached drawing for distance & other related quarries. We also advise Vendor to visit site physically if possible to determine actual work environment and difficulties*

1. Estimate of Furnishing works	Rs.
2. Estimate of Electric works	Rs.
3. Estimate of Air Conditioners works	Rs.-----
4. Total	Rs.

Certified by: -

**(Ar. Manmeet Singh Bajaj)**  
Regd. Architect.  
M/s Bajaj & Associates,  
Sophia Market, Court Road,  
Saharanpur



Tender /Fur/Uco Bank/Oct-07/2022/2678-2020

19.10.2022

**Summary**

**UCO BANK**

**PARTAPUR BRANCH, DISTT. MEERUT**

sno	Description		Amount of Tender
1.	Furnishing works		
2.	Electricals works		
3.	Air Conditioners works		
	TOTAL		
	GST 28% and 18% (+)		
	GRAND TOTAL		

**Note :-**

1. All materials to be used strictly follow the list of approved materials.
2. Any deviation in the use of materials at site other than approved materials list will not be permitted and the bank may cancel the contract at any time for any such misconduct.
3. The workman ship and quality of work should be of good quality and to be satisfaction level of the bank's architect and bank





**TENDER OF FURNISHING WORKS FOR UCO BANK PARTAPUR BRANCH DISTT MEERUT****1. FURNISHING WORKS IN BRANCH :-**

SNO	ITEMS	QTY	UNIT	RATE	AMOUNT
1.A	<b>FALSE CEILING (Gyp board):-</b>				
	Providing and fixing Gypsum false ceiling as per India Gypsum specification for ceiling with drops as per drawing including of providing and fixing G.I. Frame work as per specification of India gypsum at a distance of 2'0"c/c both ways complete with 12.5 mm board and all necessary perimeter channels etc. No extra payment will be made for the cutting of light points, stained glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required.	550.00	SQ.FT.		
B.	<b>False ceiling (24"x24" Grid False Ceiling</b>				
	<b>24" x 24" Grid False Ceiling (FINE FISSURED PLANKS):</b> Providing and Fixing False ceiling Grid using hot dipped Galvanized steel sections, exposed surface chemically cleaned capping pre-finished in baked polyster paint. Main tee of size 3000 x 32 x 24 mm at every 1200mm c/c maximum, 1200mm cross Tee of size 1200 x 27 x 24mm at every 600mm intervals and 600 mm cross Tee of size 600 x 25 x24mm at 1200mm max and 3000 x 19 x 19mm wall angle all around the wall to form grid size of 600mm x600mm. The Main grid to be suspended to the MS frame with 2mm pre-straightened GI wire and GI adjustable clamp and Laying of fiber wool board having Fire rating of 60 min. as per BS 476/23 of 1987, Noise reduction co-eff. (NRC) of 0.50, Light	832.00	SQ.FT.		
2.	<b>PARTITION</b>				





	Providing and fixing partition in position as per design with 2" x 2" Aluminum section finished frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats. The measurement will be taken upto the false ceiling visible height in case of full height partition. The frame work will be clad with 12 mm thick comm. Ply both sides and to be finished with approved 1 mm laminate (color with vertical grain) as per design with adhesive. 3" high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing glass. In the glazed partition 10mm thick.				
A	<b>PARTLY GLAZED PARTITION</b>				
I	PARTLY GLAZED CASH CABIN PARTITION UPTO 7'-0" HT.	85.00	SQ.FT.		
II	PARTLY GLAZED MANAGER CABIN PARTITION UPTO 8'-6" HT.	180.00	SQ.FT.		
III	PARTLY GLAZED LOW HEIGHT PARTITION UPTO 4'-0" HT.	180.00	SQ.FT.		
IV	COUNTER FRONT GLASS	48.00	SQ.FT.		
B	<b>BLOCKED PARTITION</b>				
I	BLOCKED PARTITION UPTO 10'-6" HEIGHT NEAR STRONG ROOM	180.00	SQ.FT.		
3	<b>DOORS</b>				
A.	Flap Door	14.00	Sq.ft.		
B.	FULLY GLAZED ENT. DOOR 12 MM Glass:- 4'-0"x 8'-6"				
	Providing and fixing partly fixed / opened aluminum door shutters consisting of JINDAL or equivalent approved make powder coated aluminum section No. 4504 for door vertical styles, section No. 4541 for door bottom rail, section No. 4531 for middle / lock rail and section No. 4542 for rail weighing approx 0.976 Kg/m, 2.122 Kg/m, 0.989 Kg/m and 1.533 Kg/m respectively suspended / supported on the floor spring and pivot of EVERITE or	94.00	SQ.FT.		



	HARDWYN make only. 2 Nos. Approved quality aluminium handles and one 6 - lever GODREJ make six level mortise lock / night latch in each shutter . The measurements of shutter area only shall be measured and requisite door frame shall be measured as a part of partitions only. Powder coating of approved quality all complete.				
4.	CASH COUNTER:-				
	For customer as per layout with provision of 3'-9" high, 2'-6" deep with shelf for CPU and storage unit out of 18 mm thick commercial board with 1.00 mm thick laminate on all exposed surfaces with key board tray with telescopic slides. All edgings. Margin etc. out of polished steamed.	5.00	RFT.		
5.	OFFICER COUNTER				
	For customer as per layout with provision of 2'-6" high, 2'-6" deep with shelf for CPU and storage unit out of 18 mm thick commercial board with 1.00 mm thick laminate on all exposed surfaces. With key board tray with telescopic slides. All edgings. Margin etc. out of polished steamed.	31'-6"	Rft.		
	Manager Table:- 6' x 3' H = 2'-6"  Providing and fixing MANEGER'S TABLE 6'-0"x3'-0"x2'-6" (ht.) and 10mm beveled glass of approved make to be fitted on top obtain the total height of 2'-6" as per detailed drawing . made up of 19 mm commercial board of approved make the finished with 1 mm thick laminate of approved make and shade as approved as par detailed drawing. Table shall be provided with 3 drawers sliding on telescopic channels with proper locking arrangements and keyboard with telescope channels tabletop shall be finished with 1.0 mm thick laminate of approved shade & quality . The work includes provided and fixing locks , wire manager, spirit polishing of steam beach bending etc. complete in all respects to the entire satisfaction of the architect.	1 no.	each		





	Officer Table:- 5' -0"x 2'-6" H = 2'-6"	0.0	each		
	Officer Table:- 4' -6"x 2'-6" H = 2'-6"	0.	each		
6.	STORAGE				
	Providing and fixing Full height storage 400mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (color, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm block board and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / moldings duly polished all complete.				
	Low Height storage (2'-6" ht).	75.00	SQ.FT.		
	Full Height storage (7'-0" ht).	260.00	SQ.FT.		
	Almirah in Pantry	32.50	SQ.FT.		
7.	VOUCHER SORTING BOX				
	Providing and making <b>Voucher Sorting</b> box 1.5'x1'x(9" deep) as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plate pasted with metal adhesive. Rate shall includes all necessary hardwares and locking and side opening arrangements.	1 NO.	EACH		
8.	SUGGESTION BOX				
	Providing and making <b>Suggestion</b> box 1.5'x1'x(9" deep)as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plate pasted with metal adhesive. Rate shall includes all necessary hardwares and locking and side	1 NO.	EACH		



	opening arrangements.				
9.	Cheque deposit box				
	Providing and <b>making Cheque deposit</b> box 1.5'x1'x(9" deep) as per design & pattern with 19 mm ply finished exterior surface with 6 mm thick extra clear white painted glass having 4"x1" slots with 3 mm thick S.S. plat pasted with metal adhesive. Rate shall includes all necessary hardwares and locking and side opening arrangements.	1 NO.	EACH		
10.	VOUCHER WRITING TABLE 1'-3" TO 1'-6" WIDE AND LENGTH 5'-0"				
	Providing and Fixing wall mounted writing tables as per design. The base of the table shall be a frame of wooden members mounted on a wooden base. The top shall be of 1" comm. Ply finished in 1.5 mm laminate the edge of the top shall be provided with a wooden moulding ¾" x 3" finished in melamine.	1 NO.	EACH		
11	NOTICE BOARD (1200x900) Providing & fixing Notice Board the tag board of approved make & design, of size 4' X 3', with anodized aluminum boarder/frame type. The board should be 3/4" th. Strow board with belvet type fabric lining of aprpd. Colour.	1 NOS.	EACH		
12	METER BOX Providing and fixing Meter Box 400 mm deep made out of 19mm bwp block board finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 19mm BWP block board in the front cladded with 1.0mm laminate (color, vertical grain). sides to be made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19 mm block board and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / plywood's to be covered with wooden lapping / moldings duly polished all complete.	32.00	SQ.FT.		





Tender /Fur/Uco Bank/Oct-07/2022/2678-2020

19.10.2022

13	Aluminum Grill on ceiling of cash Cabin:-	50.00	SQ.FT.		
14	Door closer	5 nos	Each		
15.	MORTISE LOCK IN UPS ROOM AND MANAGER CABIN:- Providing and fixing in position DOORSET 6 liver cylindrical lock silver / brass finish as approved by the Bank for UPS room and .M. Cabin.	2 nos	Each		
13.	PANELLING ON WALL IN WOODEN WORK				
	Providing and fixing paneling on wall. Framing shall consist of Aluminum Section 50 mm x 40 mm (Wall Thickness 2 mm) @ 2'0" C/C. Both ways horizontally and vertically on the wall. This framing would be covered by ¼" thick. Ply and 12mm thick gypsum board.				
	1. Manager cabin 8'-6" Height	180.00	SQ.FT.		
	2. .Column Paneling	120.00	SQ.FT.		
	3. Paneling I Banking hall upto 4'-0" height	340.00	SQ.FT.		
	4. Cash cabin Paneling	100.00	SQ.FT.		
14	Vertical Blinds in Manager Cabin window	150.00	SQ.FT.		
	TOTAL OF INTERIOR WORKS			Rs.	



**Note:**

1. All glass works will be with itching & glass logo/as per brand manual and Architects instructions.
2. Steamed Anegre (equivalent to 366 of M/s Century) colour will be provided on Table top and facade of Counters and Partitions strips.
3. Sugar Maple )Equivalent to F1 1758 of M/s Formica) colour will be provided at Vertical faces of all Counter/Partitions along with façade of the Counter/Tables.
4. Goncalo Alvez (Equivalent to 1769 of M/s Sunmica )colour will be provided at Skirting for further clarification please seek incofrmation from banks circular dated 30.01.2015 bearing ref. no. HO/GAD/4524/2014-15.

Certified by: -

**(Ar. Manmeet Singh Bajaj)**

Regd. Architect.  
M/s Bajaj & Associates,  
Sophia Market, Court Road,  
Saharanpur.





**TENDER OF ELECTRICAL WORKS FOR UCO BANK PARTAPUR BRANCH DISTT. MEERUT.****2. ELECTRICAL WORKS:-**

SN O.	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Wiring for light points, fan points, bell points, sockets etc. with 1.5 Sq.mm PVC insulated, 1100 V grade grade copper conductor wires and 1.0 Sq mm copper earth wire and 1.0 Sq mm copper earth wire in concealed/surface using PVC (Heavy)25mm dia conduits, accessories such as bends, tees, saddles, draw boxes, mounting boxes, inner plates, cover plates, ceiling rose etc. (including chase cutting where where ever required) and chromium plated brass screws/rowel plugs etc.. The conduits to be laid in ceiling with proper clamps/wall/floor and filling the chase with cement mortar and finish the same in original form/wooden partition/above false ceiling with proper clamps (wherever required as per standard specification.				
	<b>NOTE:</b>				
	i) Each circuit shall have independent earth wire.				
	ii) Each point shall be earthed.				
	a) One light point controlled by one 6A modular one way switch. i/c wiring and complete with necessary items.	60 nos	each		
	b) A set of two light points controlled by one 6A modular one way switch. i/c wiring and complete with necessary items.	8 nos.	each		
	c) One Ceiling fan point with 6A 3 pin socket controlled by one 6A modular one way switch. The switch should be at switch board level I/C REGULATOR AND i/c wiring and complete with necessary items.	04 Nos.	each		
	d) One exhaust fan point with ceiling rose controlled by one 6A modular one way switch. i/c wiring and complete with necessary items.	2 no	each		
	[FOR ITEM NO. "a" TO "d" ALL MOUNTING BOXES, INNER PLATES, MODULES, COVER PLATES ETC. SHALL BE CRABTREE MEGA SERIES, PLATINUM RANGE MATERIAL (OR EQUIVALENT OF ABB/M.K.) ONLY] AND ALL WIRING AND CIRCUIT TAKEN FROM L.T. PANEL and . LT PANEL FIXED IN INFORT OF MAIN ENT. GATE OF BRANCH.				



2.	<b>POWER POINTS</b>				
	Same as serial no. 1, but wiring for 16A 6-Pin socket by using 4 sq mm PVC insulated 1100V grade copper conductor wire with independent 2.5 sqmm earth wire from D.B. to first 1st. Socket and 1st socket to 2nd Socket with 2.5 sqmm and 1.5 sqmm earth wire including providing and fixing of 16A 6-Pin socket with 16A switch				
	a) Power point with 4 sqmm copper i/c wiring and complete with necessary items.	15.00	EACH		
	FOR ITEM NO. "a" SHALL BE CRABTREE (OR EQUIVALENT OF ABB/M.K.) MAKE MODULAR/DOUBLE MODULE WITH ALL ACCESSORIES ONLY]]				
3	<b>A.C. POINTS:</b>				
	A.C. points i/c Box, MCB, Socket, Switch i/c 32 C MCB complete i/c wiring and complete with necessary items.	6.00	NOS.		
4.	<b>DISTRIBUTION BOARDS:</b>				
	Supplying, installation, testing and commissioning of DOUBLE DOOR type distribution boards ORIGINAL FACTORY FABRICATED ONLY) of following specifications:				
	<b>A) 4-WAY TPN DB (POWER &amp; AC DB)</b>				
	INCOMER :63A 4P	1 NO.	EACH		
	OUTGOING: 32A SP MCB-6Nos.				
	25A SP MCB-6 Nos.				
	(FOR SPLIT/WINDOW A.C. & POWER POINTS)				
	<b>B) 4-WAY TPN DB (LIGHT &amp; FAN DB)</b>				
	INCOMER :40A 4P. MCB-1No.	1 NO.	EACH		
	OUTGOING: 10A SP MCB-12Nos.				
	C) Supplying & Fixing of 1 no. 40A DP MCB in 4 way SPN DB ( FOR UPS OUT-PUT AT S/R)	1 NO.	EACH		
	D) 8-way SPN DB with 32A ELCB+D.P. 100mA sensitivity Controlling 6 nos. 10Amp. SP MCB and blanking plates. (FOR UPS OUT-PUT AT HALL)	2 NOS.	EACH		





5.	<b>MAIN PANEL</b>				
	A. ) Designing, manufacturing, installation, testing and commissioning of cubical type MAIL PANEL made from 16 SWG CRCA sheet steel, "I" type base M.S. Channel for grouting on floor complete with MCCBs, MCBs, Meters, C.T. etc. complete in all respect, insulated bus-bar with heat shrinkable PVC sleeve in suitable bus-bar chamber, wiring, name plates, danger plate, earth-bus etc.& comprising of compartments with hinged doors and rubber gasket, bus-bar chamber with bolted door and rubber gasket etc. The panel being of dust & vermin proof construction and to be painted with primer and smoke gray paint (minimum two coats) to look attractive. The panel should be comprising with the followings: Degree of Protection IP-54)	1 NO.	EACH		
	<b>INCOMER:</b>				
	100A HRC fuse base and bridge with HRC fuses Natural link for three phase four wire system- 1Set				
	100A, 25KA, 4P MCCB -----1 NO.				
	100A 4-P, ON LOAD change over switch-1no.				
	160A capacity aluminum bus-bar with heat shrinkable proper insulation with color coated.				
	Digital ammeter and voltmeter with selector switches.				
	R-Y-B phase indicators with 2A backup HRC fuse.				
	<b>OUTGOING:</b>				
	63A 4-P MCCB, 25KA,-----3Nos.				
	63A 4-P ON LOAD change over switch (FOR SYSTEM ROOM/ATM)-----1No.				
	40A 4-P MCCB, 25KA-----1 No.				
	32A TPN MCB, 25KA-----1No.				
6	Supplying, installation, testing and commissioning of following light fixtures, fans etc.				
	a) PHILIPS/WIPRO/C.G./HAVELLS Make light fixtures				



	i) S/F of LED 2 X2 Light fixture instead of equal Luminous Led light of Philips by the name of Green Square Led Luminaries on	24	NOS		
	ii.) Supplying & Fixing LED down light fittings with Philips or Crompton or Bajaj make	20	NOS		
	iii. S/F of LED 4' wide ( patti ) Light fixtures	16	NOS.		
	iv. S/F of LED 2' wide ( patti ) Light fixtures	01	NOS.		
	v. LED Strip Light (Cove Light)	150.00	Rft.		
	b) CROMPTON GREAVES make fans				
	i) 400mm SDX120 Wall Mounted fan.	14	NOS.		
	ii).Ceiling fan	04	Nos.		
	c) CROMPTON/GE-ALOSTHOM make				
	1. 12" Exhaust fans with clamps, bolt/dash fastener by grouting on wall for Toilets.	02	NOS		
<b>7</b>	<b>COMPUTER POINT</b>				
	a. Wiring with sx2.5 sqmm + 1x1/5 sq mm PVC insulated 1100 V grade multistranded copper conductor wires in 2 mm thick PVC conduit from UPSDB to computer point. Each point to have 3 nos 6A -5 Pin modular type sockets, one 6A indicator at below the top of table/counter and controlled by one 16A modular switch at above the table top in wooden partition with all accessories, inner/outer plates, metal box etc. and to be fixed on wooden partitions/by grouting on wall etc. as per the requirement at site.	10	nos		
	b. Cut out 100 Amp	04 nos.	Nos		
	c. UPS wiring for UPS including switch	100.00	Mtrs.		
<b>8</b>	<b>TELEPHONE POINT / DATA CABEL</b>				
a.	Supplying & laying of 25mm dia PVC conduit	250.00	mt.		
b.	Supplying & laying of CAT - 6e UTP cable .	300.00	mt.		
c	Supplying/Fixing patch cord 1 m. and 2 meter and I/O box complete	10 nos	Nos		





d	Supplying/Fixing Tray, Cable Manager and 9 U Rack and RJ Connector with fan and other necessary items  <u>Note:-</u> All products should be D-Link, Tp Link or equivalent International Quality.	01 nos	Nos		
e	<b>TELEPHONE POINT &amp; WIRING</b> Supply & fixing of GI / PVC box suitable for fixing of Telephone jack or 2 pin telephone socket as required with 2 pair of 0.63 mm Die annealed tinned copper conductor In PVC pipe for each telephone complete in all respect As per drawing and specification give by architect i/c wiring etc.	7 nos	Nos		
f	Supplying and Fixing of 1x16 -port switch for telephone wiring connections.	01	No.		
9	a) Providing and fixing of following earth station as per IS:3043, with water pouring pipes, GI funnels, masonry brick chamber with CI cover, including excavation & refilling of pit after filling with charcoal, salt and sand, identification of pit as required.				
	i) 600x600x3.15mm Copper Plate Earth Station.	2	No.		
	ii) 1x8SWG Copper earth wire in PVC conduit inside the Branch.	60.00	Rmt.		
	<b>TOTAL</b>			Rs.	

**Note:-**

1. **Final Amount in words filled in Tender will be considered .**  
No further discount written in numerical or words will be considered. After Tender has been filled. No condition or % of discount etc. will be considered which dictates re-calculation of any kind.
2. **GST Extra.**
3. **All switches will be modular switches.**
4. **Before filling tender please go through attached drawing for distance & other related quarries. We also advise Vendor to visit site physically if possible to determine actual work environment and difficulties.**
5. **All electrical fittings will be Modern as per latest circular, brand manual & actual sample photographs.**



Tender /Fur/Uco Bank/Oct-07/2022/2678-2020

19.10.2022

6. Any or all type of shifting or making adjustable to ensure proper working of existing branch plus to accommodate your working area, time and space so that branch working is not disturb.
7. That means shifting of electrical points, material, furniture at all will be done by you at no extra cost whoseever you are expected to understood branch before filling Tender.

*Certified by :*

**(Ar. Manmeet Singh Bajaj)**

Regd. Architect,  
**M/s Bajaj & Associates,**  
Sophia Market, Court Road,  
Saharanpur.





<b>AIR CONDITIONER WORKS UCO BANK PARTAPUR BRANCH, DISTT. MEERUT</b>					
S.no	Particulars	qty	Unit	Rate	Amount
1	Split AC 1.5 ton in Banking Hall & Manager Cabin :-  <u>copper make Five Star Rated invertor A.C.</u> <u>Make Voltas, Hitachi &amp; Blue star,</u> Complete with Outdoor Units, Indoor Units, Mounting Racks, Copper Insulated Tubing, Wiring, which is standard with equipment <b>Note:-</b> <b><u>Out of there three companies selection of brand will be at sole discretion of bank</u></b>	6	Nos.		
	Supply & Fixing with installation of stabilizer (having capability to work from 90 Volts) of copper wiring for Split and Cassette A.C.	6	Nos		
2	Supply/fixing of stand for external unit of A.C. for Split	06	nos		
3	Providing and fixing concealed copper pipe with wire proper insulation i/c cutting and repairing etc. for Split A.C.	350	Rft.		
4	Providing and Fixing Concealed Drain pipe with proper fixing & water proofing i/c cutting and repairing etc. for Split A.C.	250	Rft.		
	<b>TOTAL</b>				



Certified by :

**(Ar. Manmeet Singh Bajaj)**

Regd. Architect,

**M/s Bajaj & Associates,**

Sophia Market, Court Road,

Saharanpur.