

अंकवाZOV/यों एवं विP&D/2016-17/138

दिनांक/Date : 24.01.2017

निविदा सूचना/TENDER NOTICE

विनिर्दिष्ट के अनुसार वस्तुओं के दर हेतु मुहरबंद निविदाये आमंत्रित हैं/ Sealed items rate tenders are invited for the works noted hereunder :

क्र. स. /S.N	कार्य का विवरण/Name of work	कार्य-स्थल/Location of work	अनुमानित लागत/Estimated Cost
1	शाखा फतेहपुरमाफ़ी जनपद इलाहाबाद में आंतरिक साज-सज्जा का कार्य/ interior & furniture work at Fatehpurmafi branch Distt Allahabad	शाखा फतेहपुरमाफ़ी जनपद इलाहाबाद Fatehpurmafi branch Distt Allahabad	Rs 397800/-
2	शाखा फतेहपुरमाफ़ी जनपद इलाहाबाद में विदुअत कार्य/ Electrical work at Fatehpurmafi branch Distt Allahabad	शाखा फतेहपुरमाफ़ी जनपद इलाहाबाद/Fatehpurmafi branch Distt Allahabad	Rs 154900/-

निबंधन एवं शर्तें/ Terms and Conditions :

- कार्य की पूर्ति हेतु समय : 30 दिन / Time of completion of work : 30 days.
- अर्नेस्ट मनी डिपोजिट : निविदा जमा करने के समय पे आईर/ डी डी / बैंकर्स चेक के रूप में अनुमानित लागत का 1% / Earnest Money Deposit : 1% of estimated value at the time of submission of tender in the form of pay order/DD/Banker's cheque.
- आरंभिक अभिरक्षा जमाराशि : सफल बोली लगाने वाले की अर्नेस्ट डिपोजिट मनी को शामिल करते हुए अनुबंधित राशी का 2% / initial security deposit : 2% of the contract value including the EMD by successful bidder.
- सफल बोली लगाने वाले के द्वारा अर्नेस्ट मनी डिपोजिट एवं आरंभिक अभिरक्षा जमा राशी, अनुबंध की अभिरक्षा राशी व रिटेंशन मनी के एवज में समायोजित कर ली जाएगी / The EMD and ISD so deposited by the successful bidder, will be adjusted with the security deposit/ retention money for the contract.
- क्षतिपूर्ति वहन अवधि : कार्य के वास्तविक समापन से छः माह की अवधि तक / Defects liability period : 6 months from date of virtual completion of work.
- निविदा के जमा करने का अंतिम समय एवं तिथि : 03.02.2017 को अपराह्न 2.00 बजे/ Time and last date of submission of tenders : 2:00PM on 03.02.2017
- निविदा खोलने का अंतिम समय एवं तिथि : 03.02.2017 अपराह्न 4:00 बजे/ Time and last date of opening the tenders : 4:00PM on 03.02.2017.
- जमा करने का स्थान / Place of submission : यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010
UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi - 221010
- बिना कोई कारण बताये किसी व सभी निविदाओं को स्थगित करने व निरस्त करने का अपना अधिकार बैंक के पास सुरक्षित है। सभी निविदाये, जिसमे निर्दिष्ट कोई शर्त पूरी नहीं है या किसी भी रूप में अपूर्ण है, निरास्त की जा सकती है / Bank reserves its right to postpone/ reject any or all the tenders without assigning any reason what so ever. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- सेवा कर नियमानुसार लगे होगा / Service tax applicable as per norms.
- केवल सूचीबद्ध कॉन्ट्रैक्टर्स ही सम्बिदा प्रस्तुत करे /Only empaneled contractors can submit tenders.

अंचल प्रबंधक / Zonal Manager

यूको बैंक, अंचल कार्यालय, डी-63/8-1-एम, मौज़ा - तुलसीपुर, महमूरगंज, वाराणसी - 221010

UCO Bank, Zonal Office, D- 63/8-1-M, Mauza - Tulsipur, Mahmoorganj, Varanasi - 221010

Phone: 0542-2221723, 2223323, Fax - 0542- 2223123

e-mail: zo.varanasi@ucobank.co.in

**Detailed Estimate / Schedule Of Quantity of furnishing work of UCO BANK FATEHPUR
MAFI BRANCH.**

S.No	Item's of Work	Qty.	Unit.	Rate.	Amount (Rs.)
1.	P/F Low height wooden Manager Cabin partly glazed/laminated wooden partition made out of sal wood well seasoned structure with a cost of antitermite treatment upto 3'-0" ht. framing of inside area with 2"x 2" sal wood section 2'-0" c/c horizontal and vertical both side 6mm thk ply & 1.0mm thick laminates both side & middle portion 6mm thk. Etching glass with teak wood beeding, liping/ moulded complete in all respect.	160.0	Sft		
2.	P/F Low height / Full Height partition / Wicket gate all specification as item No.4	70.0	Sft		
3.	Providing and fixing in position double leaf powder coated Aluminum entrance door made of 14 gauge thick sheet. All member shall be of 4"x1-3/4" section and bottom rail shall be of 5"x1-3/4" section with 6mm thick clear sheet glass including 4" dia 2 Nos handles 10" long 2 Nos, Tower bolts, floor spring 2 Nos lock etc. complete.	110.00	Sft		
4.	Providing and fixing Writing desk in position box type Wooden writing in public space of approximate size 4'-0" x 2'-0" made out of 19mm thick good approved quality ply with 6" to 9" wide pigeon hole type compartments in the front facade boxing for keeping pay-in-slip, book literature etc. These Writing table's must have laminates 1.0mm thick on top writing desk and two sides of the Boxes. With beeding, lipping, moulding and painting /polishing complete.	1.00	No.		
5.	Providing and fixing in position Notice boards of approximate size 3'-0"x2'-0" and 6" deep made out of 19mm thick ply with fully glazed shutter in front and soft board with felt cloth lining at the back inclusive of good approved quality lock to this shutter, hinges, fixtures,	1.0	No.		

(2)

	handle etc. and front laminate /painted complete as directed by bank architect.				
6.	Providing and fixing of Check Drop box size 1'-3" x 1'-6" with all specification as per item No.8.	2.0	No.		
7.	P/F of Godrej mortic lock	N/A			
8.	P/F of Godrej Night latch.	2.0	No.		
9.	P/F of Door closer I.S.I mark	2.0	No.		
10.	Providing and fixing Column/Wall paneling paneling all specification as per item no.4.	60.0	Sft		
11.	Providing & fixing wooden Filling Cabinet 1'-6" deep to be fixed on the wall frame made out of 19mm thick commercial ply with siding hinge shutters made out of 12mm thick ply with 1.5mm laminate on the front & side other internal surface to be painted as complete with handle, lock, wall catches etc.	70.0	Sft		
12.	Providing and placing in position Side Units made out of 19mm board with 1.0mm laminate with slidding hinged shutters (made out of 12mm thick ply with 1.0mm thick laminate on it) complete with handles etc. size 4'-0"x1'-6"x2'-6"	1.0	No.		
13.	Providing and fixing Vitrified tiled flooring 1 st quality polished 24"x24" with 4"skirting of Johnson /Bell/Naveen Ceramics or equivalent make fixing in cement sand ratio 1:5 in line and level inclusive of wastage, cutting and joints filling with white cement skirting to be flush with POP with 6mm groove between POP and skirting Johnson- Atlanta(Bell Tiles type MGCL 44). Including cleaning complete as directed by the Architect.	1208.0	Sft		
14.	Providing and placing in position Branch Manager Table made out of 19mm thk .Board with 1.0mm Thick laminate on top sides and front (other surface Shall be polished or painted with teak wood beading on edges. Drawer unit T.W. lipping etc. also including multi purpose Godrej locks, wooden handles, foot rest, ball catchers etc. complete all as/ design(size 5'-6"x3'-3"x2'-6") i) Officers Table Size (4'-6 x3'-0"x2'-6")	1.0 N/A	No.		
15.	P&F Vertical Venetian blinds made out of	100.0	Sft		

(3)

	100mm wide strips as/ shade approved including supports, etc. complete.				
16.	Providing & applying Birla white putty of Superfine grade, average thickness 5mm on plastered wall, level pads to be made before application to be done with aluminium pipe section, (Only in Banking Hall)	2850.0	Sft		
17.	Providing and fixing P.O.P Cornice 4" thick at wall corner (Design / shade approved by the bank architect) complete.	180.0	Sft		
18.	Painting of walls and ceiling in stationary room, safe room , toilet & record room with oil bound distemper two coats over primer coat As/shade approved to the satisfaction of the Bank/ Architect. Painting of steel and wooden surfaces of doors and windows in baking hall with enamel paint (two coats) over primer coat As/shade approved to the satisfaction of the Bank/Architect.	1291.0	Sft		
19.	Providing /applying Distemper Plastic Paint two or more coats, with approved colour, Brand and manufacture of reqd. shade on under coated wall surface to give an even shade over & including a priming coat with cement primer of approved brand and manufacture such as Berger, Asian, Nerolac distemper after the priming coat has been applied And perfectly died. All holes, scratches if Any shall be required as mentioned in Preparations of surface and then first Coat of distemper applied and allowed to Dry then second coat distemper shall be Applied. Work completed up to the bank satisfaction.	4518.0	Sft		
23	P/F suspended False Ceiling Gyp Board with G.I. Perimeter channels G.I. Intermediate Channels Etc. properly suspended from ceiling with Nylon /G.I. strips sleeves and Screws 12.5Mm tapered edge Gyp board (confirming To I.S.2095-1982) ceiling tiles to be screw Fixed to the ceiling section with 25mm dry Wall screw mechanically at 230C/C and Finished with jointing compound paper tape And two coars of primer and two coats of plastic paint complete as per design Including perimeter channels required for Light fitting cut out Grill diffusers etc (Only ATM Room)	70.0	Sft		
24	Providing and fixing Glass Main Door at the entrance door (approx.size 3'-6"x7') made out of Sal wood with top and middle runner	24.50	Sft		

(4)

	Of section size 4" X 1.5" while bottom Runner to be of 6"x1.5" size. The two vertical members shall be of 4"x1.5" section. The frame shall be covered with 4mm ply And 1.0 mm laminate. The glass shall be 8 mm th. Clear plain glass with anti shatter film fixed on it The door shall be fixed to floor on a floor spring. The work to include providing and fixing of Floor Spring & Handle – 2 nos.)				
25	Providing and fixing External Fixed Glazing made out of Sal wood with top runner of section size 4"x 1.5" while bottom runner to be of 6"x 1.5" size. The two vertical members shall be of 4"x 1.5" section. The frame shall be covered with 4 mm ply & 1 mm the laminate. The glass shall be 8 mm th clear plain glass with anti-shatter film fixed on it.	30.0	Sft		
26	Providing and fixing Card Access Pillar of size 6"x 6" (Out-out) dimension comprising of 12mm ply, finished with 1.0 mm laminate appropriate slot to be made for card access unit. Unit – nos.	1.0	No.		
27	P/ F wooden Cabinet 9" deep to be fixed on the wall frame made out of 19mm thick commercial ply with hinge shutters made out of 12mm thick ply with 1.0mm laminate on the front & side other internal surface to be painted as complete with handle, lock, Magnet etc. size 1'-9" x 2'-3" x 9"	5.0	Sft		
28	Providing and fixing wooden shutter boxing comprising of 2"x 2" sal wood frame work, 12mm marine plywood, trap door with sal wood lipping patti, flush tower bolt on trap door, shutter boxing finished with 1.0mm thk. Laminate fixed over it. The mode of measurement shall be of total running ft. Size (12'x1'x 2')	12.0	Rft		
29	Providing and fixing of Voucher stand made by PVC in vertical dimension	1.0	No.		
			Total	Rs.	

Add:S.T.@6.0%

Rs.

(5)

List of approved materials

Sl. No.	Materials	Approved manufacturers / suppliers
1.	Paint	I.C.I. (Dulex - Duco) / Asian paints / Goodlac Nerolac
2.	Plywood	Century plywood (BWR Grade)/ Green ply (BWR grade), Corbett (BWR grade)
3.	Wood preservative	Sal Wood
4.	False ceiling	Armstrong , Indian gypsum board
5.	Laminates	Greenlam, Century Mica, Marino
6.	Screws	G.K.W./Nettle fold
7.	Adhesive	Fevicol SH
8.	Night latch	Godrej
9	Locks	Godrej
10	Aluminium door frame	Jindal
11	Glass	Modi/Asahi/Saint Gobain
12	Aluminium cladding	Eurobond/Altobond/Alukbond
13	Key board drawer	EBCO
14	Telescopic CPU stand	EBCO
15	Cable organiser (wire manager)	EBCO
16	Vitrified tiles	Jhonsions Perlato
17	Venetion blind	Vista, Luxa flex

Note : Plywood mentioned in the drawings as well as in bill of quantities should be MR Grade only.

(6)

Detailed Estimate / Schedule Of Quantity of Electricals work of **UCO BANK
FATEHPUR MAFI BRANCH.**

S.No. Item's of work Amount(Rs)	Qty	Unit	Rate
1. Providing & fixing tube light fitting with tube, frame, choke,starter etc. of Philips.			
A) A) 2x40 watts mirror optics light for hanging Philips make (Catalogue No.TCS605/236 HPF- 2xTLD 36watt /TL40 watt -white) with Electronic Choke along with lamps as Per drawing.	10.0	Nos.	
B) Providing & fixing (Philips make) recessed mounting luminaries mirror optic fitting (CAT- No: 300/236 P5 – 2x PL-L 36W) along with 2 No 36 Watt PL-L lamp and attachment as per drawing.	1.0	Nos.	
C) Providing & fixing of 1x18 watt Down light fitting (Philips Make) along with 1x18Watt holder type CFL as per drawing.	4.0	Nos.	
2. Providing & fixing of Ceiling Fan 48” Crompton/polar / Usha make white . Including fan regulator.	6.0	Nos.	1
3. S/F A.C. Box(Hevell,s(MDS with earth metal clad(20Amps, MCB concealed in walls.)in cluding 2x6sqm+1x1.5sqm Multi standard copper wire in suitable size PVC conduit A.C. Box to main panel	4.0	Nos.	
4. P/F of point wiring 5Amp controlling switch modular type, including 1.5sqmx2 +1x1sqm multy stand red PVC insulated copper wire in suitable size PVC conduit & M.S box plate etc.	45.0	Nos.	

(2)

5. S/F 15Amp switch & 15 amp Socket including 2x2.5sqm +1x1sqm Multi standard copper wire in suitable size PVC conduit & M.S box front plate etc.	3.0	Nos.	
6. S/F 3 No. 5 Amp socket & 3No controlling switch including M.S box cover plate & top plate, 2x1.5sqm+1x1sqm multy stand Wire in suitable size PVC conduit. & separately provide 1.0 No 5 Amp switch & socket.	7.0	Nos.	
7. Supply & drawing two pair Telephone cable			

(7)

in suitable size PVC conduit with RJ -11 telephone jack in suitable enclosure	1.0	Nos.
8. Providing & installation of 6way SPN D.B. of Havell's MDS make with provision for incoming & outgoing connection and 5/20 Amp. Single pole NCB (6Nos)	1.0	Nos.
9. Providing & fixing of 32Amp.SPN including Board etc. as required at site (for U.P.S.)	1.0	Nos.
10. Supply & fixing 100Amp TPN main switch havells/ L & T make.	1.0	No.
11. Supply & fixing Change over 63Amp 4 pole SFU side handle type along with angle iron nut bolt with suitable size connection wire, LUGS extra Havells/ L & T make.	1.0	No.
12. Earthing 600x600x3mm copper plate earthing stations with earthing resistance less than 2 Ohm including watering,PVC/G.I. Pipe with funnel, excavation till 8'-0" deep or as instructed by the Architect , back filling with compaction, 2Nos. copper flats 25x3mm conn. Earthing copper wire in PVC conduit pipe from Earthing pit to Electric main board complete in all respect.	1.0	No.

(3)

13.S/Laying 2x2.5sqm +1x1sqm multi standard copper wire Circuit wire in suitable size PVC conduit for light point circuit MCB D.B to switch board 2.5sqm wire	4.0	Nos
14.Supply & fixing 63Amp copper Bus Bar TPN	1.0	No.
15. P/F main board with angle iron frame	1.0	No.
16. 32 Amp Change Over Double Pole for UPS	1.00	Nos
17. S/F of 400 mm sweep wall mounted fan CG/ KHAITAN.	2.0	NOS.
18. P/F cutout 100Amp.	3.0	Nos.
19. Call bell point with call bell in Manager Cabin	1.0	NOS

(8)

20. S/F of cash cabin light with CFL.	4.0	NOS.
22. S/F 40 watt tube light fitting along with 1x40 watt tube light connection wire testing etc.	12.0	Nos.
23. S/Laying 25sqm x4core unarmored cable branch main panel to main electric pole with 12swg G.I wire continue panel to pole	42.0	Mtr.
24. Supplying and drawing lan cable cat - 6 d-link or eqv make by 19mm pvc pipe fully concealed.	100.0	Rmt
25. Termination of lan cable in one end with RJ 45 computer jack of MK,Roma or Crab- tree make in suitable enclosures	7.0	NOS.
26. Termination of land cable in other end with RJ 45 socket	7.0	NOS.

1,54,835.00

Total Rs.

(4)

Add:S.T.@6.0%

Rs.

Note :- First of all Branch Old Electrical to be used there after new material used in branch premises as per requirement.

(10)

SPECIFICATIONS OF ELECTRICAL MATERIALS

<i>S.No.</i>	<i>Item</i>	<i>Make/ Specifications</i>
1.	FITTING	Philips & GE
2.	WIRE	Anchor, Havells, Finolex
3.	SWITCHES	Roma, M.K., Crabe Tee-Havells
4.	MCCB	Havells , L&T
5.	MCB DB	Havells, L&T
6.	Main Switch	HPL, L&T,
7.	Changeover	Havells , L&T,
8.	PVC Pipe	AKG, Plaza. 2mm thick
9.	Wall Fan	Anchor, Crompton, Havells
10.	Ceiling Fan	Anchor, Crompton, Havells
11.	Exhaust fan	Usha; Khaitan, Crompton.
12.	Cable	Gloster, Havells, National, Railisons.
13.	Telephone Wire	Delton, Anchor.

(12)

14.	Cat- 6 Cable	D - Link
15.	IO - Box	D - Link
16.	MCB	Havells, L&T
17.	CFL	Philips (Only)
18.	MS Pipe	AKG, MK,

Associates Bharat &