

TENDER DOCUMENT FOR FURNISHING OF EXISTING BRANCH PREMISES FOR UCO BANK, BRANCH OFFICE : CIVIL LINES, BAREILLY (U.P.).

Item No	Description	Qty.	UNIT	Rate	Amount
1	<u>STANDARD RUNNING COUNTERS</u> Providing, fabricating and fixing at site and in position modern Clerical/Cashiers Counters as per enclosed detailed drawing consisting of 19mm thick ARCHID, KANCHAN, LIBERTY or equivalent approved make commercial finished borer and termite resistant block board having 10 to 15" wide transacting top at 42" height and 30" wide writing/work top at 30" height from the finished floor level. The work top shall be supported by the drawer unit of stand-ard size housing 4" to 5" deep drawer for clerical counter and 3 nos. 8" deep drawers in Cash Counters running on approved make Channels as directed by Bank, placed at every 3.6" to 4'0" for CLERICAL COUNTERS and every 4'-0" for CASH COUNTERS or as per approved layout plan and consisting of 19 mm thick commercial finished block board of above specified makes. The frontside (Public side) of the counters shall be consisting of 19mm block board of approved makes for entire and length of the coun-ter. The transaction top, writing/work top and front/public side face of the counter and front face of the drawer cum cupboard unit shall be finished with White/Cream Cedar/Pear Tree Wood				
	(a) Cash counters	10	RFT		
	(b) Clerical counters	17.58	RFT		
2	Supply & Fixing of 12 mm glass with etching (design as per Architect) in wooden pillar with polish all complete.	82.5	SQFT		
3	<u>FLUSH DOOR SHUTTER WITH GLASS IN UPPER PORTION</u> Providing and fixing 40 mm thick solidcore flush Door shutters of ARCHID / KANCHAN / KANCHAN or equivalent ISI make as per sample approved by the Bank finished with approved quality and shade 1.0 mm thick lamination on both side of the shutter with matching wood beading duly melamine polished. The rate should include the following:- (i) Providing 8 mm thick float glass of 3' to 4' height fixed at 3' above the floor level with suitable beadings. (ii) Providing 4" high skirting with 1.0 mm sunmica lamination on both sides and TW lipping to edges.				



Item No	Description	Qty.	UNIT	Rate	Amount
---------	-------------	------	------	------	--------

(iii) Applying anti-termite/boarer treatment/paint to door shutter wherever directed.

(iv) Providing 4Nos -4"x1.5" Brass Oxidised Hinges, anodised aluminium Handles, tower bolt, etc. as per samples approved and as per site requirements.

63 SQFT

4 **TABLES**

Providing in position Officer's tables of sizes mentioned hereinafter. It shall consist of 19 mm thick commercial block board of ARCHID / KANCHAN or equivalent approved make on the top finished with 1.00mm thick approved quality lamination as per sample approved and as per design/detail. The writing top shall be supported over two vertical supports made out of 19 mm thick commercial board of above specified makes with lamination as above. The supports shall be connected together with 19 mm thick commercial board duly laminated front as per approval and design / detail. The table shall be complete with drawers, shelves, necessary hardware, knobs, Godrej locks etc. as per detailed drawing and samples approved. The rate to include applying 3 coats of melamine spray polishing /painting etc., plastic shoes complete.

(i) Table of size 6'-0" x 3'-0"x2'-6" height with Table top and front to be in semi-circular shape as per detailed drawing with 12mm thick tinted Glass top.

1 NOS.

(ii) Table of size 5'-0"x2'-6"x2'-6" ht. as per detailed drawing.

4 NOS.

(iii) Table of size 4'-6"x2'-6"x2'-6" ht. as per detailed drawing.

NOS.

5 **SIDE TABLES**



Item No	Description	Qty.	UNIT	Rate	Amount
---------	-------------	------	------	------	--------

Providing and fixing in position side tables of sizes mentioned hereinafter. It shall consist of 19mm thick commercial board of KANCHAN / ARCHID or equivalent approved make in top, middle shelf, bottom and sides as per detailed drawing. The top and sides shall be laminated with 1 mm thick approved quality and shade laminate as per design detail. The cabinet shall be covered from back with 6 mm ply of ARCHID / KANCHAN or equivalent approved make. The rate should include for providing 19 mm laminated block board shutters and necessary hardware, knobs sliding channels, Godrej locks etc. as per samples approved complete with applying 3 coats of melamine polishing / painting to un-laminated surface inside / outside, plastic shoes and also providing and fixing 19x4mm suitable teak wood/ inlay beading to all exposed edges to the block boards etc. as per Bank's approval.

- | | | |
|---|-----|------|
| a) Side rack of size 4'-0"x1'6"x2'-4" for B.M. | 1 | NOS. |
| b) Side rack of size 3'-0"x1'6"x2'-4" for B.M. | 2 | NOS. |
| c) Side rack of size 15'x1'6"x9' , 10'x1'6"x9'X2 for other c
Officer | 315 | SQFT |

6 **SOFA SET**

Providing and fixing sofa made out of 19 mm thick Duro / Swastik/ Green block board and 2" x 2" seasoned wood frame. The seat shall have flat tensile spring, hessian base and 4" pin hole ISI grade rubber foam pin-hole cushions of Prestige or equivalent approved make with 1"-37 density foam. The Back shall have 3"- 37 density U-foam. Sofa shall be upholstered with tapestry upto Rs. 150/-per mt.as per sample and colour / shade approved by the Bank's authorities.

THREE SEATER

NOS.

TWO SEATER

NOS.

7 **FALSE CEILING with GI frame & Gyp Sheets**



Item No	Description	Qty.	UNIT	Rate	Amount
	<p>Providing and fixing suspended false ceiling which includes providing and fixing G.I. channels -MF6A of size 27x0.5 mm thick having one flange of 20 mm and another flange of 30 mm fixed along periphery of the ceiling, screws fixed to brick wall/partition with the help of rawal plugs. The suspending G.I. Intermediate channels -MF 7 of size 45mmx0.9mm with two flanges of 15mm each from The soffit at 1200mm centre in one direction with steel G.I. strap hanger-MF8 of width 25 mm x 0.5 mm thick fixed to soffit with G.I. cleat P534 and steel expansion fasteners. The ceiling G.I. section of 0.5 mm thickness forming hollow knurled wedge of 51.5 mm and two flanges of 26mm each with lips of 10.5 mm are then fixed to the intermediate channels with the help of connecting G.I. clips -MF9 dia 2.64 mm and in direction perpendicular to the intermediate channels at 450mm centre to centre. Tapered edge Gypsum (12.5 mm will be serew find front/public side face of the counter and front face of the drawer cum cupboard unit shall be finished with White/Cream Cedar/Pear Tree Wood Grain lamination as per sample approved by Bank. The public side of the counter shall be provided with 19 mm thick laminated blockboard skirting 100mm height. The rate should include providing and fixing seasoned t.w. beading of finished size 19mm x 4 mm or as required to all exposed edges of the block board. Each cupboard/ drawer shall be provided with approved quality 1no. handles/knobs and 1no. GODREJ or equivalent approved quality cupboard locks. All exposed and unexposed</p>	1535	SQFT		
8	<p><u>MORTISE LOCK</u> Providing and fixing in position DOORSET 6 lever cylindrical lock silver/brass finish as approved by the Bank.</p>	4	NOS.		
9	<p><u>VOUCHER WRITING TABLE</u> Providing and fixing Voucher writing table with about 5 voucher slots/pockets as per the detail drawing consisting of 19mm block board of ARCHID /GREEN/ KANCHAN or equivalent approved makes duly laminated using 1.0 mm laminate of GREEN/ROYAL TOUCH or equivalent approved by the Bank having slanting top and waste paper box with dumping and cleaning window in the lower supporting column including polishing/enamel painting etc. complete.</p>	1	NOS.		



Item No	Description	Qty.	UNIT	Rate	Amount
10	<u>SOFA /SETTEE SIDE TABLES</u> Providing and fixing in position side table of size given below made out of 19mm thick specified make commercial block board finished with 1.00mm laminate on sides complete as per detailed drawing including providing 19mm approved colour profiled/bevelled edge machine polished granite stone on the top, polishing of TW lipping etc.. (a) 1'6"x3.0'x1'6" ht.	1	NOS.		
11	<u>M.S. G. I. GLAZED & PANELLED PARTITIONS (FLUSH TYPE) with M. S. frame work</u> Providing and fixing partitions made out of 45 mm x 45 mm G.I.Channel Frame @ 1' 6" c/c horizontally and 2' c/c vertically with Water proof and anti termite 8 mm exterior grade MDF Make : Action Tesa with 1.00mm approved quality and shade lamination with Teak wood moulded beading on both side duly melamine polished. The partition will be provided with 8 mm thick float glass of 4' height fixed at 3' above the floor level in average 3' wide panels. The rate should also include providing 4" high skirting of 12mm BWP ply with 1mm aica lamination on both side including applying anti-termite /boarer paint to wooden framework wherever directed.	630	SQFT		
12	<u>LOW HEIGHT WOODEN PARTITIONS</u> Providing and fixing in position low height M.S.partition as per item no. ... above upto 4 ft height but upper 10/12" portion of partition will have 8mm thick plain or tinted float glass of MODI/TRIVENI with etching and remaining lower portion to be panelled with 8mm thick Action Tesa MDF Board duly fixed with suitable beading. The top of the Partition shall be provided moulded beading made out of 65x25mm	109	SQFT.		
13	<u>PLANTER BOX</u> Supplying Planter box consisting of 19mm commercial board 15"x15" finished with 1.00mm laminate from outside and including polishing etc.all complete.		NOS.		
14	<u>NOTICE BOARD</u> 2'-0"x4'-0" all complete same as item no.1	1	NOS.		
15	<u>ALUMINIUM DOOR SHUTTER WITH GLASS</u> Providing and fixing partly fixed/opens				



Item No	Description	Qty.	UNIT	Rate	Amount
	aluminium door shutters consisting of JINDAL or equivalent approved make Powder coated aluminium section no. 4504 for door vertical styles, section no. 4541 for door bottom rail, section no. 4531 for middle/ lock rail and section no. 4542 for top rail weighing approx. 0.976 Kg/m, 2.122 Kg/m, 0.989 Kg/m and 1.533 Kg/m respectively suspended /supported on the floor spring and pivot of EVERITE or HARDWYN make only, 2 nos. approved quality aluminium handles and one 6-lever Godrej make six lever mortice lock/night latch in each shutter. The measurements of shutter area only shall be measured and requisite door frame shall be measured as a part of partition only. powder coating of approved quality all complete.	60	SQFT		
16	<u>DOOR CLOSER</u> Providing & fixing door closer of EVERITE as equivalent make all complete.	4	NOS.		
17	<u>WALL PANELLING</u> Approved quality M.S. G.I. frame work made out of 2"x1" sections placed at 15 to 18" centre to centre firmly fixed to wall covered with 8 mm MDF Board of Make Action Tesa / Merino Finished with 1.0mm thick approved quality and shade lamination in approved pattern and design including providing T.W. moulded beading at top ends or as directed, polishing etc. complete.	235	SQFT.		
18	<u>SUGGESTION BOX</u> 9"x1"x5" all complete same as item no.1	1	NOS.		
19	<u>METER BOX</u> Providing and fixing 2'x3'x8" consisting of 19mm commercial board finished with 1.00mm laminate from outside and including polishing etc. all complete.		NOS.		
20	<u>CHEQUE DROP BOX</u> 9"x1"x5" all complete same as item no.1		NOS.		
21	<u>NIGHT LATCH LOCK</u> Providing and fixing in Cash Cavin Door all complete	2	NOS.		
22	<u>FLOORING</u>				



Item No	Description	Qty.	UNIT	Rate	Amount
	P/L Vitrified floor tiles (Jointless) of standard manufactured in 24" x 24" size (thickness to be 10mm with water absorptions less than 1% and flexural strength not less 30N/sqmm in all colours and shade, laid on 20mm thick cement mortar 1:4 (1 cement :4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete including supply of material labour T & P required for the proper completion of the work.	1891	SQFT.		
<u>PAINTING</u>					
23	Painting on walls and ceiling with plastic emulsion paint after preparing the surface. Complete in all respect with two or more coats.	2840	SQFT.		
24	Painting with enamel paint after cleaning treating the surface with suitable primer over steel work such as window grill, channel shutter etc.	345	SQFT.		
25	Painting of external wall with APEX Paint	220	SQFT.		
26	Providing and fixing M.S.Gate	33	SQFT.		
27	Providing and fixing SS Three Seater Chair	3	NOS.		
28	Providing and fixing SS Two Seater Chair	1	NOS.		
29	Civil Miscellaneous Work.		Lump-sum		

TOTAL Rs.

Note:- 1-Please Quote Item Rates Separately Word & Figure.
2-Please Quote GST Separately on total cost.
3-This tender document is inclusive of all taxes, transportation & etc., only GST will be paid separately.



**Zonal Manager
UCO Bank
Zonal Office Meerut**

UCO Bank Civil Lines Bareilly					
BOQ - ELECTRICAL WORKS AT UCO Bank Existing Branch Premises, Civil Lines Branch, Bareilly					
S.NO.	DESCRIPTION OF ITEM	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Installation of 200Amp Kit kat Fuse unit 3 nos with 200 Amp neutral link on wooden board (3feet x 3feet') complete with connections (new).	1	Set		
2	<p>ELECTRICAL PANEL Design, manufacture, providing, storing & installing in position, effecting proper connection, testing and commissioning of panel made of 16 SWG, CRCA sheet steel. It shall be dust and vermin proof. It shall have compartmentalized construction with bus bar chambers, cable alley, cable glands plate etc. as required, duly painted from inside as well outside. It shall have the following -</p> <p>MAIN PANEL. Incomer : 1 No. 125 Amp. TPN, MCCB (18 KA breaking capacity), Busbars, (100 Amp, 3 phase, 4 strips, 415 volts, 50 Hz. copper busbars with colour coded PVC heat shrinkable sleeves.) Instruments. Multi function Meter for Voltage, Ampere, Power factor, KWH, Data 1 No. Outgoing : 6 Nos. 63 Amp. TP, MCB (For LDB, PDB, Branch UPS DB, ATM UPS DB and Spare Feeder) 1 No., 125 Amp. Four Pole Change Over for D.G. Set. Seperate from the panel, The design of panel should be got approved by the Architect before manufacturing. The job shall be completed, to the satisfaction of the Bank Engineer/Architect.</p>	1	Nos.		
3	UPS I/P, O/P AND DISTRIBUTION				
a.	20/32 AMP Metal industrial socket along with MCB for UPS I/P and O/P	2	Nos.		
b.	12 WAY SPN DB Double Door (1 No. 40 AMP DP MCB and 10 NOS. 6-10 AMP SPMCB) (Branch UPS power Distribution)	1	No.		
c.	SITC of 63 Amp TP MCB in M.S. Encloser complete in all respects as required. (Branch UPS)	1	No.		
e.	SITC of 63Amp Rotary Phase selector switch complete with RYB indication fitted in M.S. encloser complete in all respects as required. (Branch UPS)	1	Nos.		
4	RAW POWER & FAN, LIGHTING DB & AC DISTRIBUTION				
a.	4 WAY TPN DB Double Door Concealed in wall (1 No. 63 AMP TP MCB and 12 NOS. 6-32 AMP. SPMCB) (1 DB for Raw Power & 1 DB for Light + Fan) all complete with blanking plates.	2	Nos.		
b.	4 WAY TPN DB Double Door Concealed in wall (1 No. 63 AMP FP MCB and 9 NOS. 16-32 AMP. SPMCB) (For Branch AC) all complete with blanking plates	1	Nos.		
S.NO.	DESCRIPTION OF ITEM	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
5	CABLES				
a.	4 X 4.0 Sq.mm Copper Wire + 1X 2.50 Sqmm copper earth wire in PVC Pipe fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete (Panel to UPS Incomer, LDB, PDB)	185	Mtr.		
b.	Same as above but 4 x 10.0Sqmm + 1 x 4.0 Sqmm Copper Counductor Cable. (Kit Kat fuse unit to AC DB) complete with CU lugs at both ends.	8	Mtr.		
c.	2 X 4.0 Sq.mm Copper Wire (ROTARY SWITCH TO UPS TO UPS DB) + 1X 2.5 Sqmm copper earth wire in PVC Pipe fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. Compete	15	Mtr.		
d.	2 X 2.5 Sq.mm Copper Wire (Electric Panel to ATM Light Board & Glow Sign Board) + 1X 1.5 Sqmm copper earth wire in PVC Pipe fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete with lugs		Mtr.		
6	AC (Split) POINT				



a.	Point Wiring with 2 No. 4.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & 32 Amp. Metallic plug & Socket DB complete in all respect as required by the Bank (for 1.5 Tr AC)	7	Nos.		
7	EARTHING				
a.	PIP technology GEL type 500mm dia 3000mm long earth electro. (One Dedicated Earthing for UPS, One for Body earthing and one for neutral.)	3	Nos.		
b.	12 SWG Bare Copper Earth Wire from earthing pit /Earth terminal to load point (UPS DB and Main DB etc)	85	Mtr.		
c.	G. I. Strip 25 x 3 sqmm Strip from Electrode to wall.	10	Mtr.		
8	UPS POINT				
a	Supply & Installation of point wiring for UPS points on workstations / table for computers using 2 x 2.5 + 1 x 1.0 Sq.mm copper conductor multi strand FR PVC sheathed flexible wire pulled through floor raceways/conduit and taken upto table top using PVC rigid or flexible conduits run with in metal partitions. Each point consisting of 2 nos of 10A , 3 pin sockets & 1No., 20A Switch with socket (Modular) on 8 Module Horizontal Plate, Blanking & Box. Wired together forming one point. The earth wire of green color only. (10 nos. from Branch UPS DB & 1 nos. from ATM UPS DB)	12	Nos.		
9	RAW POWER POINT				
	Supply & Installation of point wiring for Raw power plug points on workstations / table for computers using 2 X 2.5 + 1 x 1.0 Sq.mm copper conductor PVC sheathed flexible wire Each point consisting of 1 nos of 20A , 6 pin socket & 1 No., 20A Switch (Modular) on 3 module Plate and box, wired together forming one point. The earth wire of green color only.	12	Nos.		

Page 2 of 3

S.NO.	DESCRIPTION OF ITEM	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
10	Wiring for Circuit / Submain wiring along with earth wire with the following size of FR PVC Insulated copper conductor single core cable in surface/ recessed PVC Medium duty conduit:-				
a.	2 x 1.5 Sqmm + 1 x 1.0 Sqmm Earth wire	185	Mtr.		
b.	2 x 2.5 Sqmm + 1 x 1.0 Sqmm Earth wire	190	Mtr.		
c.	2 x 4.0 Sqmm + 1 x 1.5 Sqmm Earth wire	225	Mtr.		
d.	2 x 10.0 Sqmm + 1 x 4.0 Sqmm Earth wire	8	Mtr.		
11	LIGHT/FAN POINT				
	Supply & Installation of concealed point wiring using 600v grade 1.0 Sq.mm copper conductor PVC insulated wires (with proper R,Y,B color code) pulled through Medium gauge PVC conduits laid concealed over false ceiling including 2 Nos. 2.5 sqmm circuit wires from the relevant DB and also including 1.0 sqmm green color copper earth wire and switch plate, switches, etc. as approved by the Bank's Engineer/Architect.				
a.	Primary light points including the cost of 10 A modular switch	47	Nos.		
b.	Secondary light points looped from the primary point		Nos.		
c.	Ceiling Fan Point including the cost of 10A modular Switch along with 4/5 step electronic fan regulator.	2	Nos.		
d.	Wall Fan Point along with 10 Amp modular switch on Board and 10 amp socket on two module plate near wall fan.	21	Nos.		
e.	Exhaust Fan Point along with 10 AMP modular switch	6	Nos.		
f.	6/10A Switch with 5pin 10A socket in light & fan board	10	Nos.		
12	DATA CABLING & POINT				
a.	Supplying and laying D-link make CAT-6 Cable complete with CAT-6 information outlet with plate & surface Box at individual Tables	13	Nos.		



b.	Supplying and fixing of 2 mtr long factory crimped patch cord	13	Nos.		
c.	Supplying and fixing of 1 Mtr long factory crimped patch cord	13	No.		
d.	jack Panel 24 ports with installation	1	No.		
e.	24 Port D-Link Switch with installation	1	No.		
f.	SITC of 9U rack with fan, tray, cable manager, Power strip and other fixing accessories.	1	No.		
13	VOICE NETWORKING				
(i)	1 No. RJ11 Telephone socket with plate and box incudes two pair telephone wire from connecting point.	1	No.		
14	FIXTURES				
a.	Supply and Installation of Square light fitting (2' x 2') LED Make : Philips / Wipro/Crompton greaves.	26	Nos.		
b.	Tube Light(LED) - Patti Type. (18 watts)Make : Philips	6	No.		
c.	Down Lighter 1x15W LED Panel white Make : Philips	14	Nos.		
d.	400mm Wall Mounted Fan Make : Orient/ Bajaj/ Crompton	16	Nos.		
e.	1200mm Ceiling Fan Make : Orient/ Bajaj/ Crompton		Nos.		
f.	Exhaust Fan (9") Metal Body Make : Orient/ Bajaj/ Crompton	2	Nos.		
g.	Call Bell Wireless.	1	No.		
h	1x 7 W LED Bulb with holder	6	No.		
i	Providing & Fixing Air Conditioner Capacity 1.5Ton, Split Type With Staplizar.	2	Nos.		
j	Proving & Fixing Extra Copper Pipe for Air Conditioners.	45	Mtr.		
	TOTAL (Rs.)				
Note:-	1-Please Quote Item Rates Seperatly In words & figures.				

2-Please Quote GST Seperatly on total cost.

3-This tender document is inclusive of all taxes, transportation & etc., only GST will be paid seperatly.



Zonal Manager
UCO Bank
Zonal office Meerut

Tender Document for Furnishing & Electrical Work of ATM premisses of UCO BANK at Civil Lines Bareilly is as under :-

S.NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(A) <u>FURNISHING WORK:-</u>					
1	P & F Suspended 12mm thick Armstrong board ceiling	35	Sq.ft		
2	P & F Aluminium glazed door with 16 gauge thick with 12mm clear poat float glass, aluminium members to be powder coated.	48	Sq.ft		
3	Door Handle of Die casted aluminium	1	Set		
4	Wall Panelling with ACP as Per approved color & designe fixed with (50x25) mm. 2mm thick aluminium tube in plum including joingitn tape with ALUBOND/GURING to external/internal wall surface and soffit below signage board.	184	Sq.ft		
5	Floor Spring	1	Nos		
6	<u>VITRIFIED TILES FLOORING</u> Providing & Fixing flooring with Vitrified Tiles [Color should be Ivory Shade] joint free of minimum 9mm thickness, size 24" x 24", 4" skirting, all fixed in 1:5 cement mortar, complete with cutting and filling joint with white cement. Make of tiles johnson / Bell/ Euro/ Asian/ Nitco/ Naveen/ Somani. Shade as per Bank specified..	35	Sq.ft		
7	<u>SHUTTER BOXING :</u> Providing & Fixing in position Aluminium Composite Panel [ACP] with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.20 mm, 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used, Shades to be as per Bank's standard colours: with ACP Trap door.	48	Sq.ft		



(B) ELECTRICAL WORK :-

1	P & F mirror optical fixture of 2 x 2 dimension with 2 x 36 watt philios or crompton Greaves Make.	1	Nos
2	P & F of electrical wiring of Anchor / crabtree, Havell's or equivalent make.		
(a)	4- way D. B. For ATM with 1 Nos DP 40 AMP two pole & 1 Nos D.P.- 32 AMP two pole.	1	Nos
(b)	8 - way SPM D. B. with 1 MCB - 40 AMP 4 Pole, 1 MCB - 25 AMP 1 Pole, 1 MCB 10 AMP - 1 Pole & 1 MCB 20 AMP - 1 POLE	1	Nos
(c)	AC Point - with 4.00 Sqmm Circuit wire.	1	Nos
(d)	Power Point - 3 No. For Camra, 2 No. access Lock pillar, 2 N. for ATM, 2 No for Main & 1 No. extra with 2.50 Sqmm Circuit Wire.	8	Nos
(e)	Light Point.	7	Nos
(f)	Circuit wiring 2 x 1.5 + .75 sqmm pvc insulated standard copper conductor wires	65	Mt.
(g)	Wiring- Panel to DB 2x4.0 +1x1.50 Sqmm	35	Mt.
(h)	Sine Board Point.	1	Nos
3	P & F of 4 mm copper insulated wire form main D.B to ATM D.B and from UPS to ATM D.B	35	Rmt
4	Phillips Spot Light Fixture - FBS 100/118 [5" dia CFL reflectors]	3	Nos

5 CHEMICAL EARTHING :

Based on Earthing Electrode with inbuilt copper strip / GEL/ GAF based. Should have resistance < 1 Ohm and should be < 2V between neutral and earth. Suitable electrode be used as per the site requirements. Earth enhanced compound power [Gel] with hardener to be provided minimum 20Kg per site / Back Fill / Site Filled compound [BFC / BSC] - 100 Kg. The electrode should be minimum 60mm dia and 3 meter length or 80 mm dia and 2 meter length.

1 Nos



6 AIR CONDITIONS :

1.0T High Wall split ACs with EER [Energy Efficiency Ratio] Rating of atleast 3.30, cordless remote, with stabilizer, timer, coking and temoerature display system. Of vendors of repote, like Voltas, Blue Star, LG, IFB , Samsung, Hitachi, Daikin or equivalent, having a good service network across the country. Copper, drain pipe length not exceeding 10 Ft. [with complete installation].

0 Nos

7 Profiding & installing Exhaust Fan of 12" maks Havells/Usha/Baja

0 Nos

8 Providing & installing wall fan or Havells/Usha/Bajaj make (Type - Swing), all complete.

0 Nos

TOTAL Rs.

Note:-	1-Please Quote Item Rates Seperatly In Word & Figure.				
---------------	--	--	--	--	--

2-Please Quote GST Seperatly on total cost.

3-This tender document is inclusive of all taxes, transportation & etc., only GST will be paid seperatly.



**Zonal Manager
UCO Bank
Zonal Office Meerut**