

Detailed Estimate For Furnishing work in the Premises of UCO BANK Branch office at Goverdhan Chauraha mathura.  
Is as under :-

S.N	Description	Qty	Unit	Rate	Amount
[1]	<b>STANDARD RUNNING COUNTER :-</b>				
	Providing, fabricating and fixing at site and in position modern Clerical / Cashiers Counters as per enclosed detailed drawing consisting of 19mm thick <b>ARCHID / CENTURY / GREEN</b> or equivalent approved make commercial finished borer and termite resistant block board having 10 to 15" wide transacting top at 42" height and 30" wide writing / work top at 30" height from the finished floor level. The work top shall be supported by the drawer unit of standard size housing 4" to 5" deep drawers for clerical counter and 3 Nos. 3" deep drawer in Cash counters running on approved make Channels as directed by Bank, placed at every 3.6" to 4'-0" for <b>CLERICAL COUNTERS</b> and every 4'-0" for <b>CASH COUNTERS</b> or as per approved layout plan and consisting of 19mm thick commercial finished block board of above specified makes. The front side [ public side ] of the counters shall be consisting of 19mm block board of approved makes for entire and length of the counter. The transaction top, writing work top and front / public side face of the counter and front face of the drawer - cum - board unit shall be finished with <b>FUSION MAPLE / CHOCOLATE /</b> lamination as per sample approved by Bank. The work top shall be supported by the The public side of the counter shall be provided with 19mm thick laminated block board skirting 100mm height. The rate should include providing and fixing seasoned t.w. Boarding of finished size 19mm x 4mm or as required to all exposed edges of the block board Each cupboard / drawer shall be provided with approved quality 1 No. handles / knobs and 1 No. GODREJ or equivalent approved quality locks. All exposed and un - exposed faces of teak wood. BWP block board shall be polished / painted with 3 or more coats of approved quality and shade French polish / enamel paint to have desired finish .				
	The rate should also include providing and fixing 19mm thick approved quality block board support of required size at the starting and end of the counter / duly laminated with similar quality and shade lamination and also				





	closing the first and last counter and also providing and fixing 2.5" 1.5" seasoned wood foot rest or required length to each counter complete as per the layout plan and as directed by Bank's Engineer .				
	[a] Cash counters 1050mm ht. two tier	8.50	R. ft		
	[b] Clerical counters 750 ht counter	23.50	R. ft		
[2]	Supply & Fixing of 12mm glass with etching [ design as per Architect ] in wooden pillar with polish all complete .	Nil	-		
[3a]	<b>CASH CABIN PARTITION WITH DECOGRILLE FOR FLUSH / WOODEN PARTITION</b> Up to 7'-6" ht .				
	Providing and fixing DG - 202 anodised aluminium Deco grille in the middle portion of partition at 3'-6" above floor level in upper portion including ceiling . Top will be same. [ the height of the cash cabin partitions shall be normally 10'-0" unless otherwise specifically mentioned or instructed at site ] . The rate should include approved quality and shade enamel spray painting of aluminium Grille and making transaction window wherever necessary in approved pattern and design complete as directed .	176.75	Sq.ft		
[3b]	<b>D - tel Depository Cabinet</b>				
	Supply of side cash Almira - for Cash Cabinet made of Methdex / Godrej make as per approved design.	0	Nos		
[4]	<b>FLUSH DOOR SHUTTER WITH GLASS</b>				
	Providing and fixing 40mm thick solid core flush door shutters of ARCHID / CENTURY / GREEN or equivalent ISI make as per sample approved by the Bank finished with approved quality and shade 1.0 mm thick lamination on both side of the shutter with matching wood beading duly melamine polished .	56.00	Sq.ft		
	The rate should include the following :-				
[I]	Providing 8mm thick float glass of 3' to 4' height fixed at 3' above the floor level with suitable beadings .				
[II]	Providing 4" high skirting with 1.0mm sunmica lamination on both sides and TW lapping to edges .				
[III]	Applying anti - termite / bearer treatment / paint				





	to door shutter wherever directed .				
[IV]	Providing 4 Nos - 4" x 1.5" Brass Oxidised Hinges, anodised aluminium Handles, tower bolt, etc. As per samples approved and as per site requirements .				
[5]	<b>CASH CABIN CEILING WITH DECOGRILLE FOR FLUSH / WOODEN DOORS</b>				
	Do as above in tem no __ but provided DG 202 anodised Aluminium Deco grille in the Side & Back portion of the CABIN with suitable beading complete as directed . The rate should include applying approved quality and shade enamel spray painting of Aluminium Grille complete as directed . The remaining specifications will be same .	97.62	Sq.ft		
[6]	<b>TABLES :-</b>				
	Providing in position Officer's & Manager tables of sizes mentioned herein after. It shall consist of 19mm thick commercial block board of <b>ARCHID / CENTURY / GREEN</b> or equivalent approved make on the top finished with 1.00mm thick approved quality laminated as per sample approved and as per design / detail. The writing top shall be supported over two vertical supports made out of 19mm thick commercial board of above specified makes with lamination as above . The supports shall be connected together with 19mm thick commercial board duly laminated front as per approval and design / detail. The table shall be complete with drawers, shelves, necessary hardware, knobs, Godrej Locks etc. As per detailed drawing and samples approved. The rate to include applying 3 coats of melamine spray polising / painting etc., plastic shoes complete.				
[I]	Table of size 6'-0" x 3'-0" x 2'-6" height with table top and front to be in semi - circular shape as per detailed drawing with .	1	Nos		
[II]	Table of size 5'-0" x 2'-6" x 2'-6" ht. as per detailed drawing .	1	Nos		
[III]	Table of size 4'-6" x 2'-6" x 2'-6" ht. as per detailed drawing .	Nil	No		
[7]	<b>SIDE TABLES :-</b>				
	Providing and fixing in position side tables of sizes mentioned hereinafter. It shall consist of 19mm thick commercial board of ARCHID / CENTURY / GREEN of equivalent apprvied make in top, middle shelf, bottom and sides as per detailed deawing. The top and sides shall be				





	laminated with 1mm thick approved quality and shade laminate as per design detail.				
	The cabinet shall be covered from back with 6mm ply of LIBERTY / REGAL / REAL or equivalent approved make .				
	The rate should include for providing 19mm laminated block board shutters and necessary hardware, knobs sliding channels, Godrej locks etc. As per samples approved complete with applying 3 coats of melamine polishing / painting to un - laminated surface inside / outside, plastic shoes and also proving and fixing 19 x 4 mm suitable teak wood / inlay beading to all exposed edges to the block boards etc. As per Bank's approved .				
[a]	Side rack of size 2'-6" x 1'-6" x 2'-4" for B.M.	1	Nos		
[b]	Side rack of size 2'-6" x 1'-6" x 2'-4" for officers & B.M	1	Nos		
[c]	Side rack of size (5'-0") x + 1'-6" x 2'-4" Back side	12.50	R. ft		
[d]	Side Rack of Size 11'-9" x 1'-6" x 7'-0" ht	29.37	Sqft		
[8]	<b>SOFA SET :-</b> Providing and fixing Sofa made out of 19mm thick ARCHID / CENTURY / GREEN Block board 2"x2" sea-soned wood frame. The seat shall have flat tensile spring, hesian base and 4" pin whole ISI grade rubber foam pin - whole - cushions of prestige or equivalent approved make with 1" - 37 densiry foam . The back shall have 3" - 37 density U - foam. Sofa shall be upho - lstered with tapestry upto Rs. 150/- per mt. As per sample and colour / shade approved by the Bank's authorities , Three Seater Two Seater	Nil Nil	- -		
[9]	<b>FALSE CEILING :- EXCLUDING TOILET, RECORD. At 9'-0" ht</b>				
[a]	<b>Gypsum Board</b> Providing and Fixing at all height False ceiling of straight edge 12.5 mm Gyp board, including providing and Fixing of frame work made of special sections power pressed from M.S.Sheets and galvanised in accordance with zinc coating 600 as per IS :277 and consisting of angle cleats of size 25mm wide x 1.6 mm thick with flanges of 22 mm and 37mm at 1200 mm centre to centre one flange fixed to the ceiling with dash fastner 12.5 mm dia x 40 mm long with 6mm dia bolts to the angle hangers of 25x25x5mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. Channels 45x15x0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick bottom edge of 80 mm with tapered flanges of 25 mm each having clips of 10.5mm at 450 mm centre to centre shall				





	be fixed in a direction as per manufacturer's specification.				
	Item including complete works including cutting cutouts for light fixtures and HVAC equipments as required .				
	[ All the gapes vertical or horizontal has to be concealed. only horizontal surface area will be measured. ] approved make for Gyp board and	504.00	Sq. ft		
b	<b>Modular False ceiling</b> - Armstrong / equivalent make at 10'-0" ht Providing and Fixing Armstrong [ Fine Fissured Micro Lock with Tagular Edge using 15mm Grid sections ] false ceiling of size 24"x24" at levels as shown in the drwg. From FFL Rate shall be inclusive of providing the total system with installation etc. The contractor has to maintain all tiles in good order and replace the defected tiles [ at his own cost ] before handing over the site for Branch operations [ Till Inauguration]	608.0	Sq. Ft.		
[10]	<b>GODREJ NIGHT LATECH LOCK :-</b>				
	Providing and fixing 6 liver Godrej night latch lock with non - inter changeable keys to doors of cash Cabin .	2	Nos		
[11]	<b>MORTISE LOCK :-</b>				
	Providing and fixing in position DOORSET 6 liver cylindrical lock silver / brass finish as approved by the Bank .	7	Nos		
[12]	<b>12MM GLASS IN FRONT OF CASH CTO COUNTERS &amp; manager &amp; Office Table Top :-</b>				
	Do as above in item No. 3 But also providing and fixing Aluminium grille DG - 202 DECOGRILL in addition to 12mm glass as per sample approved by Bank. The rate should also include cutting 7" x 3.5" Transaction window as per drawing, machine polishing of glasse edges, providing suitable sliding shutter arrangement to the Transaction window and applying approved Grille complete as directed. The remaining specifications will be same .	107.75	Sq. ft		
[13]	<b>VOUCHER WRITING TABLE :-</b>				
	Providing and fixing Voucher table with about 5 voucher slots / pockets as per the detail drawing consisting of 19mm block board of ARCHID / CENTURY / GREEN or equivalent approved makes duly laminated using 1.0mm laminate of GREEN / CENTURY / ARCHID TOUCH or equivalent approved by the Bank having slanting top and waste paper box with dumping and cleaning window in the lower supporting column including polishing / enamel painting etc. Complete .	1	Nos		





[14]	<b>VOUCHER SORTING BOX :-</b>				
	Providing and Fixing voucher sorting box as per the detail design consisting of 19mm block ARCHID / CENTURY / GREEN or equivalent approved makes with matching colour and quality lamination polishing etc. Complete .	1	Nos		
[15]	<b>COLUMN PANELLING with Lamination only .</b>				
	Providing and fixing 19mm thick commercial finished block board of ARCHID / CENTURY / GREEN or equivalent approved make in panelling of columns / walls fixed in perfect right angle or as directed and then providing and fixing 1.00mm thick approved quality and shade lamination as per approved pattern and design including proving moulded beading . The rate should include applying polishing etc. Complete .	0.00	Sq. ft		
[16]	<b>WALL PANELLING MANAGER &amp; CASH. :-</b>				
	Providing and fixing wall panelling consisting of made out Alluminum frame 2" -1" work made out of 2' x 1" sections placed at 15 to 18" centre to centre firmly fixed to wall covered with 12mm BWP particle board of ARCHID / CENTURY / GREEN finished with 1.0mm thick approved quality and shade lamination in approved pattern and design including, polishing etc.	215.62	Sq. ft		
[17]	<b>PROVIDING 3 SEATER BENCH :-</b>				
	Supplying 3 Seater Chair Bench of 18 Gauge jali sheet & 1" dia pipe methdex / Godrej or approved quality as per approved design and app color methodex / Godrej Mark .	Nil	Nos		
[18]	<b>WOODEN GLASSED &amp; PANELLED</b>				
	<b>PARTITIONS [ FLUSH TYPE ] with alluminium frame work .</b>				
	Providing and fixing partitions made out of 2"-1" Alluminum frame @ 2' c/c vertically with 8mm exterior grade MDF or 9/12 mm BWP particle board of ARCHID GREEN / CENTURY with 1.50mm approved quality and shade lamination with Teak wood moulded beading on both side duly melamine polished . The partition will be provided with 8mm thick float glass of 4' height fixed at 3' above the floor level in average 3' wide panels.				





	The rate should also include providing 4" high skirting of 12mm BWP ply with 1mm formica lamination on both side including applying antitermite / boarer paint to wooden frame work wherever directed .	219.38	Sq. ft		
[19]	<b>LOW HEIGHT WOODEN PARTITIONS :-</b>				
	Providing and fixing in position low height wooden partition as per item no __ above upto no. 5 ft. Height but upper 10 / 12" portion of partition will have 8mm thick seasoned t.w. Section with polish complete as directed .	85.00	Sq. ft		
[20]	<b>WHITE WASHING :-</b>				
	applying 3 or more coats of DRY DISTEMPER of johnson and Nicholson" or British of Asian" make only to ceiling / walls etc. On existing service all complete .	Nil	-		
[21]	<b>PLANTER BOX :-</b>				
	Supply planter box consisting of 19mm commercial board 15" x 15" finished with teak ply / laminate from outside and 24 gauge aluminium sheet inside including polishing etc. All complete .	Nil	-		
[22]	<b>CPU PLATEFORM COMPATMENT :-</b>				
	Providing and fixing 2'-6" wide work top consisting of 19mm thick VENUS or equivalent approved make block board finished with approved quality and shade laminate of ARCHID / CENTURY / GREEN TOUCH or equivalent approved make with 19mm thick block supports at every 4' to 5' c/c. The rates should include providing 19 x 4mm teak wood moulded bearing as per sample approved to the exposed edges of the block board and polishing / painting of all un - alminated surface of block board etc with 3 or more coats of wax polish in approved shade complete as per detailed drawing and instructions of the Bank's Engineer . The rate should also include providing tower type CPU compartment, Key Board Drawers fixed on approved quality Channels, 1 No. drawer 4" deep and Electrical switch board plate complete at every 4' length of work top as per directed .	Nil	-		
[23]	<b>NOTICE BOARD :-</b>				









**Indicative Basic Material Specifications :**

PARTICULAR	MAKE OF MATERIAL
Plywood / Block / board	archid / century green ( 6 mm ,9mm , 12mm, 19 mm )
Laminates	Greenlam / Century / Archid ( 1.00 mm Thick )
soft board ( pin up board )	jolly board , stylex
Gyp boards	india gypsum / Armstrong / gyproc
Metal ceiling	Armstrong
Vertical Blinds	Vista , Universal , Maac
Screw	GKW / Mettle fold , Hindalco
SS Hinges	Godrej / Hardwyn
Hardware	Dorma , hardwyn , Godrej
Drawer shutter lock	Godrej , Link , Dorset
Ball Catch	Dorma , Hardwyn , Godrej
Door lock / Handles	Dorma / Hardwyn , Godrej
Venner	Archid / Century / Green
Adhesives	Fevicol , Mahacol , Jeevanjor
Wood Preservatives	Black Japan
Door Closure	Dorma / Hardwyn , Godrej
Glass	Modi / Asahi / Saint Gobain
Glass tinted	Same as above
Melamine polish	asian paint , nerolac , French Zinc Oxide
Paint	Burger , Nerolac , Asain









Detailed Estimate For Electrical Work in the Premises of UCO BANK Branch office at Goverdhan Chauraha Mathura.

Is as Under :-

S.N	Description	Oty	Unit	Rate	Amount
A	<b>ELECTRICAL SYSTEM :-</b>				
1	Supply & Installation of 63A, 4-pole , MCB , for Drwaing incoming power supply from the source.	1	Nos		
2	Supply & istallation of 63 A, DP, MCB	3	Nos		
3	Supply & Istallation of 8 way Lighting & power D.B. consumer unit, 1 No. 63 A, DP incoming MCB 4 Nos, 6A & Nos. 20 A SP, MCB.	1	Nos		
4	Supply & Istallation of 12 way computer D.B. consumer unit, 1 No. 63 A, DP incoming MCB 10 Nos, 6A , SP, MCB .	1	Nos		
5	Point wiring with 3x1.5 Sqmm PVC insulated single core copper flexible wire including circuit wiring with 2x2.5 Sqmm and 1x1.5 Sqmm PVC insulated copper flexible wire in PVC conduit / casing for Light / Fan / Exhaust Fan / 6A raw power plug / Call Bell / Sign Board points [ Av. Run - 6 Mts ] with sheet & mica .	75	Nos		
6	Point wiring as described in Item SI No. 5 but in 20mm MS conduit for strong room ].	5	Nos		
7	Point wiring with 3 x 1.5 Sqmm PVC insulated single core copper flexible wire in PVC conduit casing for computer point [Av. Run - 8 Mts ] .	10	Nos		
8	Point wiring with 2x2.5 Sqmm and 1x1.5 Sqmm PVC insulated single core copper wire in PVC conduit / Casing for power / Room A. C. Point [ Av. Run - 10 Mtrs ] .	17	Nos		
8A	Supply & Fixing 1 x 6A, 5 Pin Modular sockets & Switches for raw power .	5	Nos		
9	Suppling & Fixing Computer switch board with modular type 4x6A, 5 Pin socket outlet and 1x16A switch .	10	Nos		
10	Suppling & Fixing power switch board with modular type 1x16A, 6 Pin Socket outlet and 1x16A Switch .	17	Nos		
11	Suppling & Fixing 2' x 2' LED Fitting With Crompton Philips / Bajaj Make	16	Nos		
12	Supplying & Fixing 1 x 36 W mounting rail flouorescent fixture with 1 No. 36 W flouorescent lamp.	10	Nos		





13	Suppling & Fixing LED Down Light Fitting With Phillips or Crompton / Bajaj Make	27	Nos		
14	Supplying & Fixing 1200 mm sweep double ball bearing ceiling fan .	1	Nos		
15	Supplying & Fixing 300 mm sweep Exhaust Fan.	3	Nos		
16	S & F of 450mm wall fan .	17	Nos		
17	Supplying & Fixing 10A NO / NC conductor in M.S. Enclosure for auto OFF / ON control of power inside the Strong Room .	1	Nos		
18	Supplying & Fixing 7A to 12A DOL, Starter for ROOM AC .	1	Nos		
19	Supplying & Fixing Call Bell with bell puch .	1	Nos		
20	Wiring with 2x10 Sqmm and 1x4 Sqmm single core PVC insulated copper flexibie wire in PVC conduit / casing [ From 63A, DP, MCBs near the source of supply to Lighting - Cum - Power DB and comuter DB .	75.00	R.ft		
21	Loop wiring with 4x10 + 1x4 Sqmm single core PVC insulated copper flexible wire in PVC flexible conduit at source point .	25.00	Mt		
22	Loop wiring with 2x10 + 1x4 Sqmm single core PVC insulated copper flexible wire in PVC flexible conduit for UPS incoming & outgoing .	20.00	Mt		
23	Dedicated Earth station with 600mm x 600mm Copper Earth plate as per IS : 3043 .	2	Nos		
24	Earth Bus near the UPS .	1	Nos		
25	Earth wire with 2 x 8 SWG, GI wire in M S pipe .	65.00	Mt		
				Total [A] Rs.	
<b>B</b>	<b><u>FIRE ALARM AND DETETION SYSTEM :</u></b>				
1	Supply & Installation of 2 - Zone Fire Alarm Control Panel with 12V maintenance free battery & Charger & mounting base .	1	Nos		
2	Cabling with 2x1.5 Sqmm PVC insulated copper wire in PVC conduit .	150.00	Mt		
3	Supply & Fixing of optical intelligent type smoke dector with base .	6	Nos		





4	Suppling & Fixing of Manual call point in sheet steel box with hammer and chain .	1	Nos		
5	Supply & Fixing of Response indicator .	5	Nos		
6	Supply & Installation of fisher cum electronic hooter [ Dual type ] .	1	Nos		
7	Supplying & Fixing of emergency exit sign board of approved size with photo - lminescent tapes .	2	Nos		
				<b>Total [B] Rs.</b>	
<b>C</b>	<b>DATA CABLING :-</b>				
1	Suppling & laying of 25mm dia PVC conduit	150.00	Mt		
2	Suppling & laying of CAT - 6e UTP cable .	220.00	Mt		
3	Providing CAT - 6 mounting cord [ 1mt ] - Factory crimped .	10	Nos		
4	Supplying & Fixing of CAT - 6, I/O + SMB [ Single port ] .	10	Nos		
				<b>Total [C] Rs.</b>	
	Total = A+B+ C				
	Add. 18% for Gst	-	-		Rs.
	<b>Total = A + B + C</b>	<b>=</b>	<b>-</b>	<b>-</b>	

Detailed Estimate For A.C. Work in the premisses of **Uco Bank** Branch office at Goverdhan Chauraha Mathura Is as Under :-

S.No	Description	Oty	Unit	Rate	Amount
1	Branch area, excluding for Strong Room & Recod 742.00 Sq Ft. 120 Sq ft / ton we need = $\frac{742.00}{6.18} = 120$				
1	1.50 TR Split AC in Hall with stablizer	4	No.		
2	1.00 TR Split AC in manager & Atm with stablizer ( to be used old )	2	No.		
3	M.S. stand - [ In door & out door units ]	6	No		
4	Installation Charges for Split AC.	6	No		





5	Extra cost for Copper pipe / cable over .	120	Rmt		
6	PVC drain pipe .	75	Rmt		
				Rs.	
	Add. 24.48% for Gst .	-	-	Rs.	
				<b>Total Rs.</b>	

NOTE:- AC unit shall be used at site of carrier, Voltas

[ Three Star Rated ]

Detailed Estimate for Furnishing Electrical & AC Work of A T M premisses of UCO Bank At Goverdhan Chauraha Mathura is As under.

S.No	Description	Qty	Unit	Rate	Amount
[A]	<b><u>FURNISHING WORK :-</u></b>				
1	P & F Suspended 12mm thick Armstrong board ceiling	12	Sq.ft		
2	P & Fixing of Gypsum Board Ceiling	58	Sq.ft		
3	P & F Aluminium glazed door with 16 gauge thick with 12mm clear poat float glass, aluminium members to be powder coated .	24.50	Sq.ft		
4	P & F in position 8mm modi float clear glass with aluminium 16 gauge pipe with clip section. The aluminium section to be powder coated. [ Fixed ]	16.00	Sq.ft		
5	<b><u>Door Handle of Die casted aluminium - 18" Long .</u></b>	1.00	Set.		
6	ACP Partition Material Alluminium frame 1" x 1.5" with ACP Frame on Both side .	Nil	Sq.ft		





7	PANELLING				
	Providing & Fixing in position Aluminium Composite Panel [ACP] with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.20 mm., 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used. Shades to be as per Bank's standard colours: with ACP Trap door.	252.00	Sq.ft		
8	Floor Spring.	1.00	Nos		
9	VITRIFIED TILES FLOORING				
	Providing & Fixing flooring with Vitrified Tiles [Color should be Ivory Shade] joint free of minimum 9mm thickness, size 24" x 24", 4" skirting, all fixed in 1:5 cement mortar, complete with cutting and filling joint with white cement. Make of tiles johnson / Bell / Euro / Asian / Nitco / Naveen / Somani. Shade as per Bank specified.	0.00	sq.ft		
10	Providing & Fixing of 19mm thick Granite slab [in Black colour] on steps & platforms.	0.00	sqft		
11	Poster frame wall hung :				
	Two sheets of size 24"x 36" clear acrylic [poster to be sandwiched in between] outer sheet in 5mm thick and beveled crystal edge polished for 1/4" at 8 - 10 degree on all side in the front Rear sheet is 5mm thick Flat.	2	No		
12	Cheque drop Box .-18"x12"ht x 9" deep	1	No		
13	Waste Paper Box [Dustbin].	1.00	No		
14	Writing ledge made wooden of Size 3'-0" x 1'-0"	1.00	Nos		
15	SHUTTER BOXING :				
	Providing & Fixing in position Aluminium Composite Panel [ACP] with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3mm minimum. Aluminium foil thickness to be min 0.20 mm., 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used. Shades to be as per Bank's standard colours: with ACP Trap door.	137.00	Sq.ft		
16	ATM EMBEDDING ON THE GROUND :				





















