

निविदा सूचना / TENDER NOTICE

विनिर्दिष्ट के अनुसार वस्तुओं के दर हेतु मुहरबन्द निविदायें आमंत्रित हैं/ Sealed items rate tenders are invited for the works noted hereunder:

| अ.क्र./S.N. | कार्य का विवरण Name of work | कार्य- स्थल/Location of work | अनुमानित लागत/Estimated cost |
|-------------|---|---|------------------------------|
| 1. | शाखा मदनपुरा , जनपद वाराणसी में आंतरिक साज-सज्जा का कार्य/ Interior & furniture work at MADANPURA Branch Dist: VARANASI | शाखा मदनपुरा , जनपद वाराणसी / MADANPURA Branch Dist: VARANASI | Rs8,07,250/- |
| 2. | शाखा मदनपुरा , जनपद वाराणसी में विद्युत् कार्य/Electrical work at MADANPURA Branch Dist: VARANASI | शाखा मदनपुरा , जनपद वाराणसी / MADANPURA Branch Dist: VARANASI | Rs.3,54,850/- |

निबन्धक एवं शर्तें/Terms and conditions:

- कार्य की पूर्ति हेतु समय : 30 दिन / Time of completion of work : 30days.
- अर्नेस्ट मनी डिपोजिट: निविदा जमा करने के समय पे आईर/डी.डी./बैंकर्स चेक के रूप में अनुमानित लागत का 1% Earnest money deposit : 1% of estimated value at the time of submission of tender in the form of Pay order/ DD/Banker's cheque.
- आरम्भिक अभिरक्षा जमाराशि : सफल बोली लगाने वाले की अर्नेस्ट डिपोजिट मनी को शामिल करते हुये अनुबन्ध राशि का 2% / Initial security deposit : 2% of the contract value including the EMD by successful bidder.
- सफल बोली लगाने वाले के द्वारा जमा अर्नेस्ट मनी डिपोजिट एवं आरम्भिक अभिरक्षा जमा राशि, अनुबन्ध की अभिरक्षा राशि व रिटेंसन मनी के एवज में समायोजित कर ली जायेगी / The EMD and ISD so deposited by the successful bidder, will be adjusted with the security deposit/ retention money for the contract.
- क्षतिपूर्ति वहन अवधि : कार्य के वास्तविक समापन से छ माह की अवधि तक / Defects liability period : 6 months from date of virtual completion of work.
- निविदा के जमा करने का अंतिम समय एवं तिथि : **01-06-2015** को अपरान्ह **2.00 बजे** / Time and last date of submission of tenders : **2.00 PM on 01-06-2015**
- निविदा खोलने का अंतिम समय एवं तिथि : **08-06-2015** अपरान्ह **4.00 बजे** / Time and last date of opening the tenders : **4.00PM on 08-06-2015**
- जमा करने का स्थान : यूको बैंक , अंचल कार्यालय, डी-63/8-1-एम ,महमूरगंज, वाराणसी / Place of submission : **Uco Bank , Zonal Office D-63/8-1-M, Mahmoorganj Varanasi**
- बिना कोई कारण बताये किसी व सभी निविदाओं को स्थगित करने व निरस्त करने का अपना अधिकार बैंक के पास सुरक्षित है । सभी निविदाये, जिसमें निर्दिष्ट कोई शर्त पूरी नहीं है या किसी भी रूप में अपूर्ण है, निरस्त की जा सकती हैं / Bank reserves its right to postpone / reject any or all the tenders without assigning any reason what so ever. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- 10-सेवा कर नियमानुसार लागू होगा Service tax applicable as per norms.**
- 11-Only empanelled contractors can submit tenders.**

अंचल प्रबन्धक/Zonal Manager

Material Specification for Electrical Work

| | |
|-----------------------|-------------------------------------|
| Tube Light | Phillips /GE |
| Switches | : MK wrapround / Legrand (Mosaic) |
| Wire/Cable | : /Anchor/Finolex/National / CCI |
| Fan | :Crompton Greaves (high Breeze) |
| Exhaust Fan | : Almorand/Khaitan |
| M. C. B. / D. B./MCCB | : MDS/Schneider/Siemens |
| Main Switch | : /GE/L&T |
| Change Over | : GE/L&T/ABB |
| PVC Conduit | : AKG/ Sieko |

Schedule of Quantities for Electrical work of Madanpura Branch Of UCO Bank Varanasi

| Sl No. | Description Of work | Unit | Qty | Rate Rs/per | Amount Rs-----P |
|--------|---|------|-----|-------------|-----------------|
| 1. | S/F of plug socket board consisting of 3 plug 5 Amp, three pin, three switch and one indicator with 1.5 sq mm separate circuit wiring for computer. | Each | 12 | | |
| 2. | Supplying and executing earthing work for computer with 450x450x6mm copper plate and 8 SWG copper wire provision to be made for CI cover manhole with locking device and 20mm of watering pipe with tunnel. Two plate to be buried with its top edge at a depth of atlas 2500mm from ground level with 15cm. Thick packing of characoal powder and salt as per ISI recommendation. | Job | 1 | | |
| 3. | Supply of Recessed mounting fitting suitable for 36 Watt LED 600X600MM square Fitting with PDC aluminium diecast housing with Polycarbonate diffuser in buit electrical protection like over voltage, short circuit , over loading , miswiring for additional safety protection 5600/6500K , Rated life 50000hrs Make : GE Model No. MAPPLE Cat. No. GCR036.56M1 or equivalent Philips Make | Each | 7 | | |
| 4. | S/W 10Amp. Plug point with 2.5 sq mm copper wire in counter with continuous earthing wire complete in all respect with modular switches /socket. | Each | 16 | | |
| 5. | S/F of light point (miscellaneous) in 1.5 sq mm wiring complete in all respect including Tube light and modular switches . | Each | 2 | | |
| 6. | S/F of 20 Amp plug point with 2.5 sq mm wiring including modular switches/socket with continuous circuit wiring. | Each | 8 | | |

| Sl No. | Description Of work | Unit | Qty | Rate Rs/per | Amount Rs-----P |
|--------|--|------|-----|-------------|-----------------|
| 7. | Supplying & Executing earthing work for AC/ light and fan with 450x450x6mm copper plate and 8 SWG copper wire, provision to be made for CI cover manhole with locking device and 20mm watering pipe with tunnel other specification to same as that for computer earthing. | job | 1 | | |
| 8. | Supplying and wiring for Telephone point with twisted annealed, copper conductor PVC insulated and PVC sheathed telephone wire with socket in 14 SWG with all the accessories in concealed manner with 2-pin socket in suitable size of MS box. | Each | 2 | | |
| 9. | S/F of TPNDB 12 way with MCB 32/10 Amp. 12 nos. as 63 Amp DP RCCCB 100 MA with double door IP-43 . | Each | 2 | | |
| 10. | Fixing of existing ceiling fans after cleaning and greasing in rooms with adding rod of suitable length wherever necessary including 1.5 sq mm wiring and modular switches and regulator (Power saver fans 50 Wt) | Each | 5 | | |
| 11. | Supplying and Fixing of exhaust fan in hall/ toilet 15” dia with 1.5 sq mm wiring and modular switches.(if not in the branch) | Each | 2 | | |
| 12. | Providing & Fixing of wall mounted fans (400dia) complete with 1.5 sq mm wiring and modular switches .The work to include making hole in wall and partition.(MIDEA BW -04 of Bajaj or equiv) | Each | 12 | | |
| 13. | Supplying and fixing of Call Bell in BM’s cabin including wiring etc. | Each | 1 | | |

| Sl No. | Description Of work | Unit | Qty | Rate Rs/per | Amount Rs-----P |
|--------|--|------|-----|-------------|-----------------|
| 14. | Supplying and Fixing of cabin fans (400Dia) in cash cabin/sorting cabin in 1.5 sq mm wiring and modular switches. | Each | 2 | | |
| 15. | Supplying and Fixing of circuit wiring for computer in 2.5 sq mm copper wire. | Each | 12 | | |
| 16. | Circuit wiring for lights and fans 1.5 sq mm copper wire complete in all respect. | Each | 9 | | |
| 17. | S/F of A.C. point wiring with 6 sq mm copper wire and metal socket MCB 20 Amp. complete For 1.5/2 Ton A.C. | Each | 6 | | |
| 18. | Supply of Recessed mounting LED Down Light Fitting suitable for 24 Watt with powder coated pressure diacast aluminium housing buit electrical protection like over voltage, short circuit , over loading , miswiring for additional safety protection 5600/6500K , Rated life 50000hrs Make GE Model No. GDR024.SQ.56S0 or equivalent Philips Make | Each | 24 | | |
| 19. | Supplying and fixing of 2+12 way SPN Distribution Board double Door with 12 nos SP MCB and 1 no DPRCCB 40 amp for computer . | Each | 1 | | |
| 20. | S & F of 4 way SPN DB with 2 No 32/40 amp double pole MCB 10 KA in sheet steel enclosure double door | Each | 2 | | |
| 21. | Sub main wiring of UPS input and UPS output power supply with 2 no 6 sq mm + 1 No. 4 sq mm copper flexible wire in PVC conduit pipe .(payment as/actual length on site) | Mtr | 30 | | |
| 22. | Sub main Wiring of power supply from Main to TPN distribution Board with 4 nos 10 sq mm copper flexible wire in PVC conduit pipe . (payment as/actual length on site) | Mtr | 30 | | |

| Sl No. | Description Of work | Unit | Qty | Rate Rs/per | Amount Rs-----P |
|--------|---|------|------|-------------|-----------------|
| 23. | Supplying / Fabricating / installation of Panel Board made of 16 gauge CRC sheet 415 V Incoming: -TPN MCCB 250 Amp _____ 1 36 KA (4 pole) - 100 Amp MCB 10 KA _____ 3 No - 63 Amp DP MCB _____ 2 N0 -32 Amp SP MCB _____ 6 no -250 Amp Change Over _____ 1 No - 32 Amp Change Over _____ 1 No With Double Bus Bar Chamber | Job | 1 | | |
| 24. | Supply and fixing of Main line Alluminum cable work from pole to DB in hall with 50sq mm x 3 ½ core cable with wiring. (Length to be as/site condition) To be provided if not in the branch. | Mtr | 70 | | |
| 25. | Supplying and fixing on board 3 no KIT KAT cut out 200 amp with neutral link on board | Job | 1 | | |
| 26. | S/f of 32 Amp Change over for UPS chargin.(If already available then only fixing at suitable place) | no | 1 No | | |
| . | | | | | |

TOTAL : Rs -----

MATERIAL SPECIFICATIONS FOR FURNISHING WORK OF BRANCH

| | | |
|--------------------|---|------------------------------------|
| Board/Ply | : | Green, Century, Duro |
| Prelaminated Board | : | Novopan, KITLAM |
| Laminate | : | Formica or Greelam , Century |
| Aluminium Section | : | Hindalco /JINDAL |
| Door Closure | : | Hyper, Ritz, Everite (ISI marked) |
| Glass | : | Modiguard, Saint Gobain |
| Adhesive | : | Pidilite (Fevicol) |
| Locks/Night Latch | : | Godrej |
| Paint | : | Asian Paint,Nerolac |
| Floor Spring | : | Hyper, Ritz, Everite (ISI marked) |
| Vertical Blinds | : | Vista |
| Flooring | : | Kajaria |

Schedule of Quantities for furnishing work of Madanpura Branch of UCO Bank
Zonal Office Varanasi

| No. | Particulars | Qty./Uni | Rate | | Amount | |
|-----|---|------------|------|----|--------|----|
| | | | Rs. | P. | Rs. | P. |
| 1. | P/F Full Height (8' -6" High) partly glazed Laminated partition for BM's cabin . The under framing shall be of 2"x2" mirindi Wood (anti termite treatment) for under framing at a max .distance of 2' in each direction . 6 mm th waterproof ply shall be fixed on two sides and 1 mm th laminate shall be pasted over it with chemical adhesive with skirting. 6 mm th plain glass in the middle 4' height shall be fixed. | 90 sq ft | | | | |
| 2. | Providing and fixing False ceiling in step as/design 12.5 mm th. Gypboard including taking out existing false ceiling . The board shall be screwed to metal component (Gypsum India) suspended from the ceiling. Finish shall be smooth seamless etc.. The work to include cutting for electrical fittings . | 1300 sq ft | | | | |
| 3. | Providing POP cornice 3" on the junction of wall and ceiling as/design to the satisfaction of the architect . | 300 rft | | | | |
| 4. | Providing and laying vitrified tiles of (approx.) 600mmx600mm size (Naveen Johnson or similar approved equivalent) (Shade –Parleto)shade to floor at all levels and heights fixed to the existing floor with chemical adhesive " Fevimate " of Pidilite or similar approved adhesive of adequate thickness to suite required level including preparing the existing surface as necessary with supply of requite materials all complete as per direction. | 1300 sq ft | | | | |

| No. | Particulars | Qty./Unit | Rate Rs. P. | Amount Rs. P. |
|-----------|---|-----------|----------------|------------------|
| <u>5.</u> | Providing and Placing in position Officer's table (size 5'-0"x2'-6") in continuation to the low height counter made out of 19 mm thick water proof board with 1.0mm th. laminate on all exposed surfaces (other external surfaces shall be painted with two coats of enamel paint over one coat of primer). It shall have one drawer unit on one side while Provision to be made for pull out tray on slides. The table to be finished in TW/HW lipping and Godrej lock, handles footrest, latches all complete. | 1 no | | |
| <u>6.</u> | Providing and erecting on site wooden cash counter. Height shall be 3'-10". The height of writing desk for the cashier shall be 2'-6". The counter top for the clients shall be 1'-0" deep and that of Cashier Desk shall be 2'-6" deep. Both these top shall be made out of block board (Water Proof) 19mm thick with 1.0mm thick laminate (as/shade approved by the Architect) on the cashier's top. The inside desk shall be provided with 16" wide 16" high and 21" deep .Drawers shall have lock of approved make. All the exposed edges of block board shall be provided with 6mm thick teak wood lipping dully polished all complete with footrest. The inside shall be enamel painted 2 coats over primer | 12 rft | | |
| <u>7.</u> | Finishing existing doors of the branch with pasting 1 mm th laminate after fixing 4 mm th commercial ply on one side ,other side to be enamel painted and changing new hardwares on the door size 7'x3'-6" complete in all respect | 3 no | | |

| No. | Particulars | Qty./Uni | Rate Rs. P. | Amount Rs. P. |
|-----|---|----------|----------------|------------------|
| 8 . | Providing and erecting on site wooden low height counter (as/design). Height of the counter shall be 3'-0" with lower level at 2'6" and upper level (customer top)at 3' ht. . The top and vertical surfaces shall be made of waterproof board 19 mm th. with. 1 mm th. laminate over it. Drawer unit shall be provided on one side while with space for CPU by its side. Pull out tray on slide shall be provided on each counter for keeping keyboard . All the exposed edges shall have 6 mm th. TW lipping duly polished . Inside surfaces shall be enamel painted two coats over primer coat . It shall have locks and handles etc.. Provision for wire management shall be made | 16 rft | | |
| 9. | Providing and Placing in position Officer 's table in continuation to the low height counter made out of 19 mm thick water proof board with 1.0mm th. laminate on all exposed surfaces (other external surfaces shall be painted with two coats of enamel paint over one coat of primer). It shall have Two drawer units 2pull out tray on slides. The table to be finished in TW/HW lipping and Godrej lock, handles footrest, latches all complete. | 10 rft | | |
| 10. | Providing and Placing in position Branch Manger's table (size 6'-0"x2'-6") made out of 19 mm thick water proof board with 1.0mm th. laminate on all exposed surfaces (other external surfaces shall be painted with two coats of enamel paint over one coat of primer). It shall have one drawer unit on one side while Provision to be made for pull out tray on slides. The table to be finished in TW/HW lipping and Godrej lock, handles footrest, latches all complete. | 1 no. | | |
| | | | | |

| No. | Particulars | Qty./Uni | Rate Rs. P. | Amount Rs. P. |
|-----|---|------------|----------------|------------------|
| 11. | Pop punning on walls in banking hall making the surface smooth to the satisfaction of the architect after scratching and sand papering the existing surface | 2300 sq ft | | |
| 12. | Painting of wooden and steel items of doors and windows in baking hall with enamel paint (Two Coats) over primer coat with brush As/shade approved to the satisfaction of the Bank /Architect | 300 sq ft | | |
| 13. | Painting of walls and ceiling in baking hall with acrylic emulsion paint (Two Coats) over primer coat with roller finish As/shade approved to the satisfaction of the Bank /Architect | 4200 sq ft | | |
| 14 | Providing and Fixing Of anodized Aluminum Grill 2” dia .over Cash Cabin | nill | Nill | Nill |
| 15. | P&F 7 lever Night Latch lock for cash cabin.. (Godrej product code 9954) | 2 no. | | |
| 16. | P & F Hydraulic door closer of approved quality for doors. Godrej Product Code 4539 or equiv) | 7 no | | |
| 17. | Providing and fixing of,6’-0”High paneling on cash cabin wall/ columns in the hall . The under framing shall be of 50 mmx50 mm Mirindi Wood (anti termite treatment) for under framing at a max .distance of 2’ in each direction . 6 mm th waterproof ply shall be fixed on one side and 1 mm th laminate shall be pasted over it with chemical adhesive . Provision shall be made for passage of electric /data cables and switchboard . Bottom 4 “ width shall have skirting | 240 sq ft | | |

| No. | Particulars | Qty./Uni | Rate | | Amount | |
|------|---|----------|------|----|--------|----|
| | | | Rs. | P. | Rs. | P. |
| 18 . | P & F in position double leaf Anodized aluminum entrance door made of 2 mm thick sheet microns) . All member shall be of 100x45 mm section with 8 mm thick clear float glass including 4” dia.2 nos. handles 10” long 3 nos. tower bolts, floor spring 2 nos. locks etc. complete. | 95 sq ft | | | | |
| 19. | Providing and Placing in position 10 mm th Plain Glass on BM’ Table (size 6’x2’-6”)with size matching to the Table . The work to include Bevelled Edges complete to the satisfaction of the Bank | 15 sq ft | | | | |
| 20. | Providing and Placing in position side unit. Made with 19 mm th waterproof board for all members with 1mm th laminate over it on all exposed surfaces . Inner surface shall have enamel paint two coats over priming coat and putty . Sliding shutter shall be made out of 8.0mm thick water proof ply with 1.0mm thick teak wood/hard wood lipping, hinges handles, locks, latches, etc. all complete size shall be (3’-6”x1’-6”x2’-3”). | 2 no. | | | | |
| 21. | P&F 7 lever Mortice lock for BM’s cabin, Locker room and record room (Godrej Product Code 5412/5414) | 3 no | | | | |
| 22. | Providing and placing in position Printer unit of size 900x450mm x675 mm . The top and ,vertical sides./dividers ,skirting etc shall be made of 19 mm th water proof board . with 1mm th laminate as/shade approved . on all exposed surfaces . A slit of required dimension in the top shall be provided to allow the movement of printer paper . All ex[posed edges of water proof ply shall have teak wood lipping melamine polished complete to the satisfaction of the architect . | 1 no | | | | |

| No. | Particulars | Qty./Uni | Rate | | Amount | |
|-----|--|-----------|------|----|--------|----|
| | | | Rs. | P. | Rs. | P. |
| 23. | P & F complaint/suggestion box (1'6"x1'-6"x6") made out of 19mm th. Waterproof board with 1.0mm th. laminate on all exposed surfaces. Other internal surfaces shall be painted with two coats of enamel paint over one coat of primer. All exposed surfaces to be treated with T.W. lipping. | 1 no. | | | | |
| 24. | Etching work on glass with chemicals (as/design and profile) as/where required. The rates shall include cost of all materials ,labor ,T& P ,wastage ,transportation etc required for proper completion of the work . It shall be made out of following profile . Bank's Logo (300x300mm) and linear design | 160 sq ft | | | | |
| 25. | P/F in position floor mounted storage cabinets with drawers or hinged shutters having vertical divider at 450 mm to 600 mm aprox and horizontal shelves . It shall be made out of 19 mm th water proof board with 1mm th laminate as/shade approved) on all exposed surfaces . It shall have 6mm th water proof ply on the back .Every Cabinet shall have 150 mm deep drawers at the top and open able shutters below . The drawers and shutters shall have locks ,handles ,guides ,slides ,magnetic catchers etc | 45sq ft | | | | |

| No. | Particulars | Qty./Uni | Rate | | Amount | |
|-----|--|----------|------|----|--------|----|
| | | | Rs. | P. | Rs. | P. |
| 26. | Providing and fixing glass barrier in front of Low height counter (as/profile and design) 10 mm . th polished edged float glass (modiguard) .It shall have Laminated over commercial board support (as/shape approved by the architect)to hold the glass from sides and top (optional) . A. The rates shall include for cutting in geometrical shape and polishing the edges . all complete to the satisfaction of the architect.Height of the glass barrier to be 2'-0". | 30 sq ft | | | | |
| 27. | Providing and fixing of Low Ht (6'High)Partly glazed Laminated partition with doors in Single Window Counter . The under framing shall be of 2"x2" mirindi Wood (anti termite treatment) for under framing at a max .distance of 2' in each direction . 6 mm th waterproof ply shall be fixed on two sides and 1 mm th laminate shall be pasted over it with chemical adhesive . Provision shall be made for passage of electric /data cables and switchboard . T.W molding melamine polished shall be fixed wherever necessary. Bottom 4 " width shall have skirting . Lower 3' height shall be laminated while upper 2' part shall have 10 mm th plain glass. Provision of cut/hole in the glass shall be made wherever necessary . | 205sq ft | | | | |
| 28. | P&F of customer's desk made out of 19mm thick commercial Board with 1.0mm thick laminated of size 3'-0"x 2'-0" all complete with slip stocks. | 1 no | | | | |

| No. | Particulars | Qty./Uni | Rate Rs. P | Amount Rs. P. |
|-----|---|-----------|---------------|------------------|
| 29. | <p>Providing and fixing of, 8'-6" High Laminated partition . The under framing shall be of 50 mmx40mm mirindi Wood/ (with anti termite treatment) for under framing at a max .distance of 600 mm in each direction . 6 mm th waterproof ply shall be fixed on two sides and 1 mm th laminate shall be pasted over it with chemical adhesive . Door shall have 2 nos. handles 250mm long 2 nos. tower bolts etc. all complete. Provision shall be made for passage of electric /data cables and switchboard . T.W molding melamine polished shall be fixed wherever necessary. Bottom 4" width shall have skirting . The design shall have 6mm x 4 mm grooves (horizontal or vertical) at various level as suggested by the Architect. The rate shall include cost of all materials , labor , T& P , wastages, etc required for proper completion of the work . all complete to the satisfaction of the Architect.</p> <p>All door openings shall have rebated Teak wood frame work (size 75 mm x 50 mm) on vertical (2 nos.) and horizontal (1 No.) sides. With melamine finished and rebate of 40 mm x12 mm all complete . Door shutters shall have Teak wood edging on all four sides.</p> | 411 sq ft | | |
| 30. | <p>Wooden Partition (Low height)</p> <p>Providing and fixing of, 4'-6" High Laminated partition . The under framing shall be of 50 mmx40mm mirindi Wood (with anti termite treatment) for under framing at a max .distance of 600 mm in each direction . 6 mm th waterproof ply shall be fixed on two sides and 1 mm th laminate shall be pasted over it with chemical adhesive . Provision shall be made for passage of electric /data cables and switchboard . T.W molding melamine polished shall be fixed wherever necessary. Bottom 100 mm width shall have skirting . The rate shall include cost of all materials , labor , T& P , wastages, etc required for proper completion of the work . all complete to the satisfaction of the Architect. The top and side edges shall have 75 mm x 12 mm TW capping in melamine finish .</p> | 110 sq ft | | |

| No. | Particulars | Qty./Uni | Rate Rs. P | Amount Rs. P. |
|-----|---|-----------|---------------|------------------|
| 31. | P&F of Notice Board (size 3'-0"x2'-0") made out of 12mm thick Cellotex Board velvet cloth lining on it. It shall have 1 1/2"x1". Sal wood under framing, sides shall be of 19mm thick water proof Board with 1.0mm thick laminate(As per shade approved by Architect) Front shall have 4.0mm thick glass with sliding arrangement with locking device. All complete. | 1 no | | |
| 32. | Providing , fixing and testing of Vertical Blinds (Make Vista Levelor or equivalent) made out of 100 mm wide scotch guarded , fabric louvers(as/ shade and pattern approved by the Architect) . It shall also include for Head Rail , Control unit , Carriers , Tilter , Traverse cord , Tilt rod , Bottom Mechanism , installation Brackets etc all complete to the satisfaction of the architect . | 120 sq ft | | |
| 33. | Buy Back of existing counter , partition, after removing from the existing place (to be deducted) | 1 job | - 15000 | -15000-0 |

TOTAL : Rs. 807250=0